

Form 9180-6
(April 1965)
(formerly 4-679)

UNITED STATES
DEPARTMENT OF THE INTERIOR
BUREAU OF LAND MANAGEMENT

FIELD NOTES

OF A

DEPENDENT RESURVEY OF

A PORTION OF THE SUBDIVISIONAL LINES,

TOWNSHIP 5 NORTH, RANGE 28 EAST,

[Lined area for field notes]

Of the WILLAMETTE Meridian,

In the State of OREGON.

EXECUTED BY

Frank A. Tuers, Cadastral Surveyor

Under special instructions dated April 11, 19 75, which provided for the surveys included under Group Number 864, approved April 11, 1975, and assignment instructions dated April 14, 19 75.

Survey commenced April 14, 19 75

Survey completed September 12, 19 75

INDEX DIAGRAM

Township 5 North, Range 28 East,

6	5	4	3	2	1
7	8	9	10	11	12
18 4	17 1	16	15	14	13
19	20	21	22	23	24
30	29	28	27	26	25
31	32	33	34	35	36

Dependent Resurvey, Portion, Subdivisional Lines,
T. 5 N., R. 28 E., Willamette Mer., Oregon

CHAINS

Set a steel fence post, 5½ ft. long, 2 ft. in the ground, alongside the iron post.

This cor. is located in barbed wire fence, 4 strand, extending E. and W.

Asc. over NE. slope.

64.00 Spur, slopes N.; desc. over nearly level NW. slope.

79.64 Barbed wire fence, 4 strand, bears N. and S.

80.39 The cor. of secs. 13, 18, 19, and 24, on the W. bdy. of the Tp., reestablished by Donald L. Staebler, Registered Engineer No. 3402, Oregon, in 1972, by proportionate measurement, monumented with an iron post, 2½ ins. diam., firmly set, protruding 12 ins. above ground, and in a mound of stone, 2½ ft. base, 6 ins. high, with brass cap mkd.

	T 5 N		
R 27 E		R 28 E	
S 13		S 18	
S 24		S 19	
1972			

Add the marks BLM 1975 to brass cap.

From this point, a point locally accepted as the S. 1/16 sec. cor. of secs. 13 and 18, established by person(s) unknown, monumented with a concrete post, 6 x 6 ins., firmly set, protruding 1 in. above ground, with an iron pipe, 1¼ ins. diam., in center bears N. 0° 03' E., 19.91 chs. dist.

From this same point, the cor. of secs. 19, 24, 25, and 30 bears S. 0° 03' W., 79.65 chs. dist., reestablished by David H. Krumbein, Registered Engineer No. 7728, Oregon, in 1973, by proportionate measurement, monumented with an iron post, 2 ins. diam., firmly set, 6 ins. below gravel road, with brass cap mkd.

	T 5 N		
R 27 E		R 28 E	
	24	19	
	25	30	
R	RPE 7728		R

From the cor. of secs. 19, 24, 25, and 30, a point established by David H. Krumbein as the witness cor. to the cor. of secs. 19, 24, 25, and 30, monumented with an iron post, 2 ins. diam., firmly set, protruding 4 ins. above ground, bears N. 62° 34' E., 1.47 chs. dist., with brass cap mkd.

	WC		
	T 5 N		
R 27 E		R 28 E	
	2	19	
	2	30	
R	RPE 7728		R

GENERAL DESCRIPTION

The land included in this resurvey is situated south of the town of Umatilla, in Umatilla County, Oregon. There are numerous asphalt and gravel roads south of Umatilla. The greater portion of the area is hills. The elevation ranges from about 310 feet above sea level on

CERTIFICATE OF SURVEY

(I) (~~W~~), Frank A. Tuers, Cadastral Surveyor, HEREBY

CERTIFY upon honor that, in pursuance of special instructions bearing date of the 11th day of April, 1975, (I) (~~W~~) have dependently resurveyed a portion of the subdivisional lines of Township 5 North, Range 28 East,

of the Willamette Meridian, in the State of Oregon, which are represented in the foregoing field notes as having been executed by (me), (~~W~~) and under (my) (~~own~~) direction; and that said survey has been made in strict conformity with said special instructions, the Manual of Instructions for the Survey of the Public Lands of the United States, and in specific manner described in the foregoing field notes.

9/9/76
(Date)

Frank A. Tuers
(Cadastral Surveyor)

(Date)

(Cadastral Surveyor)

CERTIFICATE OF APPROVAL

BUREAU OF LAND MANAGEMENT
Washington, D.C.

The foregoing field notes of the dependent resurvey of a portion of the subdivisional lines of Township 5 North, Range 28 East, Willamette Meridian, Oregon,

executed by Frank A. Tuers, Cadastral Surveyor, having been critically examined and found correct, are hereby approved.

OCT 04 1977
(Date)

[Signature]
Acting (Chief, Division of Cadastral Survey)

CERTIFICATE OF TRANSCRIPT

I CERTIFY That the foregoing transcript of the field notes of the above-described surveys in T. 5 N., R. 28 E., Willam. Mer., Oregon, is a true copy of the original field notes.

(Date)

(Chief, Division of Cadastral Survey) GPO 849-626