



4-679.

FIELD NOTES

OF THE SURVEY OF THE

RESUBDIVISIONS

of

FARM UNITS

along the Oregon Railroad and Navigation Company's tracks in

Sections 3, 10, 15 and 22

of

T. 4 N., R. 28 E.,

(Umatilla Project, Oregon).

Of the WILLAMETTE Meridian,

Oregon

AS SURVEYED BY

W. Roy Saxton, Assistant Engineer, U.S.R.S., ~~United States Deputy Surveyor,~~

authority Departmental instructions

Under ~~his~~ Contract No. _____, dated October 24, _____, 1906

Survey commenced March _____, 1909

Survey completed March _____, 1909

NAMES AND DUTIES OF ASSISTANTS.

Blank lined area for recording names and duties of assistants.

UMATILLA PROJECT, OREGON.

Subdivision of farm units along Oregon Railroad and Navigation Company's track that are subject to or may become subject to homestead entry under the Reclamation Act through sections 3, 10, 15 and 22, Township 4 North, Range 28 East, Willamette Meridian.

Party:

- W. Roy Saxton, Assistant Engineer
- W. E. Barnore, Chainman
- George Patterson, "
- Ralph Phay, Flagman.

Surveyed during March 1909.

A Berger transit reading to 30" of arc and standard steel tape were used.

True bearings were taken from observations on Polaris.

T. 4 N., R. 28 E., Willamette Meridian

Ch.

Section 3

Found rock accepted as original corner of sections 3, 4, 9 and 10.

Found pile of rocks which old inhabitants say were placed to perpetuate original corner of sections 3 and 4 on First Standard Parallel North.

Found rocks and post placed to perpetuate original corner of sections 2 and 3 on First Standard Parallel North.

Found rock with scribe marks placed to perpetuate the corner of sections 2, 3, 10 and 11.

The positions of above corners were accepted as being the same as the positions of the original corners.

The SW and NW corners of section 3 being intervisible from a point between, I set a hub at this point and ran due North along the west boundary of section 3.

20.00 Set trial 1/16 corner on line.

40.00 Found rock set to perpetuate $\frac{1}{2}$ corner between sections 3 and 4.

83.48 NW cor. of sec. 3.

Above 1/16 cor. being in correct position, set 2 ins. x 4 ins. stake mkd. 1/16 on line as cor.

The NW cor. and the NE cor. of sec. 3 being intervisible from a point on line between, I set a hub at this point on line.

Ran

N. 89°38' W. on line bet. NW and NE cors. of sec. 3 from NE cor. along the N. Bdy. of sec. 3.

40.00 Set trial $\frac{1}{2}$ cor.

80.61 NW cor. of sec. 3.

Set 2x4 ins. stake on line as $\frac{1}{2}$ cor. 40.31 chs. from NE cor. of sec. 3.

STATE OF OREGON }
COUNTY OF UMATILLA } SS

I, W. Roy Saxton, Assistant Engineer, U. S. Reclamation Service, do hereby certify:

That the accompanying field notes of a survey of irregular tracts of land within the Umatilla Project, Oregon, which border upon and are contiguous to the Oregon Railroad and Navigation Company's right of way and railroad track, and which are or may become subject to homestead entry under the Reclamation Act as farm units of the Umatilla Project, are the result of an actual survey upon the ground.

IN WITNESS WHEREOF I have hereunto set my hand at Hermiston, Oregon, this 9th day of April, 1909.

W. ROY SAXTON,
Assistant Engineer.

Subscribed and sworn to before me this 11th day of May,
A. D., 1909.

(SEAL)

A. G. CRAWFORD,
United States Commissioner.

U.S. Reclamation Service,
 Washington, D. C.,
May 21, 1909.

The foregoing field notes of the subdivision of Sections 3, 10, 15, and 22, and survey of farm units in said sections in T.24 N. R.28 E. Willamette Mer. Oregon, executed by W. Roy Saxton, assistant engineer, U.S.R.S., in accordance with Departmental instructions of October 24, 1906, having been examined and found to conform with said instructions, are hereby approved.

Morris Bier
 Acting Director.

Department of the Interior,
 General Land Office,
 Washington, D. C.,
June 8 1909.

The foregoing field notes of the subdivision of Sections 3, 10, 15, and 22, and survey of farm units in said sections in T.24 N. R.28 E. Willamette Mer. Oregon, having been examined and found to conform with the requirements of this office, the said field notes and the surveys they describe are hereby accepted.

(Signed) FRED DENNETT,
 Commissioner.

gcof
 I certify that the foregoing transcript of the field notes of the above described surveys in T. 24 N., R. 28 E., W. M. Oregon, has been correctly copied from the original notes on file in this office.

Fred Dennett
 Commissioner.