

Rec'd in Office ^{See 101.} 376
 Oct 31st 1861 376

Field Notes of the Survey
 of the Subdivision lines and
 Meanders of the Columbia River
 in fractional Township No 5 North
 Range 28 East, in the State of Oregon
 by Timothy W. Davenport deputy
 Surveyor, under his Contract
 No 101, bearing date Aug 5th
 1861. Commenced this Township Sept 9th
 + Finished Sept 25th

Index Diagram of fractional
 Township No 5 N Range 28 East Mer. No.

Columbia River											
				32			32		31		31
				32	9	15	10		11		12
		31	22				10		5		
32	32	29	22			14		9			4
18	27	17	21	16	14	15	9	14	4		13
30		26		20		13		8			3
19	25	20	19	21	13	22	8	23	3		24
29		25		18		12		7			2
30	24	29	17	28	12	27	7	26	2		25
28		24		16		11		6			1
31	23	32	15	33	11	34	6	35	1		36

378
379
380

Field Notes

of the Survey of the
Subdivision Lines and meanders
of the Columbia River in
Township 5 North of Range
28 East of the Willamette
Meridian. in the State of Oregon,
Surveyed by J. W. Davenport
Dept. Surveyor under his Contract
N^o 101 executed and bearing
date August 5th 1861

1381 Township 5-N Range 28 East
Monday Sept. 9th 1861
381

chs North between Secs 35 & 36
Bar $20^{\circ}30' E$

40.00 Set gr Sec post in mound
with charred stake as per inst

80.00 Set post corner to Secs 25, 26
35 & 36. in mound with charred
stake, as per instructions
Soil sandy. Surface undulating
with large Sage & Greasewood

East on random between
Secs 25 & 36. Bar $20^{\circ}45' E$

40.00 Set temporary gr Sec post

80.00 Intersect East boundary
of the Township 28 chs North
of corner to Secs 25 & 36

$189^{\circ}48'$ West on true line between
Secs 25 & 36

40.00 Set gr Sec post in mound
with charred stake as per inst

80.00 To corner of Secs 25, 26.
35 & 36.

Township 5-N. Range 28 East 2
Tuesday Sept. 10th 1861

382

382

chs North between Secs 25 & 26
Bar $20^{\circ}30'E$

40.00 Set gr Sec post, made mound,
deposited charred stake against
Secave the most of the day and
Grass-wood

80.00 Set post corner to Secs
23, 24, 25 & 26.

The surface of this mile lies
in sand waves, coursing E & W.
from 2 to 5 chains apart and
from 6 to 12 feet in height

East on random between
Secs 24 & 25. Bar $21^{\circ}10'E$

40.00 Set ~~temporary~~ gr Sec post

79.80 ~~Intersect~~ North & South
line. the Eastern boundary of
the Township 12 chs North of the

$189^{\circ}55'$ Sec corner to 24 & 25
West on true line between Secs 24 & 25

39.90 Set gr Sec post in mound
with charred stake against

79.80 To corner of Secs 23, 24
25 & 26.

3 383
Township 5-N. Range 28 East

chs North between Secs 23 & 24
Bar $21^{\circ} 10'$ East

40.00 Set gr Sec post in mound
with charred stake as pr. inst.
Enter rocky land

72.00 Columbia trail Course E & W

80.00 Set post corner to Secs 13, 14
23 & 24, made mound and
drove charred stake as pr. inst.

East on random between
Secs 13 & 24. Bar $20^{\circ} 45'$ E

40.00 Set temporary gr Sec post

79.66 Intersect East boundary
of the Township 40 lbs North
of the corner to Secs 13 & 14.

$189^{\circ} 43'$ West on true line between
Secs 13 & 14

39.83 Set gr Sec post in mound
with charred stake as pr. inst.

79.66 To corner of Secs 13, 14
23 & 24.

Surface flat and Rocky

Township 5-N. Range 28 East

3847

384

chs North between Secs 13 & 14
Bar $21^{\circ}45'16''$ E

40.00 Set gr Sec post in mound
with churred stake as per inst

80.00 Set post corner to Secs
11, 12, 13 & 14, made mound
drove churred stake as per inst
Surface flat & rocky
between the rocks sage, sage
and bunch grass.

East on random between
Secs 12 & 13. Bar $20^{\circ}20'$ E

40.00 Set temporary gr Sec post

79.62 Intersect East boundary of the
Township 28 chs North of
the corner to Secs 12 & 13

189.48 West on true line between
Secs 12 & 13

29.81 Set gr Sec post in mound
with churred stake as per inst

79.62 To corner of Secs 11, 12,
13 & 14.

5- 385.
Township 5 N. Range 28 East
385

ch North between Secs 11 & 12 ft
Bar $20^{\circ}20'E$

40.00 Set gr Sec post in mound
with charred stake as pr. inst.

45.20 Edge of perpendicular bluff
over looking the Columbia River - 100

55.00 Set meander post corner - 100

to Secs 11 & 12, on the bank of
the River 30 feet above the water
and made mound of rocks
depositing charred stake.

Bar $19^{\circ}40' East$

Surface of this mile is
generally flat but broken
by rocks.

Township 5-N. Range 28 East (C.
Monday Sept 11 1861

386

386

Ch North between Secs 34 & 35-

Bar $20^{\circ}30'$ East

40.00 Set gr Sec post in mound
with charred stake as pr. inst

80.00 Set post corner to Secs 26 & 27

34 & 35. made mound and

drove charred stake as pr. inst

Over this mile the Sage and

grease-wood are very dense

and large, ^{chaining} unfavorable for close

Cast on random between

Secs 26 & 35. Bar $20^{\circ}30'$ E

40.00 Set temporary gr Sec post

80.50 Intersect North & South

line 40 lbs North of corner

to Secs 26 & 35-

$189^{\circ}43'$ West on True line between

Secs 26 & 35-

30.25 Set gr Sec post in mound

with charred stake as pr inst

80.50 To corner of Secs 26, 27, 34 & 35-

7 387
Township 5 N. Range 28 East
387

chs North between Secs 26 & 27
Bar $20^{\circ}30'$ East

22.00 Commence to descend

40.00 Set post ~~gr Sec~~ corner in
mound with charred stake as per inst

55.00 Foot of rise - 25-

80.00 Set post corner to Secs 22,
23, 26 & 27, made mound
and deposited charred stake
as per instructions

Leave Sage & Grass-Wood

East on random between
Secs 23 & 26. Bar $20^{\circ}45'$ E

40.00 Set temporary gr Sec post

80.80 Intersect North & South line
34 lbs North of corner to
Secs 23 & 26.

$189^{\circ}44'$ West on true line between
Secs 23 & 26.

40.40 Set gr Sec post in mound
with charred stake as per inst

80.80 To corner of Secs 22, 23, 26 & 27

Township 5-N. Range 28 East

3888

388

- chs North between Sect 22 & 23
var $20^{\circ}45'1''$ East
- 40.00 Set gr Sec post, made mound
and drove chum'd stake as pr. inst
- 80.00 Set post corner to Sects 14, 15
22 & 23, made mound and
drove chum'd stake as pr. inst
-

East on random between
Sect 14 & 23. var $20^{\circ}45'1''$ E

- 40.00 Set temporary gr Sec post
- 80.65 Intersect North & South line
30 lbs North of corner
to Sects 13, 14, 23 & 24
- $189^{\circ}47'$ West on true line between
Sect 14 & 23
- 40.32½ Set gr Sec corner post
in mound, with chum'd stake
as pr. inst
- 60.65 Columbia trail course 85° E
- 80.65 To corner of Sects 14, 15, 22 & 23

9
389 Township S. N. Range 28 East
389

chs North between Secs 14 & 15 -
Bar $20^{\circ}45' E$

11.00 Columbia trail, course E & W

40.00 Set gr sec post in mound
with charred stake as pr. inst

80.00 Set post corner to Secs
^{10 & 11}
14, 15, ~~22 & 23~~, made mound
and drove charred stake
as pr instructions

East on random between
Secs 11 & 14. Bar $20^{\circ}30' E$

40.00 Set temporary gr sec post

80.75 Intersect North and South
line 30 chs North of corner
to Secs 11 12 13 & 14.

189°47' West on true line between
Secs 11 & 14.

40.37 $\frac{1}{2}$ Set post, gr sec corner, in
mound with charred stake
as pr instructions

80.75 To corner of Secs 14, 15 -
^{10 & 11}
~~22 & 23~~.

Township 5-N. Range 28 East ¹⁰

ch North between Secs 10 & 11 390

18.00 Begin to descend Columbia bluff

40.00 At foot of bluff set gr. sec. - 75
post in mound with

churned stake as per inst.

55.10 Set meander post, corner - 75
to Secs 10 & 11, made mound
above churned stake as per
inst. Per 20° 45' East

Thursday Sept. 12th 1861

Commence on the Standard
Parallel at the corner of Secs
33 & 34, on top of a rocky spine
or bluff East of the Unutilla River
and elevated 75 or 100 feet above
the River,

Thence -

1
2

11

391 Township 5-N. Range 28 East
391

chs. North between Secs 33 & 34
Bar 20° 30' East

40.00 Set gr sec post in mound
with charred stake as pr. inst.

80.00 Set post corner to Secs 33 34
27 & 28. made mound ^{of rock} and
deposited charred stake
as pr instructions, on the
East side of Rocky point.

East on random between
Secs 27 & 34. Bar 18° 30' E

40.00 Set temporary gr sec post

80.27 Intersect N+South line
3-4ths North of corner to
Secs 26, 27, 34 & 35

189° 58' West on true line between
Secs 27 & 34. Commence descending

40.1 3 1/2 Set gr sec corner post, made
mound; deposited charred stake
as pr inst.

80.27 To corner of Secs 27, 28 33 & 34 - 50

Township 5 N. Range 28 East 392

12

392

Chs	North between Secs 27 & 28 Bearing 18° 30' E	
15.00	bottom of hollow	- 35-
35.00	Top of knob	+ 40
40.00	Set gr Sec corner post, made mound with charred stake as per instructions	- 30
43.50	perpendicular ridge of rock	+ 50
80.00	Set post corner to Secs 21, 22, 27 & 28	- 45-

East on random between Sec 22 & 27. Bearing 20° 40' E

40.00	Set temporary gr Sec post
80.33	Intersect North & South line 11 lbs South of corner to Sec 22, 23, 26 & 27
889° 55'	West on true line between Secs 22 & 27.
40.16½	Set gr Sec corner post, made mound, drove charred stake as per instructions
80.33	To corner of Sec 21, 22, 27 & 28

13

393 Township 5 N. Range 28 East

chs 393 North between Secs 21 & 22

bar 20° 40' East

40.00 Set gr Sec post, made mound - 20
drove charred stake as per inst

80.00 Set post - corner to Secs
15-16-21 & 22, made mound
and drove charred stake as per inst
Surface undulating, Soil. Sand
with Sage Grass-wood and
bunch grass.

East on random between
Secs 15 & 22. bar 20° 15' East

40.00 Set temporary gr Sec post
80.00 Intersect North & South line
3-4 hrs South of corner to Secs
14-15; 22 & 23

589° 58' West on true line between
Secs 15 & 22

40.00 Set gr Sec corner post, made
mound, and drove charred
stake as per instructions

80.00 To corner of Secs 15-16, 21 & 22
Land flat & nearly all sand

Township 5 N. Range 28 East

14

394
394

- chs North. between Secs 15 & 16
Bar $20^{\circ} 15'$ East
- 26.00 Columbia trail, course $S 70^{\circ} E$
- 40.00 Set gr Sec post, made mound
and deposited churred stake as per inst
- 64.00 commene to descend bluff
- 80.00 Set post corner to Secs 9.10.15 & 16 -40
made mound, drove churred stake
as per instructions.
-

- East on random between
Secs 10 & 15. Bar $20^{\circ} 15'$ East
- 40.00 Set temporary gr Sec post
- 80.12 Intersect North & South line
at ~~section~~ corner
- West on true line between
Secs 10 & 15
- 40.06 Set gr Sec post on top of bluff
made mound, drove churred
stake as per inst
- 80.12 To corner of Secs 9.10 15 & 16 + 50

15
395 Township 5 N. Range 28 East
395

chs North between Secs 9 & 10

Bar $21^{\circ}30'$ East

this was by
20-15-00
Page 14

40.00 Set gr Sec post, made mound
and drove churred stake as per inst
Surface flat.

55.00 Set meander ~~corner~~ corner to Secs
9 & 10. at high water mark
6.00 chs from the water edge
made mound, and drove
churred stake as per inst,
Bar $21^{\circ}15'$ East

Friday Sept 13th 1861

North between Secs 32 & 33

Bar 21° East

15.70 Trail leading E & W

40.00 Set gr Sec post, made mound
, drove churred stake as per inst

80.00 Set post corner to Secs
28, 29, 32 & 33, made mound
and drove churred stake
as per inst

Surface undulating. Soil
Sandy with Sage etc.

Township 5 N. Range 28 East 16

chs East on random between 396
396

Secs 28 & 33. Var $21^{\circ} 6' E$

40.00 set temporary gr Sec post

80.10 Intersect N & South line 10 chs

South of Sec corner,

$S 89^{\circ} 56'$ West on true line between
Secs 28 & 33.

.57 Top of rock + 15

40.00~~5~~ set gr Sec post, made mound - 75
and drove charred stake as print

49.00 Amutilla landing road course N - 25

61.00 Amutilla River, 1.25 chs broad *

runs N. water in channels in rock

63.10 To West bank

65.00 Top of bank + 40

80.10 To corner of Secs 28, 29
32 & 33.

* No timber along the river
except some stunted Alders
and Willows fringing the bank
and over hanging the water.

17 397

Township S. A. Range 28 East

397

ch North between Secs 28 & 29

var $21^{\circ} 6' E$

40.00 Set gr Sec post, made mound
and drove charred stake
as per instructions

80.00 Set post corner to Secs
20, 21, 28 & 29, made mound
and drove charred stake as per inst
Surface broken by ridges
from 2 to 4 chs apart and from
12 to 20 feet in altitude, course E & W

Township 5 N. Range 28 East

398 18

398

chs East on random between

Secs 21 & 28 bar 21° East

48.00 Set temporary gr Sec post

80.50 Intersect North & South line
at post corner to Sec

21, 22, 27 & 28

West on true line between

Secs 21 & 28

4.00 strike of rocks

+ 30

15.50 Top of ridge

+ 30

29.50 leave rocks

40.25 set gr Sec post, made

mound and drove chured

stake as per instructions

- 15

69.50 Umatilla road course N & S.

- 30

70.50 descend River bank

76.50 Umatilla river 2 chs broad

course N° 20° W. Water running

77.50 commence ascending bank

79.20 Top of bank

+ 40

80.50 To corner of Secs 20 21

28 & 29.

19 399

Township 5 N. Range 28 East

399

chs North between Sect 20 & 21

bar 21° East
line descends and gradually
approaches the ^{Um} ^{atilla} River

40.00 Set gr Sec post, made
mound and drove churred
stake as per inst.

65.00 Umatilla River

- 25 -

80.00 Corner to Sect 16, 17, 20, 21

a point in the bed of the
River, from which 20 lbs
West and 20 lbs North upon
25-lbs post and 4.90 lbs ~~long~~
an island, I established
a witness corner of Stone
and post from which an
Alder 4 inches in dia,
bears S W 22 lbs distant.

The Umatilla here
is about 5:00 chs broad
the water being spread
over nearly the whole bed
and runs N 20° W

Township 5 N. Range 28 East

400.20

400

chs East on random between

Secs 16 & 21. Bur $21^{\circ}15'$ East

40.00

Set temporary gr Sec post

80.80

Intersect North & South line

30 lbs North of corner to

Secs 15, 16, 21, 22

189°47'

West on true line between

Secs 16 & 21

25.80

North point of rocky ridge + 10

40.40

Set gr Sec post, made mound

and drove charred stake as per inst. - 10

78.80

Umatilla Road - 30

80.00

Umatilla River

80.80

To corner of Secs 16, 17, 20, 21

21 401
Township S. N. Range 28 East
401

chs North between Secs 16 & 17
Bar $21^{\circ} 15' E$

- | | | |
|-------|--|------|
| 4.00 | bank of River | + 8 |
| 5.00 | Umattilla Road, $N 20^{\circ} W$ | |
| 28.00 | Top of bluff | + 50 |
| 30.57 | commence to descend | |
| 37.00 | Foot of bluff and Columbia
Trail, course NE | - 50 |
| 40.00 | Set gr Sec post, made mound
and drove charred stake
as per instructions | |
| 80.00 | Set post corner to Secs
8, 9, 16 & 17. made mound
and deposited charred
stake as per instructions | |
-

Township 5 N. Range 28 East -

402 22
402

40 chs East on random between

Secs 9 & 16. Bur $20^{\circ}30' E$

40.00 Set temporary gr Sec post

80.50 Intersect North and South
line 37 lks North of the
corner to Secs 9, 10, 15 & 16

189°44' West on true line between
Secs 9 & 16

40.25 Set gr Sec post, made
mound and drove charred
stake as per inst

80.50 To corner of Secs 8, 9, 16, 17

North between Secs 8 & 9
Bur $20^{\circ}30' E$

17.50 Set Meander corner to
Secs 8 & 9 on the bank of the
Columbia River about
1.00 from the water and
opposite a low gravelly island
or bar about 40.00 chs long

Bur $20^{\circ}30' East$

made mound & drove charred stake as per inst

23 493

Township S. N. Range 28 East

403

West on true line between

Secs 8 & 17. Bar $20^{\circ} 30'$ East

40.00 Set gr Sec post, made mound and drove churred stake as pr inst

49.50 Set meander corner to Secs 8 & 17 at high water mark on the bank of the Columbia River. 3 chs distant from made mound & drove churred stake as pr inst the water. Bar 21° East

Saturday Sept 14th 1861

North between Secs 31 & 32

Bar 21° East

40.00 Set gr Sec post. made mound and deposited churred stake as pr instructions

80.00 Set post corner to Secs 29, 30, 31 & 32, made mound and drove churred stake as pr instructions.

Surface undulating soil less sandy. more grass and less sage.

Township 5 N. Range 28 East

404 24

404

chs

~~East~~ on random between

Secs 29 & 32. bar ^{25'} 21° East

40.00

Set temporary gr Sec post

80.48

Intersect North & South line

15-lks North of corner to Secs
28, 29, 32 & 33

189° 54'

West on true line between

Secs 29 & 32

40.24

Set gr Sec post, made mound
and drove charred stake as per
instructions. Top of rise

+30

80.48

To corner of Secs 29, 30, 31 & 32

bar 21° 25' East

North between Secs 29 & 30

40.00

Set gr Sec post in mound
with charred stake as per inst

62.00

Commence to descend

80.00

Set post corner to Secs 19, 20
29 & 30, made mound and
drove charred stake as per
instructions.

- 15 -

Soil less sandy, fine
bunch grass & less Sage.

25- 425

Township S-N. Range 28 East

408

chs East on random between

Secs 20 & 29 Bar 21° 6' E

40.00 Set temporary gr Sec post

80.08 Intersect N & South line

30 lbs North of Sec corner

189° 47' West on true line between
Secs 20 & 29.

commence ascending

40.04 Set gr Sec post, made
mound and drove churled
stake as per instructions

80.08 To corner of Secs 19, 20, 29 & 30 + 50

Bar 21° 6' East

North between Secs 19 & 20

descend from corner

40.00 Set gr Sec corner post, made - 50
mound and drove churled stake etc.

60.00 commence to ascend

76.00 Top of bluff + 50

80.00 Set post corner to Secs
17, 18, 19 & 20, made - 10
mound and deposited
churled stake as per inst

Township 5 N. Range 28 East

406

chs East on random between

Secs 17 & 20. Run 21° East

40.00

Set temporary gr Sec post

80.30

Intersect North & South line

at Section corner in River Umattilla

West on true line between

Secs 17 & 20

.12

Shore of Island. edge of water

2.84

bank of River, or shore

+12

3.30

2^d bank or bluff

+40

40.15

Set gr Sec post, made mound and drove charred

stake as per instructions

80.30

To corner of Secs 17, 18, 19, 20.

27

407
Township 5 N. Range 28 East

407

chs North between Secs 17 & 18
bar 21° East

Commence to descend

28.50 Columbia Trail course E & W

30.00 Umatilla River with bank -40

12 feet high, course N40°W
width of stream 6.00 chs

38.00 Top of bank +20

40.00 Set gr Sec post, made
mound and drove chumel
stake as per instructions

71.37 Set meander corner post
between Secs 17 & 18

on the bank of the Columbia
River 2.50 chs from water. made
mound and drove chumel stake as per inst-
Umatilla Ware House

bears N68° East about
5.00 chs distant.

bar 21° East

The land about the mouth
of the Umatilla is not good
though better than most
bordering the Columbia
but at best it is very spotted
as to fertility.

Township 5-N. Range 28 East

408 28

408

chs

West on random between

Secs 30 & 31. Bar $21^{\circ} 25'$ East

40.00

Set temporary gr Sec post

79.97

Intersect West boundary of
Township 3 lks North of
the corner to Secs 30, 31

$189^{\circ} 54'$

East on true line between

Secs 30 & 31

39.97

Set gr Sec post, made
mound and drove chused
stake as pr. inst

79.97

To corner of Secs 29, 30, 31 & 32

Surface, flat, Soil
Sandy and gravelly, Grass
good and Sage less
abundant.

29 409 Sunday Sept 15th 1861

409 chd West on random between

Secs 19 & 20, bar 21^{6'} East

40.00 Set temporary gr Sec post

79.90 Intersect West boundary of the Township 10 chs South of the Sec corner

S 89° 46' East on true line between Secs 19 & 20

39.90 Set gr Sec post, made mound and chow charred stake as per inst.

67.00 Commence to rise

70.00 Top of rise

79.90 To corner of Secs 19, 20 29 & 30 &

Handwritten notes:
This post is
21 chs in pay
25

+ 50

Township 5 N. Range 28 East

410 30

400

chs West on random between

Secs 18 & 19. Bar 21 East

40.00

Set temporary gr Sec post

79.89

Intersect West boundary of

the Township 11 lbs South

of post corner to Secs 18 & 19

S 89° 56'

East on true line between

Secs 18 & 19.

39.89

Set gr Sec post, made mound

and drove chured stake

as per instructions

70.00

Foot of ridge, course N & S

75.00

Top of ridge

+ 40

79.89

To corner of Secs 17, 18, 19, 20

Soil sandy with Sage

grease wood & bunch grass

General Description.

Excepting a few ~~very~~ small patches of soil within a few rods of the Unutilla River, Columbia River, this Township is worthless except for grazing purposes, and much less valuable than other portions of the Unutilla County on account of the Sand & Cactus which abound

31. Township 5 N. Range 28 East
411

Field Notes
of the
Meanders ~~in~~ Township 5 N
of Range 28 East. of the
Columbia River.

Monday Sept 25th 1861
Commencing on the Township
line between Ranges 28 &
29 East Townships 5 North
at the meander corner to Secs
7 & 12, Thence down the
south side or left bank of the
River.

Courses	Distances	Remarks
N 74° 45' W	40.32 chs	
N 89° 15' W	40.69	To meander corner between Secs 11 & 12
N 72° 15' W	17.90	
West	38.50	
S 78° 30' W	25.50	To meander corner between Secs 10 & 11
	162.91	

Course	Distances	Remarks
N 88° 15' W	50.00	
S 87° 15' W	30.42	To meander corner of fractional Secs 9 & 10.
S 89° W	20.08	
S 59° 09' W	39.50	
S 58° 15' W	31.14	To meander corner of fractional Secs 8 & 9
S 67° 15' W	26.31	
S 73° 45' W	26.31	To meander corner between fractional Secs 8 & 17
	223.76	
S 80° W	20.47	
S 64° W	11.75	To meander corner between fractional Secs 17 & 18
S 68° W	19.50	To the mouth of the Umatilla River 11.00 chs broad. Course NW
"	10.50	
	30.00	
S 85° 15' W	18.26	
S 77° W	34.60	To the meander corner on the Township line between Secs 13 & 18

At this point the Columbia river is 62.80 chs broad and a deep and rapid current.

413

Township 5 N. Range 28 East

413

List of Names

A list of the names of the individuals employed to assist in running, measuring or marking the lines and corners described in the foregoing field notes of Township 5 North Range 28 East N. Mer.

Showing the respective capacities in which they acted

John	Miller	Chairman
Benjamin	F. Davenport	"
Henry	Allen	Apeman

We hereby certify that we assisted Timothy W. Davenport deputy Surveyor, in surveying the subdivision lines of Township No 5 North Range 28 East of the Willamette Meridian, and that said Township has been in all

414

414

respects, to the best of our knowledge
and belief, well and faithfully
surveyed, and the boundary monument
planted according to the instructions
of the Surveyor General

Benjamin^{Jr} Gavenport
Henry Allen

Subscribed and sworn to by
the above named persons, before
me, a Justice of the Peace for
the County of Marion in the State
of Oregon, this twenty first day
of October 1861

Volney Leonard J. P.

414

415

I Timothy W. Davenport, deputy Surveyor,

do solemnly swear that, in pursuance of a Contract with B. J. Pengra.

Surveyor of the public lands of the United States in the State of Oregon, bearing date the 5th day of August 1861, and in strict conformity to the laws of the United States, and the instructions furnished by the said Surveyor General, I have faithfully surveyed the subdivision and meander lines of Township No. 5 North of the base line and of Range No. 28 East of the Willamette Meridian, in the State aforesaid, and do further solemnly swear that the foregoing are the true and Original field notes of such survey.

Timothy W. Davenport

Sworn to & Subscribed before me } Deputy Surveyor
at Eugene City, October 31st 1861 }

B. J. Pengra
Survey General

416
416

Surveyors Office at
Crown City ~~Dec 7th~~ 1861
November 5th

The foregoing field notes of the
Survey of the Subdivision and
Meander lines of Township 5
North of the base line and Range
28 East - Willamette Meridian
in the State of Oregon executed
by Timothy H. Darvport under
his contract No 104, bearing date
August 5 1861 having been
critically examined the maps
and corrections and explanations
made the said field notes
and the surveys they describe
are hereby approved

B. B. Singer
Surveyor General