

219
219

Field Notes of the Subdivision
Lines in Township No 5 N R 30
E of the Willamette Meridian in
the State of Oregon, Surveyed by
Leopoldus S. Payne deputy Surveyor
under his contract No 1000 dated
August 1st 1861

Box 20-

Commenced September 18th 1861
Completed September 25th 1861

page	5-
"	7-
"	13-
"	18-
"	20-
"	22-
"	29-
"	30-
"	31-
"	35-

Payne
No. 1000

220

220

Index

Subdivision Lines in Township
No 5. N R 30 E

<i>Columbia River</i>									
6	5	5	4	4	3	10	2	7	1
34	35	25	18	12	7				
7	33	8	24	9	10	12	11	6	12
32	32	24	17	11	6				
18	31	17	23	16	17	15	11	14	5
31	30	23	16	10	4				
19	29	20	22	21	16	22	10	23	3
29	28	21	15	9	3				
30	28	29	31	28	15	27	9	26	2
27	27	20	14	8	2				
31	26	32	10	33	14	34	3	35	36

Field notes of subdivision
lines in Township No 5 North
of Range No 30 E of the
Willamette Meridian.

September 18th -

Beginning at the corner of
Sections 35 & 36 on the South
line of Town 5 - R 30,

Bear 19° 42' E

North on line between Secs 35, 36

40.00 Set Churned Stake with mound
trench and pits as per notes

for 1/4 sec corner,

80.00 Set Churned Stake with mound
trench and pits as per notes

for corner to Secs 23, 26, 35, 36,

Bear 19° 45' E

See 2^d note.

222

222

Subdivision Lines

chain

East on random between

secs 25, 36

40.00 Set charred stake with mound trench and pits as per notes

79.28 Intersect Town line 23 cks south of corner to secs 25, 26,

S89°38'W on true line between

secs 25, 36.

7.15 Indian Trail N 45° E

39.64 Set charred stake with mound trench and pits as per notes for 1/4 sec corner,

79.28 Corner to secs 25, 26, 35, 36.

See 2^o note

North on line between secs 25, 26,

37.50 Begin to descend deep Ravine,

40.00 Set charred stake with mound trench and pits as per notes for 1/4 sec corner.

47.60 Indian trail, Post.

Township 5 N R 30 E W. 11.

Chain

48.00 Bottom of Ravine about 250 feet
deep Course west,

55.00 Top of Hill.

80.00 Set Charred Stake with mound
trench and pits as per notes
for corners to Secs 23, 24, 25, 26

Bar $19^{\circ} 30' E$

Land broken. loci 3' rate

East on random between Secs 24, 25

40.00 Set limp 1/4 sec corner.

79.84 Antiseptic Town line 13 Chs North
of post corner to Secs 24, 25

$N 89^{\circ} 55' W$, on true line between Secs 24, 25

5.10 Indian trail, Course North.

39.92 Set Charred Stake with mound
trench and pits as per notes
for 1/4 sec corner.

79.84 Corner to Secs 23, 24, 25, 26

North on line between Secs 23, 24

224

H

224

Subdivision Lorus

Chains

40.00 Set charred stake with
mound trench and pits
as per instr for 1/4 sec corner.

80.00 Set charred stake with
mound trench as pits as per
instr for corner to secs
13, 14, 23, 24

Cor 19° 45' E

Soil 2^o rate

East on random distance to sec 13, 24

40.00 Set 1/4 sec corner.

78.00 Intersect town line to the
North of post corner to
secs 13, 24.

This being 2.00 chains
short of the proper length
we resun East line of
Sec 24 and find that it
bears on the North half
mile S 24° E and on the
South half mile S 2° 15' E

Township 5 N R 30 E T. 11.

Chains

which shows section 24 to
close within limits.

We therefore run
889°33' W on true line between secs
13. 24.

37.00 Indian trail North

39.00 Set Chained stake with mound
trench and pits as per notes
for 1/4 sec corner.

78.00 Corner to secs 13, 14, 23, 24
Vic 2^d rate

September 19th

North on line between secs 13. 14

40.00 Set Chained stake with mound
trench and pits as per notes
for 1/4 sec corner.

57.00 Indian trail N 45° W

70.00 Set Chained stake with mound
trench and pits as per notes
for corner to secs 11, 12, 13, 14

(Vic 20° 15' E

226

6

226

Subdivision Lines

Chains

- East on random between secs 12, 13 -
40.00 Set temp $\frac{1}{4}$ sec corner.
 - 78.00 In correct sec line 70 links
North of corner to secs 12, 13
N $89^{\circ}30'W$, on true line between
secs 12, 13.
 - 39.03 Set charred stake with mound
trench and pits as per notes
for $\frac{1}{4}$ sec corner.
 - 78.00 Corner to secs 11, 12, 13, 14 -
true 2^o rate
-

- North on line between secs 11, 12,
40.00 Set charred stake with mound
trench and pits as per notes
for $\frac{1}{4}$ sec corner.
- 80.00 Set charred stake with
mound trench and pits
as per notes for corner to
secs 1, 2, 11, 12
Bar 20^oE
true 2^o rate

Township 5 N R 30 E T 4 S

Chains

East on random between Secs 1, 12

40.00 Set Iron $\frac{1}{4}$ sec corner.

78.50 Intersect Iron line 50 links

North of post corner to Secs 1, 12.

$N 89^{\circ} 39' 11''$ on true line between Secs 1, 12

39.25 Set Charred Stake with mound
pinch and pits as per notes for
 $\frac{1}{4}$ sec corner.

78.50 Corner to Secs 1, 2, 11, 12.

Soil 2^d rate

Closing corner in sight - run

North $1^{\circ} 21' 11''$ on true line between
Secs 1, 2

25.00 Begin to descend Hill.

40.00 Set Charred Stake with mound
pinch and pits as per notes
for $\frac{1}{4}$ sec corner.

79.50 Intersect Iron line at post
corner to Secs 1, 2, 3 and 35.

36 T 6 N R 30 E -

Soil somewhat sandy - 2^d rate

228

8

228

Subdivision Lines

Chains

North on line between Secs 34, 35-

Var $20^{\circ}15' E$

40.00 Set Charred Stake with mound
trench and pits as per notes
for $\frac{1}{4}$ sec corner.

80.00 Set Charred Stake with mound
trench and pits as per notes
for corner to Secs. 26, 27, 34, 35-

Var $20^{\circ}06' E$

Var $2^{\circ}00'$

September 20th -

East on road between Secs 26, 35-

40.00 Set temp $\frac{1}{4}$ sec corner.

80.24 Intersect sec line 25 links

North of corner to sections

25, 26, 35, 36

N $85^{\circ}30'$ W on true line between Secs 26, 35;

40.12 Set Charred Stake with mound
trench and pits as per notes
for $\frac{1}{4}$ sec corner.

80.24 Corner to Secs 26, 27, 34, 35-

Township 5-NR 30 E. T111

Chairs

North on line between Secs 26, 27

5.00 Top of hill descending into Ravine

20.00 Bottom of Ravine about 13-0

put dup. Course West

32.00 Top of hill.

40.00 Set-charged stake with mound
trench and pits as per instrs

for 1/4 Sec corner.

80.00 Set-charged stake with mound
trench and pits as per instrs,

for corner to Secs 21, 23, 26, 27

over $20^{\circ} 24' E$

Land uneven, Soil sandy, 3^d sale.

East on random between Secs 23, 26

40.00 Set-temp 1/4 Sec corner.

80.40 Intersect Sec line, 0.8 links

North of post corner to Secs

23, 24, 25, 26

189^o 57' W on true line between Secs

23, 26

40.20 Set-charged stake with mound

230

10

230

Subdivision Lines

Chasins

trench and pits as per instrs
for 1/4 sec corner

80.40 Corner to Secs 22, 23, 26, 27.

See 2^o note

North on line between Secs 22, 23.

40.00 Set charred stake with mound
trench and pits as per instrs

X for 1/4 sec corner.

80.00 Set charred stake with mound
trench and pits as per instrs

for corner to Secs 14, 15, 22, 23.

Bar 20° 24' E

See 2^o note

East on random between Secs 14, 23

40.00 Set temp 1/4 sec corner.

80.24 Insectic line 60 links

North of corner to Secs 13, 14, 23, 24.

N 89° 34' W, on true line between Secs 14, 23

40.12 Set charred stake with mound
trench and pits as per instrs.

Township 5 N R 30 E M 11

Cheris

~~80.24~~ 40.24 for '14 Sec Corner.

80.24 Corner to Secs. 14, 15, 22, 23

Set 2^o rate

North on line between Secs 14, 15

40.00 Set charged stake with mound
bench and pits as per instrs.
for '14 Sec Corner.

80.00 Set charged stake with mound
bench and pits as per instrs
for corner to Secs 10, 11, 14, 15

Bar 20° 06' E

Set 2^o rate

East on random between Secs 11, 14

40.00 Set temp. '14 Sec Corner

80.10 Antisect Sec line, 60 lks

North of corner to sections

11, 12, 13, 14

N 89° 34' W. on true line between Secs 11, 14

18.50 Indian trail N 43° W

40.05 Set charged stake with mound

232

12

232

Subdivision Lines

Chains

trench and pits as per notes
for 74 sec corner.

80.00 Corner to secs 10, 11, 14, 15
Sic 2^o note

North on line between secs 10, 11

40.00 Set charred stake with mound
trench and pits as per notes
for 74 sec corner.

54.00 Begin to descend towards
the Columbia river.

80.00 Set charred stake with mound
trench and pits as per notes
for corner to secs 2, 3, 10, 11

(bear 19° 45' E

Some notes - Sic 3^o note

East on random between secs 2, 11.

40.00 Set temp 74 sec post

80.00 On intersect line 70 links
North of corner to sections
1, 2, 11, 12

233
233

Township 5 N R 30 E M 11

Chains

N 89° 30' W on true line between Secs 2, 11
10.00 Begin to descend hill towards
the river.

40.00 Set charred stake with
mound trench and pits
as per notes for 1/4 sec corner.

64.50 Indian trail N 40° W

80.00 Corner to Secs 2, 3, 10, 11

Soil somewhat sandy. 3^d rate

Closing corner being in sight use

N 1° 21' W on true line between
Secs 2, 3

40.00 Set charred stake with
mound trench and pits
as per notes, for 1/4 sec corner.

57.00 Indian trail N 20° W

62.00 Descend rocky bluff.

(Variation at this point
23° 30' E)

79.50 Intersect town line at post
corner to Secs 2, 3.

Land for -

234

14

234

Subdivision Lines

chains

September 21st

North on line between secs 33, 34

Bar 20° E

46.00 Set charred stake with mound
trinch and pits as per notes

For 1/4 sec corner.

80.00 Set charred stake with mound
trinch and pits as per notes

for corner to secs 27, 28, 33, 34

Bar 20° 30' E

See 2nd note

East on random between secs 27, 34

40.00 Set Temp 1/4 sec corner.

79.96 Subtract 1/4 sec line .09 links

North of corner to secs

26, 27, 34, 35

N 89° 56' W on true line between
secs 27, 34

39.98 Set charred stake with mound
trinch and pits as per notes

for 1/4 sec corner.

Township 5 N R 30 E Well

Chorus

79.96 Corner to Secs 27, 28, 33, 34

North on line between Secs 27, 28

12.00 Begin to descend into Ravine

16.60 Bottom of Ravine about 100 feet deep.

26.00 Top of hill.

40.00 Set Charred Stake with mound
pinch and pits as per notes
for $\frac{1}{4}$ sec corner.80.00 Set Charred Stake with mound
pinch and pits as per notes,
for corner to Secs 21, 22, 27, 28Bar $20^{\circ} 30' E$ Scri $3^{\circ} 20' E$

East on random between Secs 22, 27

40.00 Set Trip $\frac{1}{4}$ sec corner,80.10 Intersect Sec line 36 (Ks)
North of corner to sections
22, 23, 26, 27.N 89 $^{\circ}$ 45' W on true line between Secs 22, 27

236

16

236

Subdivision Series

Chains

40.05 Set Charred Stake with mound
trench and pits as per notes
for 14 sec corner.

80.10 Corner to Secs 21, 22, 27, 28.
Sue 2° rate

North on line between Secs 21, 22

40.00 Set Charred Stake with mound
trench and pits as per notes
for 14 sec corner.

80.00 Set Charred Stake with mound
trench and pits as per notes
for corner to Secs 15, 16, 21, 22
(Per 19° 48' E
Sue 2° rate

East on random between Secs 15, 22.

40.00 Set temp 14 sec post

80.00 Intersect sec line 60 lks
North of corner to Secs

X 14, 15, 22, 23

N 89° 33' W on true line between Secs 13, 22

237
237

Township 5 N R 30 E T. 11.

Chains40.00 Set Charred stake with mound
trench and pits as per notes

For 1/4 sec corner.

80.00 Corner to Secs 15, 16, 21, 22.

Bearing 2° rate.

North on line between Secs 15, 16

40.00 Set Charred stake with mound
trench and pits as per notes

For 1/4 sec corner.

80.00 Set Charred stake with mound
trench and pits as per notes

For corner to sections, 9, 10, 15, 16

Bearing 19° 31' E

Bearing 2° rate.

East on random between Secs 10, 15

40.00 Set trip 1/4 sec post

80.20 Intersect Sec line to CKS

North of corner to Secs 10, 11

14, 15

N 82° 30' W on true line between Secs 10, 15

238
238

18

Subdivision Lines

Chains

- 40.10 Set Charred Stake with mound
trench and pits as per notes
for 1/4 sec corner.
84.20 Corner to secs 9, 10, 15, 16
Some rocks - soil rather poor.
-

North on line between secs 9, 10

35.50 Begin to ascend hill.

40.00 Set Charred Stake with mound
trench and pits as per notes
for 1/4 sec corner.

80.00 Set Charred Stake with mound
trench and pits as per notes for
corner to secs 3, 4, 9, 10

Var $20^{\circ} 45' E$

Surface uneven, vic 3 rods

Closing corner being in sight run

$S 89^{\circ} 55' E$ on true line between secs
3, 10

40.06 Set Charred Stake with mound
trench and pits as per notes
for 1/4 sec corner.

Township 5 N R 30 E T11

Chains

80.12 Corner to Secs 2, 3, 10, 11

At 50' Won true line between Secs 3, 4

10.50 Begin to descend steep hill.

37.50 Indian trail, E & W.

40.00 Set Chained Stake with ground
bench and pits as per notes
for 1/4 Sec Corner.

47.70 Ascend perpendicular Bluff
Rocks about 10 feet high.

65.10 Descend perpendicular rocky
Bluffs about 50 feet high
bar at this point 29° E.

74.00 Descend steep rocky Bluff
about 30 feet high.

76.60 Descend another Bluff about
25 feet high.

79.40 Descend rocky Bluff about
50 feet high.

79.60 Enter set-Town line at
first Corner to Secs 3, 4

249

240

20

Subdivision Lines

Chorus

September 22^d

North on line between secs 32, 33.

Var 24° E -

40.00 Set-Charred stake with
 mound trench and pits as
 per notes for 1/4 sec corner,
 59.00 Begin to descend into Ravine,
~~67.00~~ Bottom of Ravine, 100 feet
 deep, course West

76.50 Top of Hill,

80.00 Set-Charred stake with
 mound trench and pits as
 per notes for corner to secs
 28, 29, 32, 33.

Var 20° E

Land hilly & rocky, soil 3. rate

Realizing corner being in sight run

East on ~~line~~ between

secs 28, 33,

13.00 Begin to descend into Ravine
 35.00 Bottom of Ravine, about
 100 feet deep, - S 60° N.

Township 5 N R 30 E Tm.

chains40.00 Set Chopped Stake with mound
trench and pits as per notes

For 1/4 Sec Corner,

68.00 Top of Hill

80.20 Corner to Secs 27, 28, 33, 34
Land hilly. Set 3^d rate

North on line between Secs 28, 29

40.00 Set Chopped Stake with
mound trench & pits as per
notes For 1/4 Sec Corner,80.00 Set Chopped Stake with mound
trench and pits as per notes
For Corner to Secs 20, 21, 28, 29

Bar 20° 15' E

Set 2^d rate

East on random between Secs

21, 28

40.00 Set Temp 1/4 Sec Corner

80.00 Antissect Sec line 3-3 lks
North of corner to sections

242
242

22

53

7159

46 5 5
22

Subdivision Lines

Chains

21, 22, 27, 28

N 89° 38' W on true line between
pics 21, 28

40.00 Set Charred Stake with
mound trench & pits as per
notes for 1/4 sec corner,
80.00 Corner to pics 20, 21, 28, 29.
pic 2 rate

North on line between pics 20, 21

40.00 Set Charred Stake with mound
trench and pits as per
notes for 1/4 sec corner,
80.00 Set Charred Stake with
mound trench and pits as
per notes for corner to
pics 16, 17, 20, 21.

Top of Hill ascending
towards the Columbia,
bear 20° 06' E
pic 2 rate

Township 5 NR 30 E Well.

Chains

East on random between
Secs 16, 21

40.00 Set temp 74 sec post

80.32 Intersect Sec line 30 CRs
North of corner to Secs
13, 16, 21, 22.

N 89° 47' W on true line between
Secs 16, 21

40.16 Set charred stake with
mound trench and pits
as per instrs for 74 sec corner.

80.32 Corner to Secs 16, 17, 20, 21

Land sandy - 3° soil soil

September 23^o

North on line between Secs 16, 17.

40.00 Set charred stake with
mound trench and pits as
per instrs for 74 sec corner.

80.00 Set charred stake with
mound trench and pits
as per instrs for corner

244

244

24

Subdivision Series

Chasms

to secs 8, 9, 16, 17.

Bar 20° 21' E

Lana hilly - Soil 2° rate

East on random between

secs 9, 16

8038 Perimeter Sec line 45 lbs

North of corner to Secs

9, 10, 13, 16

N 89° 40' W on true line between

secs 9, 16

4029 Set-charged stake with mound bench and pits

as per notes for 1/4 sec corner,

8038 Corner to secs 8, 9, 16, 17

Lana hilly - Soil 3° rate

North on line between secs. 8, 9

4000 Set-charged stake with mound bench and pits as per notes

for 1/4 sec corner.

8000 Set-charged stake with mound

Township 3, RR 30 & Well

Cherino

bench and pits as per notes
for corner to Secs 4, 5, 8, 9

Cor 20° E

Surface uneven. Soil 3^d rate

East on random between Secs 4, 9

40,00 Set limp 1/4 sec post

80,60 Intersect sec line 35-1/2

North of post corner to Secs

3, 4, 9, 10

N 89° 45' W on true line between

Secs 4, 9

40,30 Set Charred Stake with

round bench and pits as

per notes for 1/4 sec corner,

80,60 Corner to Secs 4, 5, 8, 9

Land broken. Soil 3^d rate

North on true line between sec-

tioned Secs 4, 5

26,50 Trail and River Bottom

N 70° E.

246

246

Subdivision Lines

Chains

30.78 River bank. Set-changed
 stake with mound trench
 and pits as per notes for
 meander corner ~~at~~
 Practiced Secs 4, 5,
 Cor $19^{\circ}30'E$

September 24th

North on line between Secs 31, 32

Cor $20^{\circ}15'E$

32.50 Begin to ascend into ravine
 Course $88^{\circ}W$

40.00 Set-changed stake with
 mound trench and pits
 as per notes for 1/4 Sec Corner.

49.50 Bottom of Ravine about 80 feet
 deep.

58.00 Top of Hill.

80.00 Set-changed stake with
 mound trench and pits as
 per notes for corner to
 Secs 29, 30, 31, 32.

Township 5. N R 30 E Well

Chains

Cor 19° 54 E

Soil rather sandy. 3^d rate

East on random between Secs
29, 32

40.00 Set temp 1/4 sec post

79.80 Intersect Sec line 14 lks
South of corner to Secs

28, 29, 32, 33

889⁰ 34' N on true line between
Secs 29, 32

39.90 Set charred stake with
ironed bunch and pits
as per notes for 1/4 sec corner.

79.80 Corner to Secs 29, 30, 31, 32
Soil 2^d rate

West on random between Secs
30, 31

40.00 Set temp 1/4 sec corner,

79.94 Intersect town line 5 lks
North of corner to Secs 30, 31

248
248

Subdivision Series

Chains

N 89° 39' E on true line between Secs 30, 31
 39.94 Set-charged stake with
 mound trench and pits
 as per notes for 1/4 sec
 corner.

79.94 ~~Corner to~~ Secs 29, 30, 31, 32
 Side 2^d rate

North on line between Secs 29, 30
 40.00 Set-charged stake with
 mound trench and pits as
 per notes for 1/4 sec corner.

80.00 Set-charged stake with
 mound trench and pits
 as per notes for corner
 to Secs 19, 20, 29, 30.
 per 20° 18' E
 Side 2^d rate

East on ~~random~~ between Secs
 21, 29
 40.00 Set temp 1/4 sec corner

Township 5 N R 30 E. 7th

chains

79.78. Intersect sec line 32 links
North of post corner to secs
20, 21, 28, 29

N 83° 43' W on true line between
Secs 20, 29

39.89 Set-charged stake with
round tinch and pits as
per instris for 1/4 sec corner.

79.78 Corner to Secs 19, 20, 29, 30

relocating corner being in sight - run

Dist on true line between Secs
19, 30

5.00 Begin to ascend hill towards
the Columbia river,

40.00 Set-charged stake with
round tinch and pits as
per instris for 1/4 sec corner.

80.30 Intersect Iron line at post
corner to Secs 19, 30.

September 25-

North on line between Secs 19, 20

40.00 Set-charged stake with

250

250

Subdivisión Lima

Cherino

Mound trench and pits as
per notes for 1/4 sec corner.

80.00 Set Charned Stake with mound
trench and pits as per notes for
corner to Secs 17, 18, 19, 20

Bar 20, 21 E

Land Landy. Soil 3' 20" E

East on random between Secs
17, 20

40.00 Set temp 1/4 sec corner.

79.86 Intersect Sec line 10 links
North of corner to sections
16, 17, 20, 21

N 89° 55' W on true line between
Secs 17, 20

39.93 Set Charned Stake with
mound trench and pits
as per notes for 1/4 sec corner.

79.86 corner to Secs 17, 18, 19, 20
Soil 2' 20" E

Township 5-N R 30 E T11

Chains

West on random between Secs
18, 19

40.00 Set ~~trip~~ $\frac{1}{4}$ sec corner.

80.00 Connect Town line 40th N
North of corner to Secs 18, 19
N 89° 42' E on true line between
Secs 18, 19

40.00 Set charred stake with
mound trench and pits
as per notes for $\frac{1}{4}$ sec corner.

80.00 Corner to Secs 17, 18, 19, 20
True 3rd rate. X X

North on line between Secs 17, 18

40.00 Set charred stake with mound
trench and pits as per notes
for $\frac{1}{4}$ sec corner.

59.40 Perpendicular bluff, rocks
about 12 feet high. S 40° W

80.00 Set charred stake with
mound trench and pits

252

252

Subdivision Lines

Chains

as per notes for corner
to Secs 7, 8, 17, 18

Var $21^{\circ}30'E$

East on random between Secs
8, 17

40.00 Set temp $1/4$ Sec corner,

80.24 Intersect Sec line 39 lks

North of post - corner to

Secs 8, 9, 16, 17

$N89^{\circ}43'W$ on true line between
Secs 8, 17

4.60 Second rocky Bluff (N & S)

40.12 Set charred stake with

round bench and pits

as per notes for $1/4$ Sec corner.

41.50 Indian trail (North)

80.24 Corner to Secs 7, 8, 17, 18

West on random between Secs
7, 18

40.00 Set temp $1/4$ Sec corner

Township 5-N R 30-E M 11

Chains

- 80.00 Antissect - From line 30 lks
North of Corner to Sec 7. 18
N 85° 47' E on true line between
Secs 7. 18
- 40.00 Set-Charged Stake with
mound bench and pits as
per notes for 1/4 sec corner,
80.00 Corner to Secs 7. 8. 17. 18

North on line between Sections
7. 8

- 27.00 Descend step Bluff.
- 40.00 Set-Charged Stake with
mound bench and pits
as per notes for 1/4 sec corner.
- 40.50 Descend step Bluff
- 42.75 River Bottom (E & W)
- 43.50 Trace (E & W)
- 44.25 Bank of Slough E & W,
Offset 2.00 Chs East,
Object on North shore of
Slough across N 11 1/2° W

254
254

34

Subdivision Series

Chains

Making distance across
9,85 Chains and

37,10 Whole distance to North
side of Slough.

About 8,60 Chains
East of this point is a con-
siderable grove of large
Willow trees, above which
the Slough is dry at the
date of survey.

8,600 Set Charred Stake with
mound trench and pits
as per notes for corners to
aces 5, 6, 7, 8

Cor 19° 30' E

Land on this side
very sandy and barren
down to the river bottom,
from that North point
level and fertile, —
not subject to inundation.

Township 5th N R 30 E M 11

- Chains Closing corner being in sight run
East on true line between
Secs 3, 8
37.10 North bank of dry slough
N 50° E
46.00 Set Charred Stake with
ground, trench and pits
slough, ^{of wells in dry}
at ~~the~~ ^{the} ~~corner~~ ^{corner}
57.10 South bank of dry slough.
51.60 Trace to Halle Halla, West.
Reyn to Ascena Hill.
Intersect Sec line at post
80.50 Corner to Secs 4, 5, 8, 9
-

- West on true line between Prac-
tinal sections 6, 7
46.00 Set Charred Stake with
ground trench and pits
as per notes for 1/4 Sec corner.
54.50 South bank of Columbia
river, Set Charred Stake
with ground trench and
pits as per notes for
meander corner between

256

36

256

Submission Lines

Cherms

Fractional Sections C, 7,
Bar 19° 30' E

North on line between Fractional
Sections 5, 6

19.82 South bank of Columbia
river, set Charred stake
with mound trench and
pits as per notes for
meander corner between
Fractional Sections 5, 6.
Bar 19° E

Meanders of the left bank of
the Columbia river in Township
5 N R 30 E. Beginning
at the point where the
North line of Township
intersects the river bank.
Using the corner to Fractional
Sections 4, 5, and 33 T. C. N
Hence run down the

257
257

Township 5-N R 30-E T 11-N

Stream with the meanders thereof in Sec 4

S 57 3/4° W	89.14 chs	to corner of fractional Sec 4. 3 rd thence in Sec 3 rd
S 57 3/4° W	2.86	head of dry slough Course S 30° W. 7.00 chs wide
S 86 1/2° W	52.45	
S 70° W	10.90	
S 76 1/2° W	7.70	to corner of fractional sections 5, 6 thence in Sec 6
N 86° W	9.82	
S 70° W	17.58	
S 61° W	15.08	
S 66 1/4° W	16.35	to corner of fractional sections 6, 7 thence in Sec 7
S 66 1/4° W	23.82	
S 49° W	5.47	Antisect Town line at post

258
258

Corner to fractional
Sections 7R30 and 12R29.

General Description

The land in this Township
(except on the slope of the hills
next to the river) is all fair
grass land. The steep slopes
in the vicinity of the river are
extremely rough broken and
barren. Producing only
sage brush and grease wood.
The low river bottom is
however very fertile
producing a heavy crop
of grass, wild sunflower
and a variety of weeds of
smaller growth.

List of Names

A list of the names of the individuals employed to assist in running measuring or marking the subdivision lines and corners described in the foregoing field notes of Township No 5 North of Range No 30 East of the Willamette Meridian showing the respective capacities in which they acted.

John Brattain, Channerman
William B. Penger, Channerman
John L. Luckey, Axeman

I hereby certify that the
assisted by George S. Payne

560

260

deputy surveyor. in surveying
the subdivision lines in
Township No 5 North Range
30 East of the Willamette
Meridian and that said
Township has been in all
respects to the best of our
knowledge and belief well
and faithfully surveyed
and the boundary monuments
planted according to the
instructions furnished by
the Surveyor General.

John Brattain, Chairman
W. B. Rogers - Chairman
John L. Luckey, Assessor.

Subscribed & Sworn by the above named
persons before me, a Justice of the Peace in
& for the County of Lane, State of Oregon
this 1st day of November A.D. 1861

R. St. Parsons
Justice of Peace

I, Golshus S. Payne deputy Surveyor
do solemnly swear that in pursuance
of a contract with B. J. Pengra Surveyor
of the public lands of the United States
in the State of Oregon bearing date the
first day of August 1861, and in strict
conformity to the laws of the United States
and the instructions furnished by the
said Surveyor General I have faithfully
surveyed the subdivision lines in
Township No 5 North of the base line
of Range No 30 East of the Willamette
Meridian in the State of Oregon,
and do further solemnly swear
that the foregoing are the true and
original field notes of such
survey.

Golshus S. Payne,

Subscribed and sworn
before me this 4th day
of November A.D. 1861

B. J. Pengra, Surv General of Oregon

262

Paynes - Notes ...

262

Surveyors Office at
Eugene City Oreg Dec 5th 1861

The foregoing field notes of the
Survey of the Subdivisions
Township number
5 North of the base line and
Range 35 East of the Meridian
in the State of Oregon executed
by Delphis & S. Payne under
his Contract Number 100 dated
August 1st 1861 having been
critically examined the
necessity corrections and
explanations made the
said field notes and the
surveys they describe are
herby approved.

J. D. Payne
Surveyor General