

100

Rec'd in Office

137

Nov 4<sup>th</sup> 1861

137A

Field notes of the western boundary line of Township No 3 N R 31

and of Township No 5 N R 30 East of the Willamette Meridian surveyed by Dolphus S. Payne, <sup>deputy surveyor</sup> under his Contract No 100 dated August 1<sup>st</sup> 1861

Town 3 N R 31

Commenced August 20<sup>th</sup> 1861

Completed August 23<sup>rd</sup> 1861

Town 5 N R 30

Commenced September 17<sup>th</sup> 1861

Completed September 17, 1861

80

5-90

74-10



State of Oregon }  
 County of Wasco } ss: We, John Brattain

William B. Pengra, having been  
 appointed Chairman in the service  
 of A. S. Payne, deputy surveyor of the  
 lands of the United States in Oregon  
 do solemnly swear that we will  
 faithfully execute the duties of  
 Chain Carriers; - that we will  
 level the chain upon uneven  
 ground and plumb the tally  
 pins whether by sticking or drop-  
 ping the same; that we will  
 report the true distance to all  
 notable objects and the true  
 length of all lines that we  
 assist in measuring to the  
 best of our skill and ability.

Subscribed & sworn }  
 before me this 12<sup>th</sup> }  
 day of August 1861 }  
 W. C. Murray }  
 County Clerk }

John Brattain  
 Wm B Pengra

140

140A

State of Oregon }  
County of Wasco } ss:

The John L.  
Luc Key, & Benjamin F. Crow having  
been appointed assessors in the  
service of A. S. Payne, deputy surveyor  
of the lands of the United States in  
Oregon do solemnly swear that  
we will perform the duties of  
assessor or flagmen according  
to instructions given us and to  
the best of our skill and ability.

Subscribed & sworn to }  
before me this 12<sup>th</sup> }  
day of August 1861 }

Jno L. Lenokey  
B. F. Crow,

W. C. Murray  
County Clerk

Chains

Field notes of the exterior  
 boundary lines of Township No.  
 3 North of Range No 31 East  
 of the Willamette Meridian  
 in the State of Oregon, sur-  
 veyed by L. S. Payne, Deputy  
 Surveyor, under his Contract  
 No. 100, dated August 1<sup>st</sup>  
 1861.

August, 20<sup>th</sup> 1861

Having previously adjusted  
 my compass to the course of  
 the Guide Meridian by  
 actual tracing of the West  
 boundary of Township 3  
 North Range 31 East.

Began at the South East  
 corner of Section 30, T. 3, N. R.  
 31 E. - (Var 19° 30' E. run thence  
 North on East boundary of

Township 5<sup>th</sup> N R 30 E 153A

Field notes of the exterior  
boundary lines of Township  
No 5 North of range No 30 East  
of the Willamette Meridian,

Chonis

September 17<sup>th</sup>

West boundary T 5 N R 30 E  
Beginning at the S.E. Corner  
of T 3 R 29, S.W. Corner of  
T 5, R 30 on the 1<sup>st</sup> Standard  
Parallel North,

Nov 19<sup>th</sup> 31<sup>st</sup> E

North on the west boundary of  
Sections 31, T 5 R 30

40.00 Set Charred Stake with  
round trench and pits  
as per instructions for  
Section Corner,

80.00 Set Charred Stake with  
round trench and pits  
as per instructions for Corner

154 154A<sup>14</sup>

## West-Boundary

Cham's

to Secs 30 & 31, T5, R30  
and Secs 25 & 26 T3 R  
29E - Var 19°30'E -  
Sand rolling. Soil 2<sup>o</sup> rate

---

North on line between Secs 30 R. 31  
& 25 R 29.

40.00 Set charred stake with  
mound trench and pits as  
pr. instructions for gr. section  
corner.

48.00 Top of hill descending towards  
the Columbia river. Height  
about 600 feet.

64.50 Indian trail (N 45° W)

80.00 Set charred stake with  
mound trench and pits as  
pr. instrs. for corner to Secs  
19 & 20 R 30 E and 24 & 25  
R 29 E. - Var 19°39'E  
Soil sandy. Soil 3<sup>o</sup> rate

---

Township 3<sup>rd</sup> N R 30 EChains

North on line between Secs 19 R  
30 & 24, R 29 E -

40.00 Set Charred Stake with mound  
trench and pits as per instrs,  
for q.r. Sec. Corner.

80.00 Set Charred Stake with mound  
trench and pits as per instrs,  
for corner to Secs 18 & 19 R 30  
and 13 & 24 R 29 E.

Var 19° 39' E

Soil 2<sup>o</sup> rate.

North on line between Secs 18 R 30 & 13  
R 29 E.

31.50 Ascend Rocky bluff, bank  
about 25 feet in height, E & W.

40.00 Set Charred Stake with mound  
trench and pits as per instrs,  
for q.r. Sec. Corner.

80.00 Set Charred Stake with mound  
trench and pits as per instrs,  
for corner to Secs 7 & 18 R 30



156 156A 14

West-Boundary

Chains

and 12813 R29E -

(Var 19° E -

This mile sandy and rough.  
Some sage brush.

---

North on line between Secs 7 R30  
and 12 R29E.

8.00 Trail N 70° E.

8.18 Edge of Slough. Bluff bank  
about 40 feet in height.

Set Charred Stake with mound  
trench and pits for meander  
corner.

Set up flag for object to tri-  
angulate to from the north  
side of Slough.

Regain the line on the North  
bank of Slough, offset 2.00  
chains due west, object on  
South bank bears south  
12° 24' East making the