

Field Notes of the Resurvey
of Exterior boundary lines of Townships
4 North of Range 27 East Township
5 North, Ranges 31 & 32 East and
fractional Townships, 6 North of the
Base line of Ranges 31, 32 & 33 East
of the Willamette Meridian, executed
by Nicholas O. Walden, Deputy
Surveyor under his contract No
209, bearing date the 6th day of
July 1874.

Commenced Oct. 23^d 1874.

Completed Decemb. 9th 1874.

Index.

Referring the lines to the pages of the Field notes

T. S. N. R. 31 C.

8.	7.	7.	7.	6.	6.	
6.	5	4.	3	2	1	6.
					12	5
					13	5
					24	5
					25	4.
31	32	33	34.	35	36	4
8	8	9	9	9	9.	

Index:

Referring the lines to the pages of the Field notes

T. 5. N. R. 32. E.

6	5	4	3	2	1	12
					12	11
					13	11
					24	11
					25	10
31	32	33	34	35	36	10
14	14	15	15	15	15	

Index:

Referring the lines to the pages of the Fieldnotes.

J. H. N. R. 27. C.

				27	27.
25	6.			2	1. 21.
24.	7				12. 20
23	18				13. 20
23	19.				24. 19
22	30.				25. 19
22	31.				36. 18.

Resurvey of the Exterior Boundaries of Township

After surveying the Subdivisional lines of the Eastern tier of sections in Township 5 North of Range 31 East and finding that I could not close within the required limits to all the corners on the East boundary of the Township and to the corner to Secs. 1 + 2 in the North boundary I began at ~~at~~ the Standard corner to Townships No. 5 North of Ranges 31 + 32 East and run

North on a blank line along the East boundary of Sec. 36
 T. 5 N. R. 31 E.

- 40.37 A point 37 lks. West of the $\frac{1}{4}$ Sec. Cor.
- 80.00 A point 115 lks. South and 45 lks West of the corner to Secs. 25 + 36

North on a blank line along the East boundary of Sec. 25
 Var. $21^{\circ} 00'$ East

- 41.65 A point 45 lks. West of the $\frac{1}{4}$ Sec. Cor.
- 80.00 A point 215 lks. South and 78 lks.

57

5 North, Range 31 East - Will. Mer. Oregon

West of the corner to Secs. 24 & 25

North on a blank line along the East boundary of Sec. 24
Var. $20^{\circ}30'$ East

42.59 A point - 9 lks. West of the $\frac{1}{4}$ Sec. Cor.

80.00 A point 311 lks South and 13 lks East of
the corner to Secs. 13 & 24

North on a blank line along the East boundary of Sec. 13
Var. 22° East:

43.52 A point - 18 lks. West of the $\frac{1}{4}$ Sec. Cor.

80.00 A point - 369 lks. South and 1 link East
of the corner to Secs. 12 & 13

North on a blank line along the East boundary of Sec. 12
Var. $21^{\circ}30'$ East.

44.09 A point - 105 lks. East of the $\frac{1}{4}$ Sec. Cor.

80.00 A point - 445 lks. South and 120 lks East
of the corner to Secs. 1 & 12

6. 8
Resurvey of the Exterior Boundaries of Township

North on a blank line along the East boundary of Sec. 1
Var. $22^{\circ} 06'$ East.

44.77 A point - 65 lks. East of the $\frac{1}{4}$ Sec. Cor.

81.07 A point - 291 lks East of the corner to
Townships 5 and 6 North, Ranges 31
and 32 East

From the established corner to Townships
5 and 6 North, Ranges 31 + 32 East -
A run

West on a blank line along the North boundary of Sec. 1
Var. $20^{\circ} 30'$ East

40.41 A point - 58 lks, North of the $\frac{1}{4}$ Sec. Cor.

80.00 A point - 86 lks East and 58 lks.
North of the corner to Secs. 1 & 2

West on a blank line along the North boundary of Sec. 2
Var. $21^{\circ} 00'$ East

41.05 A point - 39 lks. North of the $\frac{1}{4}$ Sec. Cor.

80.00 A point - 123 lks. East and 88 lks. North
of the corner to Secs. 2 & 3

List of Names

A list of the names of the individuals employed to assist in running, measuring and marking the lines and corners described in the foregoing field notes of the resurvey of the Exterior Boundary lines of Townships 4 North of Range 27 East, Townships 5 North of Ranges 31 & 32 East and Fractional Townships 6 North of the base line of Ranges 31, 32 & 33 East of the Willamette Meridian showing the respective capacities in which they acted.

Rufus S. Moore	Chairman
Henry Meldrum	Chairman
William H Cooper	Assessor

We hereby certify that we assisted
 Nicholas O. Madden, Deputy Surveyor in
 resurveying the Exterior boundary line
 of fractional Townships No. 6 North of
 the Ranges Nos. 31, 32 and 33 East of
 Townships No. 5 North, Ranges Nos 31 and
 32 East, and Township No. 4 North of
 the base line of Range No. 27 East of
 the Willamette Meridian in the capaci-
 ties indicated by our respective signa-
 tures, and that said Exterior bound-
 ary lines have been in all respects
 to the best of our knowledge and belief
 well and faithfully surveyed and
 the boundary monuments placed accord-
 ing to the instructions furnished by
 the Surveyor General.

Rufus S. Moore Chairman
 Henry Melvin Choquian
 William H. Cooper Clerk

Subscribed and sworn to before me a Notary
 Public, this 12th day of December 1874

John W. Eldrum
 Notary Public

John W. Eldrum
 Notary Public

U.S. Surveyor General's Office
Eug. Portland Oregon
June 23^d 1875

The foregoing field notes of the survey ~~made~~
the Re-Survey of the Exterior lines of T 4 N
R 27 E Will. Mer. Oregon and of the
Standard Parallel in R 27 E have
executed by N. O. Walden U.S. Deputy
Surveyor having been critically ex-
amined the necessary corrections and
explanations made the said field
notes and the surveys they describe
are hereby approved

Ben Simpson
Sur Gen of Or.

33

I Nicholas O. Walden, Deputy Surveyor do solemnly swear that in pursuance of a contract with Benjamin Simpson U.S. Surveyor General for the State of Oregon bearing date the 6th day of July 1874, and in strict conformity to the laws of the United States and the instructions furnished by the said Surveyor General, I have faithfully resurveyed the Exterior Boundaries of Township 4 North, Range, 27 East; Townships 5 North, Ranges 31 + 32 East and ~~Townships~~ Townships 6 North of the base line of Ranges 31, 32 and 33 East of the Willamette Meridian in the State aforesaid, and do further solemnly swear that the foregoing are the true and original field-notes of such Survey.

Nicholas O. Walden
Deputy Surveyor

Subscribed and sworn to by the above named Nicholas O. Walden, Deputy Surveyor before me a Notary Public on this the 12th day of December 1874

John W. Meldrum
Notary Public.

Meldrum
Notary Public