

# Index

To the Field notes of the Exterior  
 line of Township No 5<sup>th</sup> North,  
 of Base Line in Range No 31  
 East of Willamette Meridian,

|    |    |    |    |    |    |    |
|----|----|----|----|----|----|----|
| 24 | 24 | 25 | 26 | 26 | 27 |    |
| 6  | 5  | 4  | 3  | 2  | 1  | 22 |

---

12 21

---

13 21

---

24 20

---

25 19

---

36 19

---

Township 5 North Range 31, East,  
 Ravine Course West from  
 Charred Stake Bug Pit  
 raised mound as per  
 instructions.

8000 Set Post Corner for Secs 1, 12,  
 604. On top of High Hill  
 drove Charred Stake Bug Pit  
 raised mound as per instructions,  
 Sand broken good grass  
 Soil 2<sup>o</sup> Kali.

North on East Bound of Sect.  
 Town 5 North Range 31, East,  
 Variation 21<sup>o</sup> East.

4000 Set 1/4 Sec Post on top of Ridge  
 sloping to West. Drove  
 Charred Stake Bug Pit  
 raised mound as per  
 instructions.

8000 Set Post Corner for Townships  
 5 & 6 North Ranges 31 & 32,  
 Secs 1, 6, 31 & 36, on Flat.

23  
645 ~~543~~

Township 5 North Range 31 East,  
Drove Charred Stake Wagon Pit  
raised Mound as per Instructions,  
Sand Broken Grass good,  
Soil 2<sup>o</sup> Rate,

May 11<sup>th</sup> 1865

Went on Random Between  
Townships 5 & 6, North Range 31, East  
Variation 21<sup>o</sup> East.

At 40 & 80 Set 1/4 & Mile Posts,  
480, Not finding Township Corner  
Character of Land being such  
as to render it difficult to make  
Permanent Corner, I therefore  
conclude that the Original  
Town Corner has been removed  
or destroyed, Hence I set Corner  
for Townships 5 & 6, North Range  
30 & 31, In Basin Low Sand  
Hills Surrounding, Drove  
Charred Stake, Wagon Pit  
raised Mound as per  
Instructions,

Township 5 North Range 31, East,  
 Thence East on North Boundary  
 of Sect. Town 5 North Range 31, E,  
 Var.  $18^{\circ} 25'$  East

40.00 Set  $\frac{1}{4}$  Sec Post. Top of steep  
 Sand Hill drove Charred  
 Stake. Dug Pit & raised  
 Mound as per Instructions.

80.00 Set Post Corner for Secs 8 & 16,  
 31 & 32, on Flat. Drove Charred  
 Stake. Dug Pit & raised  
 Mound as per Instructions.  
 Sand Broken grass Poor  
Soil 3" Rate.

East on North Boundary of Sec  
 5, Town 5 North Range 31, East,  
 Variation  $20^{\circ} 30'$  East.

40.00 Set  $\frac{1}{4}$  Sec Post on Top of  
 Hill about 400 ft high,  
 drove Charred Stake. Dug  
 Pit & raised Mound as per  
 Instructions.

Township 5 North Range 31 East,  
 8000 Sec Post Corner for Sec 4, 5,  
 32 + 33. On Side Hill Sloping  
 North West. Drove Charred  
 Stake dug pit raised  
 Mound as Per Instructions.  
Sand Rolling Soil 3<sup>rd</sup> Rate.

East on North Boundary of Sec  
 4 Town 5 North Range 31 East,  
 Variation 21<sup>o</sup> East.

8000 Sec 4 Sec Post. Drove Charred  
 Stake dug pit raised  
 Mound as Per Instructions.

8000 Sec Post Corner for Sec 3, 4,  
 33 + 34. North West Side of Ravine  
 Course South West. Drove  
 Charred Stake. Dug pit  
 raised Mound as Per  
 Instructions. Sand Rolling  
 Soil Sandy. 3<sup>rd</sup> Rate.

Range 31, East,

Township 5 North, Boundary of Sec 3  
East on North Boundary of Sec  
3, Township 5 North Range 31, East,  
Variation 21° East,

4000 Set 1/4 Sec Post Wroove Charred  
Stake, Dug Pit, raised  
Mound as Per Instructions,

8000 Set Post Corner for Secs 2, 3,  
34, & 35 on Top of Hill  
Sloping to the South West,  
Wroove Charred Stake  
Dug Pit, raised Mound  
as Per Instructions,

Land Broken, some grass  
and Sage Brush, Soil 3<sup>rd</sup>  
Rate,

East on North Boundary of Sec.  
2, Town 5 North Range 31, East,  
Variation 21° East,

4000 Set 1/4 Sec Post on Top of Hill  
Wroove Charred Stake, Dug  
Pit, raised Mound as Per

Township North Range 31, East.  
Instructions.

8000 Set Post Corner for Secs 1, 2,  
35 & 36, on South Side of  
Prairie, corner West. Wood  
Charred Stake Nug Pit  
raised mound as per  
Instructions.

Sand Broken grass of poor  
Soil Sandy 3<sup>rd</sup> Rate.

East on North Boundary of Sec  
1, Town North Range 31, East.  
Variation 21° East.

4000 Set 4 Sec Post on side Mill  
Slapwing, to the North, Wood  
Charred Stake, Nug Pit  
raised mound as per  
Instructions.

8000 Set Post Corner Townships  
5 & 6, Ranges 31 & 32, etc.  
Sand Broken, some grass  
Soil 2<sup>nd</sup> Rate.

The lands in this Township are high and broken soil excepting the N.W. Corner is good 2<sup>nd</sup> rate, producing a fine growth of Grass.

Water is scarce but can be obtained by sinking wells. There is no timber whatever.

Yet the day is not far distant when stock raisers will occupy these lands because of the excellent Grass and its nearness to Market.

The survey of the Exterior lines were made, as set forth in affidavit duly made out, by Deputy W. H. Odell

Walter W. Johnson Copassman  
 C. C. Harcum Chairman  
 and



651 <sup>29</sup>  
~~549~~

A Shibles Chairman  
William Warren Axeman

I W. H. Bell do hereby certify that  
the foregoing are the true and  
original field notes of the Exterior  
lines of Township No. 5 N. Range  
No. 31 East of Willamette Meridian  
as made under contract No. 110  
with B. J. Penner surveyor general,  
according to Affidavit made  
at the close of said contract  
which appear after the field  
notes and general remarks for  
Township No. 5 North of Range  
No. 31 East of Willamette Meridian  
William H. Bell  
Deputy Surveyor

624

Surveyor General's Office  
Eugene City, Aug. 23<sup>d</sup> 1865

The foregoing field notes of the Survey of the Exterior  
lines of ~~Tps. 4 N. R. 31, 32, 33, & 4 East; and of~~  
Tp 5 N. Ranges 31, 32 and 36 East; and of  
Tp 6 N. Ranges 34, 35 and 36 East, Will. Mer,  
Oregon, Executed by Odell and Lewis under contract  
No. 110 bearing date February 7<sup>th</sup> 1865, having  
been critically examined, the necessary explanations  
and corrections made, the said field notes and  
the surveys they describe are hereby approved.

E. L. Applegate  
Surveyor General.