

Index

9	10	10	11	12	12	13	14	15	15	16	17	17	18
31	32	33	34	35	36	31	32	33	33	35	36	31	32
Sections													
Range 31 East													
Range 32 East													

18	20	20	21	22	23	24	24	25	26	27	28	29	30
33	34	35	36	39	32	33	34	35	36	31	32	33	34
Range 33 East													
Range 34 East													
Range 35 East													

34	32	33	34	34	35	36	36	37	38	40	40	41	42
35	36	37	32	33	34	35	36	31	32	33	34	35	36
Range 36 East													
Range 37 East													

copying this

445

6 446

We William H. Odell and William S. Lewis, having been appointed deputy Surveyors of the lands of the United States in Oregon, do solemnly swear that we will well and faithfully, and to the best of our skill and ability, execute the duties confided to us pursuant to a contract with B. J. Pengra, surveyor general of the public lands in Oregon bearing date the seventh day of February 1865 according to the laws of the United States and the instructions received from the said surveyor general.

William H. Odell,
William S. Lewis,

State of Oregon }
County of Washtilla } ss

sworn and subscribed
to before me this 13th day March
1865-

J. W. Northrup
A Justice of the Peace

447
7

We Cyrus Dixon and D. C. Wallace
do solemnly swear that we will
faithfully execute the duties of
chain carriers; that we will level
the chain upon uneven ground,
and plumb the tally pins,
whether by sticking or dropping
the same, that we will report
the true distance to all notable
objects, and the true length of
all line that, ^{we} assist in measuring,
to the best of our skill and ability

Cyrus Dixon
D. C. Wallace

State of Oregon }
County of Wmatilla } ss Sworn and
subscribed to before me this
13th day of March 1865

J. W. Northrup
A Justice of the Peace

448

~~8~~ 348

I Robert Cook do solemnly
swear that I will well and
truly perform the duties of
Axeman, according to instruc-
tions given me, and to the
best of my skill and
ability.

Robert Cook

State of Oregon }
County of Yamhill } 38 Sworn
and subscribed to before
me this 13th day of
March 1865.

J. W. Northrup
A Justice of Peace

March 15th 1865.

Commenced the survey of the first
Standard Parallel North of Base Line
and East ~~between~~ ^{through} Ranges 31. 32. 33.

34. 35. 36 & 37. between Township 4 & 5

North, at the North East Corner of
Township No 4 North in Range No 30

East of Willamette Meridian, Thence

East on South boundary of section

31 Town ^{5th} North in Range 31 East,

Variation 20° East.

40.00 Set Standard corner for 1/4 sec,

Drove charred Stake and dug
Pit & constructed Mound as per
Instructions

73.00 Dry Gulch course North West 100

80.00 Set post ^{Standard} corner for sec 31 & 32. 60

Drove charred Stake and raised
Mound with pits as per Instruction

This line passes over Rolling
grounds good grass see
Timber Soil 2nd Rate

456
70

East on South boundary of Sec 32
Township 5 N. Range 31 E.

Variation 20° E.

4000 Set Standard corner for 1/4 Sec, +
40

Drove charred Stake and raised
Mound with Pits as per
Instructions

8000 Set Standard corner for sections

32 & 33. on level, Drove charred
Stake and raised Mound with
Pits as per Instructions.

This line passes over
Rolling ground, good good
Soil 2nd Rate

East on South boundary of sec
33 Township 5 N. Range 31 East
Variation 20° East,

4000 Set Standard corner for 1/4 Sec

Drove charred Stake and
raised Mound as per Instructions

First Standard Parallel North Between T485 R31E,

8000 Set Standard corner for sections 33 & 34 on land sloping to the South East, Drive Charred Stake and raised Mound with pits as per Instructions.

Land Crokers good Grass Soil 2nd Rate.

East on South boundary of sec 34 Township No. 5 N. Range 31 East Bear, 20° East.

16.50 Trail course North East in Canyon

100

40.00 Set Standard cor. for 1/4 Sec. Drive Charred Stake and raised Mound with pits as per Instructions

75

58.00 Trail in deep Canyon course N.W. 100

80.00 Set first Standard corner for sections 34 & 35 - Drive Charred Stake and raised Mound with pits as per Instructions.

~~12 352~~ 452

First Standard Parallel North
This line passes over broken
land good grass 2nd Rate

East on South boundary of sec,
35 Township No 5 N Range 31 E,
Bar. 20° East,

40.00 Set post Standard corner for 1/4 Sec
Drove charred Stake dug pits
and raised Mound as per
Instructions,

80.00 Set post corner for sections 30
35 & 36, on steep hill side sloping
the North West, Drove charred
Stake, dug pits, and raised
Mound as per Instructions,
Land Broken good
grass 2nd Rate,

East on South boundary of section
36 Township No 5 N Range 31 E,
Bar 21° East,

Between T. 495 N in Range 31 East of Will. Mer.

40.00 Set post Standard Cor, for 1/4 Sec.

Drove charred Stake, dug pits and raised Mound as per Instructions

80.00 Set post Standard corner for 80⁺

Townships N. 5 North in Ranges

31 & 32, also sections 36 & 31.

Drove Charred Stake, dug pits and raised mound as per Instructions.

This line passes over land high and rolling good grass soil 2nd Rate

Thursday March 16th 1865.

East on South boundary of Sec,

31. Township N. 5 N. Range 32 East.

Bar 21st E.

40.00 Set post Standard corner for

1/4 Sec. Drove charred Stake dug pits & raised Mound as per Instructions.

80.00 Set post Standard corner for

Townships 4+5 north In Range 34 East.

Fir Tree 20 inches in diam N. 24° 31' E. 19 Sinks

Fir Tree, 10 do do do S. 4° 30' W. 80 do

Fir Tree 8. do do do N. 73° W. 60 Sinks.

This Line Passes through Heavy
Timber Fir, Pine & Larch.

Undergrowth Same & Vine
Maple. Land gently rolling.

This Standard line passes
over high rolling lands
covered with good grass
along the whole extent
affording an extensive
range for stock, But
from the fact that water
is scarce over most of the
distance the land will
not be considered very
valuable until enterprise
shall sink wells to
give water to stock,

which can be done
 at very little expense,
 The timbered lands
 in the Mountains
 are considered valuable
 and would soon be
 entered by the settlers
 in the Valley if offered
 at public or private
 sale.

The Standard Parallel of
 which the foregoing are the
 field notes was surveyed
 Deputy W. H. Odell assisted
 through Ranges 31, 32, 33, 34, 35
 & 37 by Cyrus Dixon } Chairman
 D. C. Wallace }
 Robert Cook } Axeman
 Through Range 36 by
 W. W. Johnson Compassman
 C. C. Harcane } Chairman
 A. Shibles }
 William Warren Axeman

I William H. Odell, do hereby certify that the foregoing are the true and original field notes of the survey of the First Standard Parallel North between Townships 5 & 6 North and East through Ranges 31, 32, 33, 34, 35, 36 & 37, East of Willamette Meridian, made under contract No. 110, bearing date February 7th 1865, in accordance with the laws of the United State and the Instructions furnished by the Surveyor General, as will appear from affidavits duly made out and attached to the field notes of Township No. 5 North of Range 36 East of Will; Mer;

William H. Odell

Deputy Surveyor

Surveyor General's Office
Eugene City, Aug. 23, 1865

The foregoing field notes of the survey of
the 1st Standard Parallel North through
Ranges 31, 32, 33, 34, 35, 36 and 37 E
Will. Mer. Oregon, executed by Odell &
Lewis, Deputy Surveyors, under their con-
tract No. 110, bearing date Feby. 7th
1865, having been critically examined
the necessary explanations and corrections
made, the said field notes and the sur-
veys they describe are hereby ap-
proved.

E. L. Applegate
Surveyor General of Oregon.