

Index

Referring the lines to the pages in the field notes

Township 4 N. Range 31 E. Will. Mex.

6	40	5	30	4	23	3	17	2	10	1
40		39		29		23		16		9
7	38	8	29	9	22	10	15	11	8	12
38		37		28		22		15		8
18	37	17	28	16	21	15	14	14	7	13
36		35		27		20		13		6
19	35	20	27	21	20	22	13	23	6	24
34		33		26		19		12		5
30	33	29	26	28	19	27	12	26	4	25
32		31		25		18		11		4
31	31	32	24	33	17	34	11	35	3	36



Field notes of the Subdivision  
lines of Township number 4,  
North of the Base Line of Range  
31 East of the Willamette Meridian

From corner to sections  
1. 2. 35 & 36 on south boundary  
I. run

North between sections 35 & 36.

40,000 Set post corner for 1/4 section  
drove charred stake, dug  
pit and raised mound  
as per instructions

80,000 Set post corner for sections 25. 26  
35 & 36, drove charred stake, dug pit  
and raised mound as per  
instruction,

Land broken, grass good,  
soil 2<sup>d</sup> rate.



10 2360

Township No 4 North Range 31. East Will-Mer-

drove charred stake, dug, pits, and raised mounds as per instructions

7,90 To post corner.

40

Land broken, grass good

X Soil 2<sup>nd</sup> rate,

North between sections 142.

40,00 Set post corner for 14 section, on.

+40

Summit of bridge course S.W.,

drove charred stake, dug pits, and raised mound as per instructions

80,50 Intersect first Standard Parallel North 10 lbs west of post,

corner for sections 35 & 36,

T 5 N, R 31 E,

at point of intersection

set post closing corner for sections 142, drove charred

stake, dug pit and raised mound as per instructions

Land broken, grass good, Soil 2<sup>nd</sup> rate,



Township 4 North, Range 31 East, Will Met 367<sup>17</sup>

North between sections 2 & 3.

40.00 Set 1/4 section post corner,  
above charred stake dug pit,  
and raised mound as per  
instructions.

67.50 Bottom of Ravine course N, W, 80

80.39 Intersected 1<sup>st</sup> Standard Parallel 75<sup>+</sup>

North 22 links West of Post  
Corner - for section 34 & 35 - T. 5 N.

R. 31 E. Set post closing corner  
for sections 2 & 3, above charred  
stake dug pit and raised mound  
as per instructions.

Land broken, grass good,

Soil 2<sup>nd</sup> rate -

August 11<sup>th</sup> 1866.

X

North between sections 33 & 34.

2.00 Ravine course N W 10

40.00 Set post corner for 1/4 section +  
20

above charred stake, dug pit,  
and raised mound as per

X



12 Township 4 North, Range 31 East, Will-Mer-  
 and 10., on level, drove charred  
 Stake dug pits and raised mound  
 as per instructions,  
 Land broken, grass good  
 Soil 2<sup>nd</sup> rate,

+

East on random between section 34~~40~~  
 Bar 20 East,

40.00 Set temporary 1/4 section post corner,  
 50.28 Intersected North and south line 34 the  
 north of post corner.

N 89° 45' W on true line

40.14 Set post corner for 1/4 section, on 30  
 land sloping to the West,  
 drove charred stake, dug pits,  
 and raised mound as per  
 instructions

80.28 To Post Corner — 20  
 Land broken Soil 2<sup>nd</sup> rate,

+

North between sections 344-

40.00 Set 1/4 section post corner, drove



24 374

Township 4 North, Range 31 East Will-Mer-

Charred stake dug pits and raised mound as per instructions,

80.05 Intersected of first Standard Parallel North 28 lbs West of Post Corner for sections 33 & 34 T 5 N R 31 East, at point of intersection set post Closing Corner for sections 3 & 4. Above Charred stake dug pits, and raised mound as per instructions,

Soil broken grass good

Soil 2<sup>d</sup> rate,

X

August 11<sup>th</sup> 1866-

North between sections 32 & 33

40.00 Set post corner for 1/4 section,

on land sloping to the N.W. Above Charred stake, dug pits, and raised mound as per instructions,

59.00 Bottom of ravine course N.W.

20 X



30 380

Township 4 North Range 31 East. Will-Mer-  
Car 20° East

4000 Set temporary 1/4 section post corner,

80,26 Intersected North and south line 58  
links North of post corner,  
N 89° 35' W on true line,

40,13 Set post corner for 1/4 section 37

Above charred stake dug pit  
and raised mound as per instructions

80,26 To post corner -

Land broken, grass good, 20

+ Soil 2<sup>nd</sup> Rate,

North between sections 445,

4000 Set post corner for 1/4 section. Above  
charred stake, dug pit, and  
raised mound as per instructions

79,82 Intersected 1<sup>st</sup> Standard Parallel  
North 52 links West of Standard  
Corner for sections 32 & 33 T. 5 N. R. 31 E.

Set Closing corner at point  
of intersection, for sections 445,  
Above charred stake, dug pit



38,31

Township 4 North Range 31 East Will-Mer=  
and raised mound as per instructions  
Land broken good grass  
Soil 2<sup>d</sup> rate,  
August 12<sup>th</sup> 1866.

North between sections 31 & 32,  
40.00 Set post corner for 4 section (on level)  
drove charred stake dug pit and  
raised mound as per instructions  
80.00 Set post corner for sections  
29, 30, 31 & 32, on land sloping to  
the North West, drove charred  
stake dug pit and raised mound  
as per instructions.  
Land rolling good grass  
Soil 2<sup>d</sup> rate,

East on random between sections  
29 & 32,  
Bar 20° East,  
40.00 Set temporary 1/4 section post corner  
80.15 Intersected North and South line



40 390

Township 4 North, Range 31 East Will, Mer,

West on random between sections

6 & 7.

40.00 Set temporary  $\frac{1}{4}$  section post corner

79.43 Intersected North and south line

25 links North of post corner

$N 89^{\circ} 41'$  East on true line,

39.43 Set post corner for  $\frac{1}{4}$  section

above charred stake, dug pits  
and raised mound as per  
instructions,

79.43 To post corner.

Land broken, grass  
good Soil 2 $\frac{1}{2}$  rate,

North between sections 5 & 6,

40.00 Set post corner for  $\frac{1}{4}$  section

above charred stake dug  
pits and raised mound  
as per instructions,

61.00 Bottom of Parvin course  $N 75^{\circ}$

79.61 Intersected <sup>75</sup> Standard Parallel

North 76 links West of Post



Township 4 North, Range 31 East, Will. Mer - <sup>391</sup>  
Standard corner for sections 31 & 32

T 5 N R 31 E, at point of intersection  
set Closing corner for sections 5 & 6  
above charred stake dug pit, and  
raised mound as per instructions

Land broken, good  
grass, Soil 2<sup>d</sup> rate,

The lands of this Township  
are well set with rich bunch  
grass, affording extensive and  
excellent range for stock,

There is water in the N. E.

Corner of the Township, standing  
in holes during the dry season  
But with little labor could  
be so arranged as to afford a good  
supply of water for a large amount  
of stock, Timber is wholly wanting  
and agricultural lands can be found  
only in very limited quantities,  
August 14<sup>th</sup> 1866



A list of the names  
of the persons employed to assist  
in running measuring or  
marking the lines and corners  
described in the foregoing field  
notes of Township No 4 North  
of the Base Line of Range 31 East  
of Willamette Meridian, showing  
the respective capacities in  
which they acted;

J. J. Henderson }  
John A. Rigg } Chainmen  
P. M. Denney }  
A. A. Auman



We hereby certify that we assisted William  
 H. Odell, deputy surveyor, in subdividing  
 Township No. 4 North of Range 31 East  
 of Willamette Meridian, and that  
 said Township has been in all respects  
 to the best of our knowledge and belief  
 well and faithfully surveyed and  
 the boundary monuments planted  
 according to the instructions furnished  
 by the Surveyor General,

J J Henderson	Chairman
J A Prigg	Chairman
J P M. Demney	Member

State of Oregon }  
 County of Umatilla } S.S. Subscribed  
 and sworn to before me this  
 22 day of September 1866.

William Luccallen, Justice of the Peace



J. William H. Odell,

395

deputy, surveyor, do solemnly swear that in pursuance of a contract with E. L. Applegate surveyor of the public lands of the United States in the State of Oregon, bearing date July 2<sup>nd</sup> 1866, and in strict conformity to the laws of the United States and the instructions furnished by said Surveyor General, I have faithfully surveyed the subdivisional lines of Township No. 4 North of Range 31 East of Willamette Meridian in the State aforesaid and do further solemnly swear that the foregoing are the true and original field notes of such survey.

William H. Odell

State of Oregon }  
County of Lane } ss Subscribed and  
sworn to before me this 22<sup>nd</sup> day  
of December 1866.

Joel Ware

Notary Public



Surveyor General's Office  
 Eugene City January 11<sup>th</sup> 1867

The foregoing field notes of the  
 of the ~~subdivision~~ <sup>subdivision</sup> lines  
 Survey of Township No 4 North  
 Range 31 East Will. Mer. Oregon  
 executed by William H. Odell Dept.  
 Surveyor under his contract No  
 114 bearing date July 2nd, 1866  
 having been critically examined  
 the necessary corrections and expla-  
 nations made the field notes and  
 the Survey they describe are hereby  
 approved

E. L. Applegate  
 Surveyor General of Oregon