

Field Notes of the Subdivision
Lines in Township No 5 N R 30
E of the Willamette Meridian in
the State of Oregon, Surveyed by
Leopoldus S. Payne deputy Surveyor
under his contract No 1000 dated
August 1st 1861

Box 20-

Commenced September 18th 1861
Completed September 25th 1861

page 5
" 7
" 13
" 18
" 20
" 22
" 29
" 30
" 31
" 35

Payne
No. 1000

220

220

Index

Subdivision Lines in Township
No 5. N R 30 E

<i>Columbia River</i>									
6	5	5	4	4	3	10	2	7	1
34	35	25	18	12	7				
7	33	8	24	9	10	12	11	6	12
32	32	24	17	11	6				
18	31	17	23	16	17	15	11	14	5
31	30	23	16	10	4				
19	29	20	22	21	16	22	10	23	3
29	28	21	15	9	3				
30	28	29	31	28	15	27	9	26	2
27	27	20	14	8	2				
31	26	32	10	33	14	34	3	35	36

Township 5 N R 30 E W. 11.

Chain

48.00 Bottom of Ravine about 250 feet
deep Course west,

55.00 Top of Hill.

80.00 Set Charred Stake with mound
trench and pits as per notes
for corners to Secs 23, 24, 25, 26

Bar $19^{\circ} 30' E$

Land broken. $\text{Loc } 3^{\circ} \text{ rate}$

East on random between Secs 24, 25

40.00 Set limp 14 sec corner.

79.84 Antiseptic Town line 13 Chs North
of post corner to Secs 24, 25

$N 89^{\circ} 55' W$, on true line between Secs 24, 25

5.10 Indian trail, Course North.

39.92 Set Charred Stake with mound
trench and pits as per notes
for 14 sec corner.

79.84 Corner to Secs 23, 24, 25, 26

North on line between Secs 23, 24

224

H

224

Subdivision Lorus

Chains

40.00 Set charred stake with
mound trench and pits
as per instr for 1/4 sec corner.

80.00 Set charred stake with
mound trench as pits as per
instr for corner to secs
13, 14, 23, 24

Cor 19° 45' E

Soil 2^o rate

East on random distance to sec 13, 24

40.00 Set 1/4 sec corner.

78.00 Intersect town line 60 chs
North of post corner to
secs 13, 24.

This being 2.00 chains
short of the proper length
we resun East line of
Sec 24 and find that it
bears on the North half
mile S 24° E and on the
South half mile S 2° 15' E

Township 5 N R 30 E T. 11.

Chains

which shows section 24 to
close within limits.

We therefore run

~~889°33'N~~ on true line between secs
13. 24.

37.00 Indian trail North

39.00 Set Chained stake with mound
trench and pits as per notes
for 1/4 sec corner.

78.00 Corner to secs 13, 14, 23, 24
true 2° rate

September 19th

North on line between secs 13. 14

40.00 Set Chained stake with mound
trench and pits as per notes
for 1/4 sec corner.

57.00 Indian trail N 45° W

70.00 Set Chained stake with mound
trench and pits as per notes
for corner to secs 11, 12, 13, 14

(Nor 20° 15' E

226

6

226

Subdivision Lines

Chains

- East on random between secs 12, 13 - 40.00 Set temp 1/4 sec corner.
 - 78.00 On intersect sec line 70 links North of corner to secs 12, 13 $N 89^{\circ} 30' W$, on true line between secs 12, 13.
 - 39.03 Set charred stake with mound trench and pits as per notes for 1/4 sec corner.
 - 78.00 Corner to secs 11, 12, 13, 14 - true 2^o rate
-

- North on line between secs 11, 12, 40.00 Set charred stake with mound trench and pits as per notes for 1/4 sec corner.
 - 80.00 Set charred stake with mound trench and pits as per notes for corner to secs 1, 2, 11, 12 $N 20^{\circ} E$ true 2^o rate
-

Township 5 N R 30 E T 11 S

Chains

East on random between Secs 1, 12

40.00 Set Iron $\frac{1}{4}$ sec corner.

78.50 Intersect Iron line 50 links

North of post corner to Secs 1, 12.

$N 89^{\circ} 39' 11''$ on true line between Secs 1, 12

39.25 Set Charred Stake with mound
pinch and pits as per notes for
 $\frac{1}{4}$ sec corner.

78.50 Corner to Secs 1, 2, 11, 12.

Soil 2^d rate

Closing corner in sight - run

North $1^{\circ} 21' 11''$ on true line between
Secs 1, 2

25.00 Begin to descend Hill.

40.00 Set Charred Stake with mound
pinch and pits as per notes
for $\frac{1}{4}$ sec corner.

79.50 Intersect Iron line at post
corner to Secs 1, 2, 3 and 35.

36 T 6 N R 30 E -

Soil somewhat sandy - 2^d rate

List of Names

A list of the names of the individuals employed to assist in running measuring or marking the subdivision lines and corners described in the foregoing field notes of Township No 5 North of Range No 30 East of the Willamette Meridian showing the respective capacities in which they acted.

John Brattain, Channimer
William B. Penger, Channimer
John L. Luckey, Axeman

I hereby certify that the
assisted by George S. Payne

560

260

deputy surveyor. in surveying
the subdivision lines in
Township No 5 North Range
30 East of the Willamette
Meridian and that said
Township has been in all
respects to the best of our
knowledge and belief well
and faithfully surveyed
and the boundary monuments
planted according to the
instructions furnished by
the Surveyor General.

John Brattain, Chairman
W. B. Rogers - Chairman
John L. Buckley, Assessor.

Subscribed & sworn by the above named
persons before me, a Justice of the Peace in
& for the County of Lane, State of Oregon
this 1st day of November A.D. 1861

R. St. Parsons
Justice of Peace

I, Golshus S. Payne deputy Surveyor
do solemnly swear that in pursuance
of a contract with B. J. Pengra Surveyor
of the public lands of the United States
in the State of Oregon bearing date the
first day of August 1861, and in strict
conformity to the laws of the United States
and the instructions furnished by the
said Surveyor General I have faithfully
surveyed the subdivision lines in
Township No 5 North of the base line
of Range No 30 East of the Willamette
Meridian in the State of Oregon,
and do further solemnly swear
that the foregoing are the true and
original field notes of such
survey.

Golshus S. Payne,

Subscribed and sworn
before me this 4th day
of November A.D. 1861

B. J. Pengra, Sur. General of Oregon

262

Paynes - Notes ...

262

Surveyors Office at
Eugene City Oreg Dec 5th 1861

The foregoing field notes of the
Survey of the Subdivisions
Township number
5 North of the base line and
Range 35 East of the Meridian
in the State of Oregon executed
by Delphis S Payne under
his Contract Number 100 dated
August 1st 1861 having been
critically examined the
necessity corrections and
explanations made the
said field notes and the
surveys they describe are
herby approved.

J. D. Payne
Surveyor General