

Township No 5 N, Range 33 E, Will, Mer,
4000 Set 1/4 Sec post cor in dup

Barine Course N 100

Dug pits Drove Charred
Stake, and Raised Mound
as per instructions.

8000 Set post corner for sec,
1. 12. 677. on Spur of hill
Course North.

Drove Charred Stake, dug
pits, and Raised Mound
as per instructions.

Land hilly good Grass Soil
2nd Rate,

North on East boundary of sec
1 T. 5 N, R. 33. E, Will, Mer,
Bar 21° E.

4000 Set 1/4 Sec post on ridge.
Course N, W,

Drove Charred Stake, dug
pits and Raised Mound
as per instructions

2
 Township No 33 N, Range 33 E, Will, Mo.,
 8000 Set post corner for Townships
 546 N in Ranges 33 & 34 E,
 and sec 1. 6. 31. 436.

Drove churned stake, dug pits
 and raised mound as per
 instructions,
 Found Broken good
 Grass soil hardly 2nd Rate,

West on Random between
 Townships 546 N, Range 33 E,
 Bar, 21° E,

April 20th 1865,
 Set Half Mile and Mile posts
 at 4000 and 8000 chs and
 found the Town line to
 be 5 Miles 78.60 The
 falling to be, 50 South
 of Corner post,

The correction will be
 S 85° 56' E, on true line the
 west fraction 1.40 Short

Township No. 5 N. Range 33 E, Will. Mer,
 S 89° 56' East on true line on
 North boundary of Section 6 T5 N.
 Range 33 E,
 Bar 21° E -

- 3860 Set 1/4 Section cor post level
 Drove charred stake, dug pits,
 and raised mound as per
 instructions.
- 7600 Proposed Stage Road from T5
 Wallula to La Grange, C. N. W.,
- 7660 Dug branch C. N. W.,
- 7860 Set post corner for sec
 5, 6. 31. & 32, on hill side
 facing the S. W. +
25
 Drove charred stake, dug
 pits, and raised mound
 as per instructions.
 Land is Broken good
 Grass soil good 2nd
 Rate

S 89° 56' E on true line on
 North boundary of sec

Township 45 N, R. 33 E, Will, Mex,
 5th N. R. 33 E

Bar, 21° E,

\$10.00 A Cabin a proposed Stage
 Station on the proposed
 Stage Route from Wallula
 to Ladysand, near
 a Spring of Water,

40.00 Set 1/4 Sec post on side hill ⁴⁰
 sloping to the West
 Drove charred Stake, dug
 pits, and raised Mound
 as per instructions

80.00 Set post corner 4th sec
 4. 5. 32 & 33, land slopes to the
 S. W. Drove charred Stake,
 dug pits, and raised
 Mound as per instructions
 Found Rolling good
 Grass Soil good 2nd Note.

S 89° 56' E, on true line
 on North boundary of sec 4
 T. 50 N, R. 33 E,

Township No 5 N, R 33 E, W. Mer,
Bar, 21° E -

4000 Set 1/4 Sec post Land Surveying ⁺ 20
Gently to the S, W,
Drove Churned Stake,
 dug pits, and raised
Mound as per instructions

80.00 Set post corner for sec 9
3. 4. 33 & 34. in head of
ravine course N 20
Drove churned stake, dug
pits, and raised
Mound as per instructions
Land Rolling good
Grass Soil good 2nd Rate,

889° 56' on true line on
North boundary of sec
3, T. 5 N, R. 33 E -
Bar, 21° E -

4000 Set 1/4 Sec post on steep 50
side hill facing N, E,
Drove Churned Stake, dug

Township N. 50. R. 33. E. Will, Mer,
pits, and raised mound
as per instructions,

80.00 Set post corner for Secs 5-0
2. 3. 34. 35, at foot of hill
on the South,

Drove charred Stake, dug
pits, and raised mound
as per instructions,

This line passes over
summit of hill crossing
to the North and
quite hilly good
grass soil good 2nd
Rate.

88° 56' E on true line
on North boundary of
Sec 2, T. 50 N, R. 33 E,
Bar 21 E-

40.00 Set 1/4 Sec post on
level, drove charred
Stake, dug pits, and

Township No. 5 N. R. 33 E. Will. Mer,
Revised Mound as per
instructions,

80,000 Set post corner for sec 1
1, 2, 35-436 Drive charred
stake, Aug pits, and
Revised Mound as per
instructions,
Land Broken good
Grass Soil 2nd Rate,

S 89° 56' E on true line on
North boundary of sec 1
T 5 N. Range 33 E,
Dist. 21⁰ E -

40,000 Set 1/4 Sec post corner
Drive charred stake, Aug
pits, and Revised
Mound as per instructions
8000 post corner,
Land quite broken
Soil 2nd Rate good grass

For General Remarks see
field notes of Subdivisional
lines.

The survey was executed
by Deputy W. H. Odell assisted
by
C. C. Harcam? }
A. Shibles } Chairman
William Warren Arman,

I William H. Odell do hereby
certify that the foregoing
are the true and original
field notes of the survey
of the Exterior lines
of Township No. 5 North
of Base Line of Range No.
33 East of Willamette Meridian
State of Oregon: made,
under contract No. 110
bearing date February
7th 1865, in accordance
with the laws of the

United States and the Instructions
furnished by the Surveyor
General, as will appear from
Affidavits duly made out
the Close of said Contract
and attached to the field notes
of Township No. 5 North,
Range 36 East of Willamette
Meridian,

William H. Odell

Deputy Surveyor

Surveyor General's Office
Eugene City Aug 23 1865

The foregoing field notes of the Survey of the ~~the~~
~~Standard Quarter North, through Ranges 31,~~
~~32, 33, 34, 35, 36 & 37 East Will. Mer. Oregon,~~
~~and of the~~ exterior lines of Tps. 5 North Ranges
33, 34, 35 East Willamette Meridian, Oregon,
executed by Odell & Lewis, Deputies, under con-
tract No. 110, bearing date February 7th 1865,
having been critically examined, the necessary ex-
planations and corrections made, the said field
notes and the surveys they describe, are hereby approved.

E. L. Applegate
Surveyor General of Oregon.