

Field Notes of the Exterior
Lines of Townships No. 4 North
of Ranges 31. 32. 33 & 34.
No. 5 North of Ranges
31. 32. & 36. also No. 6 North
of Ranges 34. 35 & 36.
in the State of Oregon
by W. H. Leell & W. S. Lewis,
Deputy Surveyors under
their contract No. 100 bearing
date February 7th 1865.

Township 4 N. R 31 E	see Pages 97-102
" " " " 32 " " "	89-95
" " " " 33 " " "	83-86
" " " " 34 " " "	68-82
" 5 " " 31 " " "	18-28
" " " " 32 " " "	6-16
" " " " 36 " " "	45-57
" 6 " " 34 " " "	40-45
" " " " 35 " " "	32-36
" " " " 36 " " "	59-64

Township 5 North Range 32 East
 North on East Boundary of Sec 12
 Town 5 North Range 32 East
 Variation 21° East.

40.00 Set 1/4 Sec Post in Prairie Corn
 North — 100 ft. Drive Charred
 Stake. Dug Pit raised
 mound as per instructions

80.00 Set Post Corner for Secs 1:12,
 6th on High Ridge + 75 ft.
 Drive Charred Stake. Dug Pit
 raised mound as per instructions.
 Land Broken grass good. Soil 2°
 Rate.

North on East Boundary of Sec 1.
 Town 5 North Range 32 East
 Variation 21° East.

40.00 Set 1/4 Sec Post Drive Charred
 Stake. Dug Pit raised
 mound as per instructions.

80.00 Set Post Corner for Secs Township
 5 1/2 North. Ranges 32 + 33 East

Township 5 north Range 32 East
Secs 1, 6, 36 & 37. Grove Charred
Stake dug Pit raised
Ground as per Instruction.
Land Broken grass good
Soil 2^o Rate.

May 9th 1845

Met on Pandora between Towns
5th north Range 32 East
Variation 21^o East.

At 40 & 80 Chains set 1/4 half
Mile Post 478 Chains 66 Sink,
Intersect North & South Line
2 Chains 150 Sink, South of Post.
Hence the Correction will be South
89^o 46' 26" East. on True Line.

S. 89^o 46' 26"

East on North Boundary of Sec
6 Town 5 north Range 32 East
Variation 21^o East.

38.66 Set 1/4 Sec Post on north side
of Big Hollow on side Hill
Grove Charred Stake dug

624

Surveyor General's Office
Eugene City, Aug. 23^d 1865

The foregoing field notes of the Survey of the Exterior
lines of ~~Tps. 4 N. R. 31, 32, 33, & 4 East; and of~~
Tps 5 N. Ranges 31, 32 and 36 East; and of
Tps 6 N. Ranges 34, 35 and 36 East, Will. Mer,
Oregon, Executed by Odell and Lewis under contract
No. 110 bearing date February 7th 1865, having
been critically examined, the necessary explanations
and corrections made, the said field notes and
the surveys they describe are hereby approved.

E. L. Applegate
Surveyor General.