

Index

9	10	10	11	12	12	13	14	15	15	16	17	17	18
31	32	33	34	35	36	31	32	33	33	35	36	31	32
Sections													
Range 31 East													
Range 32 East													

18	20	20	21	22	23	24	24	25	26	27	28	29	30
33	34	35	36	39	32	33	34	35	36	31	32	33	34
Range 33 East													
Range 34 East													
Range 35 East													

34	32	33	34	34	35	36	36	37	38	40	40	41	42
35	36	37	32	33	34	35	36	31	32	33	34	35	36
Range 36 East													
Range 37 East													

copying this

445

6 446

We William H. Odell and William S. Lewis, having been appointed deputy Surveyors of the lands of the United States in Oregon, do solemnly swear that we will well and faithfully, and to the best of our skill and ability, execute the duties confided to us pursuant to a contract with B. J. Pengra, surveyor general of the public lands in Oregon bearing date the seventh day of February 1865 according to the laws of the United States and the instructions received from the said surveyor general.

William H. Odell,
William S. Lewis,

State of Oregon }
County of Washtilla } ss

sworn and subscribed
to before me this 13th day March
1865

J. W. Northrup
A Justice of the Peace

447
7

We Cyrus Dixon and D. C. Wallace
do solemnly swear that we will
faithfully execute the duties of
chain carriers; that we will level
the chain upon uneven ground,
and plumb the tally pins,
whether by sticking or dropping
the same, that we will report
the true distance to all notable
objects, and the true length of
all line that, ^{we} assist in measuring,
to the best of our skill and ability

Cyrus Dixon
D. C. Wallace

State of Oregon }
County of Wmatilla } ss Sworn and
subscribed to before me this
13th day of March 1865

J. W. Northrup
A Justice of the Peace

448

~~8~~ 348

I Robert Cook do solemnly
swear that I will well and
truly perform the duties of
Axeman, according to instruc-
tions given me, and to the
best of my skill and
ability.

Robert Cook

State of Oregon }
County of Yamhill } 38 Sworn
and subscribed to before
me this 13th day of
March 1865.

J. W. Northrup
A Justice of Peace

March 15th 1865.

Commenced the survey of the first
Standard Parallel North of Base Line
and East ~~between~~ ^{through} Ranges 31. 32. 33.

34. 35. 36 & 37. between Township 4 & 5

North, at the North East Corner of
Township No 4 North in Range No 30

East of Willamette Meridian, Thence

East on South boundary of section

31 Town ^{5th} North in Range 31 East,

Variation 20° East.

40.00 Set Standard corner for 1/4 sec,

Drove charred Stake and dug
Pit & constructed Mound as per
Instructions

73.00 Dry Gulch course North West 100

80.00 Set post ^{Standard} corner for sec 31 & 32. 60

Drove charred Stake and raised
Mound with pits as per Instruction

This line passes over Rolling
grounds good grass see
Timber Soil 2nd Rate

Township 45 N. in Range 32 East Well Mer
Mound as per Instructions.
This line passes over rolling
land good grass Soil 2^d Rate

East on South boundary of section
36 Township 5 N. Range 32 East.

Bar, 20th.

40.00 Set post Standard Corner for 1/4 Sec.
Drove Charred Stake dug pits as
per Instructions.

80.00 Set post Standard corner for
Townships 5 North in Ranges
32 & 33 East. Drove Charred
Stake dug pits and raised
Mound as per Instructions.
Land gently rolling
good grass Soil Good
2nd Rate

East on South boundary of
section 31 Township 45 N.
Range 33 East

First Standard Parallel North Between
Bar 20° E,

4000 Set post Standard corner for
1/4 Section Drove Chaired
Stake dug pits and
Revised Mound as per
Instructions.

8000 Set post Standard corner for
Sections 31 & 32, Drove Chaired
Stake dug pits and Revised
Mound as per instructions
The land on this line is
gently rolling Soil good
2nd Rate

East on South boundary of sec 32,
Township ~~28~~ 25 N. R. 33 E.
Bar 20° E-

4000 Set 1/4 Section Standard
Corner Drove Chaired
Stake dug pits and
Revised Mound as
per instructions,

Town 475N in Range 33E. of Will, Mer,
8000 Set post Standard corner for
sections 32 & 33. on level
Drove Charrred Stake Aug
pits and raised Mound
as per instructions.

Land Pulling good
Grass Soil Good 2nd Rate

Crat on South boundary of
section 33. Township N. 50N
Range 33 East
Bearing 20° E -

4000 Set post Standard corner for 1/4 Sec
Drove Charrred post Aug
pits and raised Mound
as per Instructions

8000 Set post Standard corner for
sections 33 & 34 Land facing
the South East.

Drove Charrred Stake Aug
pits and raised Mound
as per Instructions

First Standard Parallel North Between

* East on South boundary of sec,
34 Township 5 N. Range 33 E,
40.00 Set Standard corner for ^{Bar 20° E} 1/4 Sec
in reverse course N. E. 40

Drove Churred Stake dug pits
and raised Mound as per
instructions.

75.00 A well defined trail course
N. W. March 20th / 1865.

80.00 Set post standard corner for
sections 34 & 35 on land gently
sloping to the South,
Drove Churred Stake, dug
pits and raised Mound
as per instructions

The land on this line
is gently rolling good
Grass Soil 2nd Rate

East on South boundary of
Section 35 Township 5 N. R. 33 E.
Bar 20° E -

Townships 49 5d, in Range 33 E T11, Mex,
40.00 Set Standard corner for 1/4 Sec

on hill side facing the East
Drove Churred Stake, dug
pits and Raised Mound
as per instructions

80.00 Set post Standard corner for
sections 35 & 36 on Summit of
ridge

40

Drove Churred Stake dug
pits and Raised Mound
as per instructions.

Land Rolling good
grass Soil good 2nd Rate

East on South boundary
of section 36 Township 50d
Range 33 East
Bear 20° E-

40.00 Set post Cor for 1/4 Sec
Drove Churred Stake dug
pits & Raised Mound as
per instructions,

First Standard Parallel North Between
8000 Set post Standard corner for
Townships 5 N. in Ranges
33 & 34 East and sections
36 & 37, on land sloping to the
East. Drove Charred Stake dug
pit and raised mound as
per instructions,
Land rolling good
grass soil 2nd rate

East on South boundary of
section 31 Township 5 N
R 34 East
Bar 20' 8"

4000 Set post Standard corner for 1/4 Sec
on land sloping to the South
Drove Charred Stake dug pits
and raised mound as
per instructions

8000 Set post Standard corner for Secs
31 & 32, Land slopes to the West,
Drove Charred Stake dug pits

Townships 4+5 north In Range 34 East.

Fir Tree 20 inches in diam N. 24° 31' E. 19 Sinks

Fir Tree, 10 do do do S. 4° 30' W. 80 do

Fir Tree 8. do do do N. 73° W. 60 Sinks.

This Line Passes through Heavy
Timber Fir, Pine & Larch.

Undergrowth Same & Vine
Maple. Land gently rolling.

This Standard line passes
over high rolling lands
covered with good grass
along the whole extent
affording an extensive
range for stock, But
from the fact that water
is scarce over most of the
distance the land will
not be considered very
valuable until enterprise
shall sink wells to
give water to stock,

which can be done
 at very little expense,
 The timbered lands
 in the Mountains
 are considered valuable
 and would soon be
 entered by the settlers
 in the Valley if offered
 at public or private
 sale.

The Standard Parallel of
 which the foregoing are the
 field notes was surveyed
 Deputy W. H. Odell assisted
 through Ranges 31, 32, 33, 34, 35
 & 37 by Cyrus Dixon } Chairman
 D. C. Wallace }
 Robert Cook } Axeman
 Through Range 36 by
 W. W. Johnson Compassman
 C. C. Harcane } Chairman
 A. Shibles }
 William Warren Axeman

I William H. Odell, do hereby
certify that the foregoing are
the true and original field notes
of the survey of the First
Standard Parallel North
between Townships 5 & 6
North and East through
Ranges 31, 32, 33, 34, 35, 36 & 37,
East of Willamette Meridian,
made under contract No. 110,
bearing date February 7th 1865,
in accordance with the laws
of the United State and the
Instructions furnished by the
Surveyor General, as will appear
from affidavits duly made out
and attached to the field notes
of Township No. 5 North of Range
36 East of Will; Mer;

William H. Odell

Deputy Surveyor

Surveyor General's Office
Eugene City, Aug. 23, 1865

The foregoing field notes of the survey of
the 1st Standard Parallel North through
Ranges 31, 32, 33, 34, 35, 36 and 37 E
Will. Mer. Oregon, executed by Odell &
Lewis, Deputy Surveyors, under their con-
tract No. 110, bearing date Feby. 7th
1865, having been critically examined
the necessary explanations and corrections
made, the said field notes and the Sur-
veys they describe are hereby ap-
proved.

E. L. Applegate
Surveyor General of Oregon.