

Index

To field notes of Exterior lines
to Township N^o 5 North of Base
Line in Range 32 East of
Willamette Meridian

11	12	13	14	14	15	
6	5	4	3	2	1	10
						12 10
						13 9
						24 8
						25 8
						36 7

Township 5 North Range 32 East
 Commenced Survey of Exterior Lines
 April 18th 1865

North between Secs 31 & 36.

Variation 20° East.

4000 Set 1/4 Sec Post. Sand Stakes
 with East. Drove Chared
 Stake. Dug Pitts & raised
 Ground as Per Instruction

8000 Set Post corner for Secs 31, 36,
 37 & 25. Sand facing S. E.
 Drove Chared Stake Dug Pitts
 & raised Ground as Per Instruc
 tion.

Sand Broken good grass
 Soil 2^d rate.

Township 5 North Range 32 East,
North on East Boundary of Sec 25,
Town 5 North Range 32 East
Variation 21° East

40,000 Set 1/4 Sec Post on a Level
Drove Chared Stake Dug Pitt
raised Mound as Per
Instruction

80,000 Set Post corner for Secs 24, 25,
19+30, on a Level Drove
Chared Stake, Dug Pitt,
raised Mound as Per
Instructions. Sand Rolling
grass good, Soil 2^d Rate.

North on East Boundary of Sec
24, Town 5 North Range 32, E,
Var 21° East,

40,000 Set 1/4 Sec Post on Level, Drove
Chared Stake, Dug Pitt, raised
Mound as Per Instruction,

80,000 Set Post corner for Secs 18, 24,
18+19, On a Level, Drove

Township 5 North Range 32 East
Charred Stake. Dug Pit raised
mound as per instructions.
Sand broken. Grass good
Soil 2^o Rate.

North on East Boundary of Sec
13. Town 5 North Range 32 East
Variation 21' East

4000 Set 1/4 Sec Post on Sand descending
to the North. Drove Charred
Stake. Dug Pit. raised
mound as per instructions

8000 Set Post corner for Sec 12, 13.
7+8. In Prairie Drove Charred
Stake Dug Pit. raised.
mound as per instructions
Sand broken. Good grass
Soil 2^o Rate.

Township 5 North Range 32 East
North on East Boundary of Sec 12
Town 5 North Range 32 East
Variation 21° East.

40.00 Set 1/4 Sec Post in Prairie Corn
North — 100 ft. Drive Charred
Stake. Dug Pit raised
mound as per instructions

80.00 Set Post Corner for Secs 1:12,
6th on High Ridge + 75 ft.
Drive Charred Stake. Dug Pit
raised mound as per instructions.
Land Broken grass good. Soil 2°
Rate.

North on East Boundary of Sec 1.
Town 5 North Range 32 East
Variation 21° East.

40.00 Set 1/4 Sec Post Drive Charred
Stake. Dug Pit raised
mound as per instructions.

80.00 Set Post Corner for Secs Townships
5th North. Ranges 32 + 33 East

Township 5 north Range 32 East
 Secs 1, 6, 36 & 37. Grove Charred
 Stake Wagon Pit raised
 Ground as per Instruction.
 Land Broken grass good
 Soil 2^d Rate.

May 9th 1845

Met on Pandora between Towns
 5th north Range 32 East
 Variation 21° East.

At 40 & 80 Chains set 1/4 half
 Mile Post 478 Chains 66 Sink,
 Intersect North & South Line
 2 Chains 150 Sink, South of Post.
 Hence the Correction will be South
 89° 46' 26" East. on True Line.

S. 89° 46' 26"

East on North Boundary of Sec
 6 Town 5 north Range 32 East
 Variation 21° East.

38.66 Set 1/4 Sec Post on north side
 of Big Hollow on side Hill
 Groves Charred Stake Wagon

624

Surveyor General's Office
Eugene City, Aug. 23^d 1865

The foregoing field notes of the Survey of the Exterior
lines of ~~Tps. 4 N. R. 31, 32, 33, & 4 East; and of~~
Tps 5 N. Ranges 31, 32 and 36 East; and of
Tps 6 N. Ranges 34, 35 and 36 East, Will. Mer,
Oregon, Executed by Odell and Lewis under contract
No. 110 bearing date February 7th 1865, having
been critically examined, the necessary explanations
and corrections made, the said field notes and
the surveys they describe are hereby approved.

E. L. Applegate
Surveyor General.