

Field Notes of the Resurvey
of Exterior boundary lines of Townships
4 North of Range 27 East Township
5 North, Ranges 31 & 32 East and
fractional Townships, 6 North of the
Base line of Ranges 31, 32 & 33 East
of the Willamette Meridian, executed
by Nicholas O. Walden, Deputy
Surveyor under his contract No
209, bearing date the 6th day of
July 1874.

Commenced Oct. 23^d 1874.

Completed Decemb. 9th 1874.

Index.

Referring the lines to the pages of the Field notes

T. S. N. R. 31 C.

6.	5	4.	3	2	1	6.	
						12	5
						13	5
						24	5
						25	4.
31	32	33	34.	35	36		4
8	8	9	9	9	9.		

Index:

Referring the lines to the pages of the Field notes

T. 5. N. R. 32. E.

6	5	4	3	2	1	12
					12	11
					13	11
					24	11
					25	10
31	32	33	34	35	36	10
14	14	15	15	15	15	

Index:

Referring the lines to the pages of the Fieldnotes.

J. H. N. R. 27. C.

				27	27.
25	6.			2	1. 21.
24.	7				12. 20
23	18				13. 20
23	19.				24. 19
22	30.				25. 19
22	31.				36. 18.

Resurvey of the Exterior Boundaries of Township

After surveying the subdivisional lines of the Eastern tier of sections in Township 5 North of Range 32 East and finding that it could not close within the required limits, to all the corners on the East boundary of the Township, and to the corner to sections 1 & 2 in the North boundary, I began at the Standard Corner to Township 5 North, Ranges 32 & 33 East and run

North on a blank line along the E. boundary of Sec. 36
T. 5 N. R. 32 E.

40.08 A point 28 lbs. East of the $\frac{1}{4}$ Sec. Cor.

80.00 A point 47 lbs. South and 50 lbs. East of the corner to Secs. 25 & 36

North on a blank line along the East boundary of Sec. 25

Var. $21^{\circ} 20'$ East.

5 North, Range 32 East Will. Mer. Oregon.

40.70 A point 60 lbs. East of the $\frac{1}{4}$ Sec. Cor.

80.00 A point 90 lbs. South and 82 lbs. East
of the corner to Secs. 24 & 25

North on a blank line along the E. boundary of Sec. 24
Var. $21^{\circ} 15'$ East

41.16 A point 110 lbs. E. of the $\frac{1}{4}$ Sec. Cor.

80.00 A point 139 lbs. South and 82 lbs.
East of the corner to Secs. 13 & 24

North on a blank line along the E. boundary of Sec. 13
Var. $21^{\circ} 30'$ East

41.57 A point 52 lbs. East of the $\frac{1}{4}$ Sec. Cor.

80.00 A point 193 lbs. South and 52 lbs. East
of the corner to Secs. 12 & 13

North on a blank line along the E. boundary of Sec. 12
Var. $21^{\circ} 30'$ East

42.35 A point 82 lbs. East of the $\frac{1}{4}$ Sec. Cor.

80.00 A point 288 lbs. South and 111 lbs.
East of the corner to Secs. 1 & 12

Resurvey of the Exterior Boundaries of Township

North on a blank line along the E. boundary of Sec. 1
 Var. $21^{\circ} 45'$ East.

43.39 A point 121 lbs. E. of the $\frac{1}{4}$ Sec. Cor.

83.88 A point 132 lbs. East of the corner
 to Townships 5 + 6 North, Ranges
 32 + 33 East

From the established corner to Townships
 5 and 6 North, Ranges 32 + 33 East
 & run

West on a blank line along the N. boundary of Sec 1
 Var. $21^{\circ} 30'$ East

40.25 A point - 19 lbs north of the $\frac{1}{4}$ Sec. Cor.

80.25 A point 25 lbs. East and 39 lbs. North
 of the corner to Secs. 1 + 2

West on a blank line along the N. boundary of Sec 2
 Var. 22° East.

40.82 A point - 39 lbs. N. of the $\frac{1}{4}$ Sec. Cor

80.00 A point - 112 lbs. East and 69 lbs.
 North of the corner to Secs. 2 + 3

List of Names

A list of the names of the individuals employed to assist in running, measuring and marking the lines and corners described in the foregoing field notes of the resurvey of the Exterior Boundary lines of Townships 4 North of Range 27 East, Townships 5 North of Ranges 31 & 32 East and Fractional Townships 6 North of the base line of Ranges 31, 32 & 33 East of the Willamette Meridian showing the respective capacities in which they acted.

Rufus S. Moore	Chairman
Henry Meldrum	Chairman
William H Cooper	Assessor

We hereby certify that we assisted
 Nicholas O. Madden, Deputy Surveyor in
 resurveying the Exterior boundary line
 of fractional Townships No. 6 North of
 the Ranges Nos. 31, 32 and 33 East of
 Townships No. 5 North, Ranges Nos 31 and
 32 East, and Township No. 4 North of
 the base line of Range No. 27 East of
 the Willamette Meridian in the capaci-
 ties indicated by our respective signa-
 tures, and that said Exterior bound-
 ary lines have been in all respects
 to the best of our knowledge and belief
 well and faithfully surveyed and
 the boundary monuments placed accord-
 ing to the instructions furnished by
 the Surveyor General.

Rufus S. Moore Chairman
 Henry Melvin Choquian
 William H. Cooper Clerk

Subscribed and sworn to before me a Notary
 Public, this 12th day of December 1874

John W. Eldrum
 Notary Public

John W. Eldrum
 Notary Public

U.S. Surveyor General's Office
Eug. Portland Oregon
June 23^d 1875

The foregoing field notes of the survey ~~made~~
the Re-Survey of the Exterior lines of T 4 N
R 27 E Will. Mer. Oregon and of the
Standard Parallel in R 27 E have
executed by N. O. Walden U.S. Deputy
Surveyor having been critically ex-
amined the necessary corrections and
explanations made the said field
notes and the surveys they describe
are hereby approved

Ben Simpson
Sur Gen of Or.

33

I Nicholas O. Walden, Deputy Surveyor do solemnly swear that in pursuance of a contract with Benjamin Simpson W. S. Surveyor General for the State of Oregon bearing date the 6th day of July 1874, and in strict conformity to the laws of the United States and the instructions furnished by the said Surveyor General, I have faithfully resurveyed the Exterior Boundaries of Township 4 North, Range 27 East; Townships 5 North, Ranges 31 & 32 East and ~~Townships~~ Townships 6 North of the base line of Ranges 31, 32 and 33 East of the Willamette Meridian in the State aforesaid, and do further solemnly swear that the foregoing are the true and original field-notes of such Survey.

Nicholas O. Walden
Deputy Surveyor

Subscribed and sworn to by the above named Nicholas O. Walden, Deputy Surveyor before me a Notary Public on this the 12th day of December 1874

John W. Meldrum
Notary Public.

Meldrum
Notary Public