

54 ~~394~~

494

Index

To Exterior lines of Township N^o 5 N, R^o 34 E.

See Page 67

71	72	73	73	74	75	
6	5	4	3	2	1	70
						12 69
						13 69
						24 68
						25 67
						36 67

Township N^o 5 N. R 34 & Will, Mex,
 April 8th / 1865

North between Ranges 34 & 35 on
 East boundary of sec 26 T 5 N,
 Var, 21° East,

40.00 Set $\frac{1}{4}$ Sec post Drive charred
 Stake, dug pits, and raised
 Mound as per instructions.

80.00 Set post Corner for secs 25 & 36
 30 & 31. Land slopes to the East
 Drive Charred Stake, dug pits,
 and raised mound as per
 instructions.

This line passes over broken
 lands good Gross Soil 2nd rate

North between Ranges 34 & 35 on
 East boundary of sec 25 T 5 N,
 Var 28° 30' E -

40.00 Set charred post Corner for
 $\frac{1}{4}$ Sec, Dug pits and raised
 Mound as per instructions,

80.00 Set post Corner for secs 24 & 25

Township N^o 5 N. R 34 E. Will, Mer,
19430. Drove charred stake,
dug pits, and raised mound as
per instructions This line passes
over broken land good grass
Soil good 2nd Rate.

North between Ranges 34 & 35 on
East boundary of Sec, 24. T. 5 N,
Rar, 21st East,

40.00 Set 1/4 Sec, post cor, on hill side 40
facing the East. Drove Charred
Stake, dug pits, and raised
Mound as per instructions.

80.00 Set post corner for sees 13 & 24. 18 & 19
on Land sloping gently to the N, E, ⁵⁰
Drove charred Stake, dug pits and
raised mound as per instructions
Land broken Soil 2nd Rate,

North between Ranges 34 & 35.
on East boundary of sec, 13 T. 5 N,
Rar, 21st East,

Township No 5 N, R, 34 E, Will, Mer,

40.00 Set 1/4 sec, post on hill side facing 40
the East, Dug pits, drove Charred
Stake and Raised Mound as per
instructions.

~~80.00~~

69.50 Road Course N, E, & S W.

80.00 Set 1st Cor, for secs 12 & 13. 7418⁸⁰
on hill side sloping to the North
Drove Charred Stake, dug pits,
and raised mound as per
instructions.

Land hilly Good Grass
Soil 2^d Rate,

North between Ranges 34 & 35, on
East boundary of sec 12 S, 5 N,
Bar, 21° East

40.00 Set 1/4 Sec post on hill side 40
facing the North, Drove Charred
Stake, dug pits, and raised
Mound as per instructions

^{73.00} 80.00 ~~Per~~ ^{Creek} ~~the~~ ^{Piae} ~~Creek~~ course NW
Set post cor, for secs 1 & 12, 70
40

To 419 510

Township No. 5 N, R. 34 E, Will. Mer,
677. Dug pits drove charred
Stake, and raised mound as per
instructions,

Land hill grass poor Soil
3rd Rate,

North between Ranges 34 & 35 on
East boundary of Sec, 1 S 5 N
Var, 2^o East,

40.00 Set $\frac{1}{4}$ Sec post corner 20
Drove Charred Stake, dug
pits, and raised Mound as
per instructions

80.00 Set post Corner for Towns, 60
546 N in Ranges 34 & 35 E
on Secs 1. & 31 & 36. Land
Slopes to the North
Drove Charred Stake, dug
pits, and raised Mound
as per instructions,
Land hill fair grass
Soil 3rd Rate,

Surveyor General's Office
Eugene City Aug 23 1865

The foregoing field notes of the Survey of the ~~the~~
~~Standard Quarter North, through Ranges 31,~~
~~32, 33, 34, 35, 36 & 37 East Will. Mer. Oregon,~~
~~and of the~~ exterior lines of Tps. 5 North Ranges
33, 34, 35 East Willamette Meridian, Oregon,
executed by Odell & Lewis, Deputies, under con-
tract No. 110, bearing date February 7th 1865,
having been critically examined, the necessary ex-
planations and corrections made, the said field
notes and the surveys they describe, are hereby approved.

E. L. Applegate
Surveyor General of Oregon.