

Index.

Referring the lines to the pages of the field notes
 Township 4 North, Range 34 East, Will. Mer.

6	38	5	28	4	22	3	15	2	8	1
57		37		28		21		14		8
17	36	8	27	9	21	10	14	11	7	12
35		35		26		20		13		7
18	34	17	26	16	19	15	13	14	6	13
34		23		25		19		12		5
19	33	20	25	21	18	22	12	23	5	24
32		31		27		18		11		4
30	31	29	24	28	17	27	11	26	3	25
30		29		23		16		10		3
31	29	32	23	33	16	34	9	35	2	36

Field Notes of the subdivision
lines of Township No. 4 North
Range 34 East of Willamette
Meridian.

Subdivision commenced
July 31st 1866.

From the corner to sections
1. 2. 35 & 36. on the South
boundary of the Township.

I run
North between sections 35 & 36.

40.00 Set post corner for 1/4 section
drove charred stake; dug pits;
and raised mound as per
instructions.

80.00 Set post corner for sections 25, 26 level
35 & 36, drove charred stake; dug
pits; and raised mound as
per instructions.

Land gently rolling, good

Township No. 4 North, Range 34 East, Willamette Meridian.

1. 2. 11 & 12. Drove charred stake,
dug pits and raised mound as per
instructions.

Land broken, grass good, soil 2^d Rate

East on random between sections
1 & 12.

Bar 20° East.

40.00 Set temporary 1/4 section post corner

80.56 Intersect North and South line 40 lbs
North of post corner.

N 85° 43 W, on true line.

40.28 Set 1/4 section post corner, drove
charred stake dug pits and raised
mound as per instructions

80.56 ~~Set~~ post corner

Land broken, good grass.

Soil 2^d Rate.

North between sections 1 & 2.

40.00 Set post corner for 1/4 section, drove
charred stake, dug pits, and

9 2409

Township No 4 North Range 34 East Williamst Meridian

raised mound as per instructions

69.46 Intersect 1st Standard North, 5.94 chs

West of Standard corner for sections

35 & 36, S 5th N R 34 E. Set Closing corner
for sections 1 & 2 at intersection

above charred stake, dug pits

and raised mound as per instructions

Land broken covered with good

grass, Soil 2nd Kate

August 1st 1866.

X

North between sections 34 & 35,

40.00 Set post corner for 1/4 section. Drove charred
Stake, dug pits; and raised mound as
per instructions,

60.75 Wild Horse Creek 10 the wide course N.W.

61.00 Enter field.

67.00 Leave field course of fence E & W.

80.00 Set post corner for sections 26. 27.

34 & 35, above charred stake, dug
pits, and raised mound as
per instructions.

Land level, Soil 1st Kate.

15 415

Township No 4 North, Range 34 East, Will. Mer.

40.00 Set temporary 1/4 section post corner,

80.22 Intersect North and south line 19ths

South of post corner,

S 89° 52' W on true line

40.11 Set post corner for 1/4 section.

Drove charred stake, dug pits,
and raised mound as per instructions.

80.22 To post corner -

Land rolling, good grass

X Soil 2nd rate,

North between sections 2 & 3.

40.00 Set post corner for 1/4 section,

drove charred stake, dug pits,

and raised mound as per instructions

70.25 Intersect First Standard North

6.71 chs West of Standard corner

for sections 34 & 35 T. 5 N., R. 34 E.

At point of intersection set

post corner for sections

2 & 3. Drove charred stake, dug

pits and raised mound as per

Township 44 North, Range 34 East, Will. Mer.
instructions.

Land rolling, good grass,
Soil 2nd rate,

+

August 2nd 1866.

North between sections 33 & 34.

40.00 Set post corner for 1/4 section, drove
churned stake, dug pit, and
raised mounds as per instructions

80.00 Set post corner for sections 27,
28, 33 & 34. Drove churned stake,
dug pit and raised mound
as per instructions.

Land rolling, good grass,
Soil 2nd rate,

+

East on meridian between
sections 27 & 34.

Var 21° East.

40.00 Set temporary 1/4 section corner
79.13 Intersect North and South line
29 lbs north of post corner,

Township N. 4 North, Range 34 East Willamette Mer-

39.96 Set post corner for $\frac{1}{4}$ section, drove charred stake dug pits, and raised mound as per instructions.

79.92 Go post corner,
 Land broken, good grass,
 Soil 2^d rate,

com

North between sections 344.

40.00 Set post corner for $\frac{1}{4}$ section, drove charred stake dug pits and raised mound, as per instructions,

69.57 Intersect 1st Standard North 6.85 lbs West of Standard corner for sections 33434, T. 5 N., R. 34 E., Set closing corner at point of intersection, drove charred stake dug pits, and raised mound as per instructions,

Land broken, good grass,
 Soil 2^d rate,

August 3^d 1866.

X

Township No 4 North, Range 34 East, Will-Mer-
East on random between 449,
Bar 20° East

40.00 Set temporary $\frac{1}{4}$ section post corner

80.49 Intersect North and south line,

5.2 links south of post corner
S 89° 38' W on true line,

40.24 Set post corner for $\frac{1}{4}$ section
drove charred stake, dug pit,
and raised mound as per
instructions

80.49 To post corner,

X Land broken grass
excellent. Soil 2nd Rate

North between sections 445,

40.00 Set post corner for $\frac{1}{4}$ section, drove
charred stake dug pits and
raised mound as per instructions.

70.30 Intersected 1st Standard North
6.45 West of Standard corner
for sections 32433 T5NR 34E -
Set post at point of intersection

29 429

Township of 4 North, Range 34 East, Will-Mer-

for closing corner for sections
4 & 5. Drove charred stake, dug
pit and raised mound of
earth as per instructions.

Land broken. grass good
Soil 2^d Rate,

August 4th 1866.

*

North between sections 31 & 32.

29.00 Road course N. E. & S. W.

40.00 Set post corner for ^{1/4} section

Drove charred stake, dug pit, and
raised mound as per instructions

80.00 Set post corner for sections 29, 30.

31 & 32. Drove charred stake
dug pit and raised mound
as per instructions.

Land broken, grass excellent,

+ Soil 2^d rate,

East on random between sections
29 & 32.

Township No 4 North, Range 34 East, Will-Mer-

80.23 To post corner,

80.23 Land rolling, grass excellent,
Soil 2^d rate.

X

North between sections 546-

40.00 Set post corner for 1/4 section, drove
charred stake dug pits, and
raised mound as per instructions,

69.81 Set Closing corner for sections 546.

on 1st Standard North, 622 lbs

West of Standard corner for
sections 81432. T5 N R 34 E-

Drove charred stake, dug
pits and raised mound as
per instructions.

Land rolling, grass
good, Soil 2^d rate.

X

The lands in this Township
are well adapted to stock
raising being well covered
with the very best of Buck

A list of the names of the individuals employed to assist in running, measuring, or marking the lines and corners described in the foregoing field notes of Township No. 4 North of the Base Line of Range No. 34 East of Willamette Meridian, showing the respective capacities in which they acted:

J. J. Henderson	} Chairmen
John A. Bigg	
P. M. Demney	Axeman

+

We hereby certify that we assisted
William H. Odell, deputy survey, in
surveying the subdivisioinal lines of
Township No 4 North of Base Line of Range
No 34 East of Willamette Meridian, and that
said Township has been in all respects, to the
best of our knowledge and belief, well and
faithfully surveyed and the boundary
monuments planted according to the
instructions furnished by the Surveyor
General.

J J Henderson Chairman
J A Pigg Chairman
P C M. Demmey Foreman

State of Oregon
County of Washtilla } ss, Subscribed and
Sworn to before me this day
of September A.D. 1866, at
William Luccallen
Justice of the Peace

I William H. Odell, deputy surveyor, do solemnly swear that, in pursuance of a contract with E. S. Applegate surveyor of the public lands of the United States in the State of Oregon, bearing date the 2^d day of July 1866, and in strict conformity to the laws of the United States and the instructions furnished by said Surveyor General, I have faithfully surveyed the subdivisions of Township number 4 North of the Base Line of Range 34 East of the Willamette Meridian, in the State aforesaid, and do further solemnly swear that the foregoing are the true and original field notes of such survey.

William H Odell

State of Oregon }
 County of Lane } ss. Subscribed
 and sworn to before me this
 22^d day of December 1866

Joel War

Notary Public

449
Surveyor General's Office

Eugene City, Jan 17th 1867

The foregoing field notes of the survey of
the Subdivisional series of Township No 4
North Range 34 East Will. Mer. Oregon
Executed by William H. Odell, Deputy
Surveyor under his contract No 114 bearing
date July 2nd. 1866 having been critically
examined the necessary corrections and
examinations made the field notes and
the surveys they describe are hereby
accepted

E. L. Applegate

Surveyor General of Oregon