

# Index

|               |    |    |    |    |    |    |    |    |    |    |    |    |    |
|---------------|----|----|----|----|----|----|----|----|----|----|----|----|----|
| 9             | 10 | 10 | 11 | 12 | 12 | 13 | 14 | 15 | 15 | 16 | 17 | 17 | 18 |
| 31            | 32 | 33 | 34 | 35 | 36 | 31 | 32 | 33 | 34 | 35 | 36 | 31 | 32 |
| Range 31 East |    |    |    |    |    |    |    |    |    |    |    |    |    |

|               |    |    |    |    |    |    |    |    |    |    |    |    |    |
|---------------|----|----|----|----|----|----|----|----|----|----|----|----|----|
| 18            | 20 | 20 | 21 | 22 | 23 | 24 | 24 | 25 | 26 | 27 | 28 | 29 | 30 |
| 33            | 34 | 35 | 36 | 39 | 32 | 33 | 34 | 35 | 36 | 31 | 32 | 33 | 34 |
| Range 33 East |    |    |    |    |    |    |    |    |    |    |    |    |    |

|               |    |    |    |    |    |    |    |    |    |    |    |    |    |
|---------------|----|----|----|----|----|----|----|----|----|----|----|----|----|
| 34            | 32 | 33 | 34 | 34 | 35 | 36 | 36 | 37 | 38 | 40 | 40 | 41 | 42 |
| 35            | 36 | 37 | 32 | 33 | 34 | 35 | 36 | 31 | 32 | 33 | 34 | 35 | 36 |
| Range 36 East |    |    |    |    |    |    |    |    |    |    |    |    |    |

Range 37 East  
copy this

445

6 446

We William H. Odell and William S. Lewis, having been appointed deputy Surveyors of the lands of the United States in Oregon, do solemnly swear that we will well and faithfully, and to the best of our skill and ability, execute the duties confided to us pursuant to a contract with B. J. Pengra, surveyor general of the public lands in Oregon bearing date the seventh day of February 1865 according to the laws of the United States and the instructions received from the said surveyor general.

William H. Odell,  
William S. Lewis,

State of Oregon }  
County of Washtilla } ss

sworn and subscribed  
to before me this 13<sup>th</sup> day March  
1865

J. W. Northrup  
A Justice of the Peace

447  
7

We Cyrus Dixon and D. C. Wallace  
do solemnly swear that we will  
faithfully execute the duties of  
chain carriers; that we will level  
the chain upon uneven ground,  
and plumb the tally pins,  
whether by sticking or dropping  
the same, that we will report  
the true distance to all notable  
objects, and the true length of  
all line that, <sup>we</sup> assist in measuring,  
to the best of our skill and ability

Cyrus Dixon  
D. C. Wallace

State of Oregon }  
County of Wmatilla } ss Sworn and  
subscribed to before me this  
13<sup>th</sup> day of March 1865

J. W. Northrup  
A Justice of the Peace

448

~~8~~ 348

I Robert Cook do solemnly  
swear that I will well and  
truly perform the duties of  
Axeman, according to instruc-  
tions given me, and to the  
best of my skill and  
ability.

Robert Cook

State of Oregon }  
County of Yamhill } 38 Sworn  
and subscribed to before  
me this 13<sup>th</sup> day of  
March 1865.

J. W. Northrup  
A Justice of Peace

March 15<sup>th</sup> 1865.

Commenced the survey of the first  
Standard Parallel North of Base Line  
and East ~~between~~ <sup>through</sup> Ranges 31. 32. 33.

34. 35. 36 & 37. between Township 4 & 5

North, at the North East Corner of  
Township No 4 North in Range No 30

East of Willamette Meridian, Thence

East on South boundary of section

31 Town <sup>5<sup>th</sup></sup> North in Range 31 East,

Variation 20° East.

40.00 Set Standard corner for 1/4 sec,

Drove charred Stake and dug  
Pit & constructed Mound as per  
Instructions

73.00 Dry Gulch course North West 100

80.00 Set post <sup>Standard</sup> corner for sec 31 & 32. 60

Drove charred Stake and raised  
Mound with pits as per Instruction

This line passes over Rolling  
grounds good grass see  
Timber Soil 2<sup>nd</sup> Rate

Townships 49 5d, in Range 33 E T11, Mex,  
40.00 Set Standard corner for 1/4 Sec

on hill side facing the East  
Drove Churred Stake, dug  
pits and Raised Mound  
as per instructions

80.00 Set post Standard corner for  
sections 35 & 36 on Summit of  
ridge

40

Drove Churred Stake dug  
pits and Raised Mound  
as per instructions.

Land Rolling good  
grass Soil good 2<sup>nd</sup> Rate

East on South boundary  
of section 36 Township 50d  
Range 33 East  
Bear 20° E-

40.00 Set post Cor for 1/4 Sec  
Drove Churred Stake dug  
pits & Raised Mound as  
per instructions,

First Standard Parallel North Between  
8000 Set post Standard corner for  
Townships 5 N. in Ranges  
33 & 34 East and sections  
36 & 37, on land sloping to the  
East. Drove charred stake dug  
pit and raised mound as  
per instructions,  
Land rolling good  
grass soil 2<sup>nd</sup> rate

East on South boundary of  
section 31 Township 5 N  
R 34 East  
Bar 20' 8"

4000 Set post Standard corner for 1/4 Sec  
on land sloping to the South  
Drove charred stake dug pits  
and raised mound as  
per instructions

8000 Set post Standard corner for Secs  
31 & 32, Land slopes to the West,  
Drove charred stake dug pits

Township No 5 N. Range 34 E. Will. Mer,  
and raised Mound as per  
instructions.

The land on this line is rolling  
good grass Soil good  
2<sup>nd</sup> Rate

East on South boundary of section  
32. Township No 5 N Range 34 East  
Bar 20° E.

40.00 Set post Standard corner for 1/4 Sec  
Drove charred Stake dug  
pits and raised Mound as  
per instructions,

80.00 Set post Standard cor for  
Sec, 32 & 33. Land slopes to the  
S.W. Drove Charred Stake dug  
pits and raised Mound  
as per instructions

On this line the Land is  
rolling good grass  
Soil 2<sup>nd</sup> Rate



First Standard Parallel North Between  
 East on South boundary of  
 section 33 Township N. 5. N. 34 E.  
 Bar 20° E.,

17.75 A Trail Course N. W. 30

40.00 Set post Standard Corner for ~~1/4~~ Sec,  
 dug pits raised mound and  
 drove charred stake as per  
 Instructions

80.00 Set post Standard Corner 20

337 For sections 34 & 33, land  
 slopes to the North,  
 Drove charred stake, dug pits,  
 and raised mound as  
 per instructions

Land Broken good  
 Grass Soil 2<sup>00</sup>/<sub>100</sub> rate

East on South boundary  
 of section 34 Township N. 5  
 N. Range 34 E.  
 Bar 20° E.,

40.00 Set post Standard Corner for

Township 445 N Range 34 East Will. Mer.  
1/4 Section 20

Drove Charred Stake dug pits  
and Raised Mound as per  
instructions,

80.00 Set post Standard corner for 20

Secs 34 & 35. on hill side slopes

to the West. Drove Charred Stake  
dug pits and Raised Mound  
as per instructions

Land on this line broken,  
good grass. Soil 2<sup>nd</sup> Rate,

March 22<sup>nd</sup> 1865,

East on South boundary of  
Sec 35 Township 445 N. R. 34 E,  
Bar 20° East,

40.00 Set post Standard corner  
1/4 Sec. Land slopes to the N  
Drove Charred Stake, dug  
pits, and Raised Mound  
as per instructions,

7950 A Road Course N E, & S W,

First Standard Parallel South Between  
8000 Set post Standard corner for  
sections 35 & 36. Land slopes to  
the South, Drive Cherrred Stake  
Aug pits and raised Mound  
as per instructions

Land Broken good  
Grass Soil good Low Rate

Cast on South boundary  
of section of 36 Township  
No 5 North Range 34 East,  
Variation 20 East,

4000 Set post, Standard corner for  
1/4 Section on level,

Drive Cherrred Stake  
Aug pits and raised  
Mound as per instructions,

8000 Set post Standard  
Corner for sections  
31 & 36, Township 5 North  
in Ranges 34 & 35 East,

Townships 47 5 N, Range 34 E.

Land slopes to the North  
Drove Charred Stake dug  
pits and raised Mound as  
per instructions.

Land on this Mile Rolling  
Good Grass Soil 2<sup>nd</sup> Rate

East on South boundary of sec  
31 Township 35 E N. 5 N.

Var 20° E -.

40.00 Set post Standard corner for  
1/4 Sec. Land slopes to the East  
Drove Charred Stake, dug pits,  
and raised Mound as per  
instructions.

80.00 Set Standard Corner for sections  
31 & 32, on hill slope to the E 100  
From which a Pine  
20 in in dia, B ~~Set~~ S 88° E 57 1/2 ft  
A Balm 10 in do to N 60° E 31 1/2 ft

The pine stands on opposite  
side of pine Creek in edge.

Townships 4+5 north In Range 34 East.

Fir Tree 20 inches in diam N. 24° 31' E. 19 Sinks

Fir Tree, 10 do do do S. 4° 30' W. 80 do

Fir Tree 8. do do do N. 73° W. 60 Sinks.

This Line Passes through Heavy  
Timber Fir, Pine & Larch.

Undergrowth Same & Vine  
Maple. Land gently rolling.

This Standard line passes  
over high rolling lands  
covered with good grass  
along the whole extent  
affording an extensive  
range for stock, But  
from the fact that water  
is scarce over most of the  
distance the land will  
not be considered very  
valuable until enterprise  
shall sink wells to  
give water to stock,

which can be done  
 at very little expense,  
 The timbered lands  
 in the Mountains  
 are considered valuable  
 and would soon be  
 entered by the settlers  
 in the Valley if offered  
 at public or private  
 sale.

The Standard Parallel of  
 which the foregoing are the  
 field notes was surveyed  
 Deputy W. H. Odell assisted  
 through Ranges 31, 32, 33, 34, 35  
 & 37 by Cyrus Dixon } Chairman  
 D. C. Wallace }  
 Robert Cook } Axeman  
 Through Range 36 by  
 W. W. Johnson Compassman  
 C. C. Harcane } Chairman  
 A. Shibles }  
 William Warren Axeman

I William H. Odell, do hereby  
certify that the foregoing are  
the true and original field notes  
of the survey of the First  
Standard Parallel North  
between Townships 5 & 6  
North and East through  
Ranges 31, 32, 33, 34, 35, 36 & 37,  
East of Willamette Meridian,  
made under contract No. 110,  
bearing date February 7<sup>th</sup> 1865,  
in accordance with the laws  
of the United State and the  
Instructions furnished by the  
Surveyor General, as will appear  
from affidavits duly made out  
and attached to the field notes  
of Township No. 5 North of Range  
36 East of Will; Mer;

William H. Odell

Deputy Surveyor

Surveyor General's Office  
Eugene City, Aug. 23, 1865

The foregoing field notes of the survey of  
the 1<sup>st</sup> Standard Parallel North through  
Ranges 31, 32, 33, 34, 35, 36 and 37 E  
Will. Mer. Oregon, executed by Odell &  
Lewis, Deputy Surveyors, under their con-  
tract No. 110, bearing date Feby. 7<sup>th</sup>  
1865, having been critically examined  
the necessary explanations and corrections  
made, the said field notes and the Sur-  
veys they describe are hereby ap-  
proved.

E. L. Applegate  
Surveyor General of Oregon.