

Field notes of the Sub-divisional  
Lines of Township No 5 North  
of Range 35 East of Will, Mer,  
from the 7<sup>th</sup> to the 51<sup>st</sup> Page  
and of Township No 5 North  
of Range 34 East Will, Mer,  
from the 53<sup>rd</sup> to the 102<sup>nd</sup> Page,  
as made under Contract  
No 110 by William H Odell  
and William S. Lewis Deputy  
Surveyors commencing April  
8<sup>th</sup> and finishing April 18<sup>th</sup>  
A.D. 1865.







57A

1944

Commenced the survey of  
the Subdivisional lines  
of Township No 5 N, Range  
34 East of Will, Mer,

April 10<sup>th</sup> 1865.

North between sections  
35 & 36 T 5 N R 34 East

Var 20° East.

150 Trail course east of North.

40.00 Set 1/4 Section post corner  
Drove charred stake, dug  
pits and raised mound  
as per instructions.

80.00 Set post corner for sections  
25, 26, 35 & 36 land sloping  
gently to the West.  
Drove charred stake, dug  
pits and raised mound  
as per instructions.

Land rolling good  
Grass soil good 2<sup>nd</sup> rate.



195<sup>5-5</sup>

Township No 5 N, R, 34 E, Will, Mex,  
East on Random between sec,  
25 & 36, T<sup>5</sup> N, R, 34 E,

9.50 A Fossil course East of North,

40.00 Set Temporary 1/4 section post

80.00 Intersect N & S, line 25 sks South  
of post, corner for sections

25, 36, 31 & 30, from which I  
run, S 85° 45' West on true line

40.00 Set 1/4 section corner post  
Land sloping to the South East,  
Drove charred stake, dug pits,  
and raised mound as per  
instructions.

80.00 To post corner,

Land rolling good  
grass. Soil good 2<sup>nd</sup> rate

---

North between sections  
25 & 26 T<sup>5</sup> N, R, 34 E,

Bar 21° East,

40.00 Set 1/4 section post corner,  
on level, Drove charred



56

196

Township N. 4 N., R. 34 E., Will. Mer,  
Stake, dug pits, and raised  
mound as per instructions.

80.00 Set post corner for sections  
24, 25, 26 & 23, on level,

Drove barred stake, dug  
pits, and raised mound  
as per instructions,

Ground gently sloping  
to South West

Good Grass Soil good  
Gov. Rate.

East on random between  
sections 24 & 25, 5 N., R. 34 E.,

38.00 Trail course East of North,

40.00 Set temporary 1/4 Sec  
post cor,

79.84 Intersect N & S line 10 lbs  
south, post from which  
I run S 89° 56' West on line  
line

39.92 Set 1/4 section corner post,



197<sup>57</sup>

Township No. 4 N, R. 34 E, Will. Mer,  
on level, Drove charred Stake,  
dug pits and raised  
mound as per instruction

7584 To post corner  
Land gently rolling  
Good grass soil good  
2<sup>nd</sup> rate,

North between sections  
23 & 24 T. 5 N, R. 34 E,  
Variation 20° East.

40.00 Set 1/4 section post corner,  
Land slopes gradually to the  
N. E, Drove charred stake,  
dug pits, and raised  
mound as per instructions

80.00 Set a post corner for sections 30  
13. 14. 23 & 24, on south side  
of Prairie Course East, Drove  
Stake, dug pits, and raised  
mound as per instructions.  
Land gently rolling



58 198

Township 5 N, R. 34 E, Will, Mer,  
grass good soil 2<sup>nd</sup> Rate.

\* East on road down between  
sections 13 & 24, T. 5 N, R. 34 E,  
17.00 Spring branch 2<sup>1/2</sup> ft wide 100  
course N 8

40.00 Set temporary 1/4 section  
post

58.00 Trail course North,

80.10 Intersect North & South 100  
line at post from  
which I run West on  
true line

40.05 Set 1/4 section post corner  
on side hill facing the  
West Drive charred stake,  
dug pits and raised mound  
as per instructions.

80.10 To post corner,  
Land broken good  
grass soil 2<sup>nd</sup> rate,



59  
199

Township 5 N, R 34 E, M Will, Mer,  
April 11<sup>th</sup> 1865,

North between sections 12 & 14  
T 5 N, R 34 E,

Bar 21° East,

40.00 Set 1/4 section post, T and 30  
slopes to the East, Drove charred  
Stake, dug pits and  
raised Mound as per  
instructions,

Bar 20° E,

80.00 Set post corner for sections <sup>100</sup>  
11, 12, 13 & 14, on side hill facing  
the West, Drove charred Stake  
and raised Stone Mound  
as per instructions  
Land broken good grass  
Soil 2<sup>d</sup> rate,

East on Bandow between

sections 12 & 13 T 5 N, R 34 East,

40.00 Set 1/4 section temporary post



Township 5 N, R. 34 E, Will, Mer,  
 79,95 Intersect North & South line  
 27 lbs North of post, corner  
 for sections 12. B. 7418,

from which I run  
 $N 83^{\circ} 48' 49''$  West on true line

39,96 Set  $\frac{1}{4}$  Section post corner,  
 on hill side facing the  
 East, Drove charred stake,  
 and raised stone mound  
 as per instructions,

79,98 To post,

Found very broken  
 soil hardly  $2\frac{1}{2}$  rate,

North between sections  
 11412 T. 5 N, R. 34 E,

Var  $21^{\circ} E$ .

40,00 Set  $\frac{1}{4}$  section post corner 40  
 hill slopes to the West,  
 Drove charred stake,  
 dug pit & raised  
 mound as per instructions



20, 61

Township 5 N, R. 34 E, Will. Mer,  
8000 Set a post corner sections,

1. 2 & 11 & 12. Land sloping  
to the N. W. Drove Charred  
Stake, dug pits, and raised  
mound as per instructions  
Land broken and gravelly  
soil hardly 2<sup>nd</sup> rate,

East on random between  
sections 1 & 12. T5 N. R 34 E.

40.00 Set temporary 1/4 section  
post.

62.00 Pine Creek course N. W.

80.65 Intersect N. V. S. Line  
38 lbs north of post, corner.  
from which I run  
N 89° 44' West on true line

40.32 Set post corner for 1/4 section  
Drove charred stake dug  
pits and raised mound  
as per instructions.



Township 5 N, R, 34 E, Will, Mer,  
 80.65 To post corner,  
 Land broken soil hard  
 2<sup>nd</sup> Rate,

North on Random between  
 sections 1 & 2, T, 5 N, R, 34 E,  
 Bar 21' E

40.00	Set temporary 1/4 Sec post,	50
70.50	Bringing of steep bank,	40
72.50	Foot of bank	30
78.00	Pin Creek 30 lbs wide course	

North West,

79.30 Intersect E & W Township  
 line 49 lbs East of post,  
 Corner for sections 1, 2, 35 & 36,  
 from which I run  
 S 21' E on true line

39.30 Set 1/4 Section post corner,  
 on hill side sloping to  
 the West, drove churred  
 stakes, dug pits, and  
 raised mound as



Township 5 N, R. 34 E, Will, Men,  
 per instructions  
 77.30 To post corner,  
 Land broken soil  
 2<sup>nd</sup> rate,

---

+ North between sections 35 & 34  
 T. 5 N, R. 34 E,  
 Var 20° E

40.00 Set  $\frac{1}{4}$  Section post corner.  
 Drove charred stake, dug  
 pits and raised mound as  
 per instructions.

80.00 Set post corner for sections  
 26, 27, 34 & 35, Drove charred stake  
 dug pits and raised mound  
 as per instructions,  
 Land broken grass good  
 soil good 2<sup>nd</sup> rate,

---

East on railroad between  
 sections 26 & 35, T. 5 N, R. 34 E,  
 40.00 Set  $\frac{1}{4}$  section post cor,



Township No 5 N. R. 34 E. Will, Mer,  
temporarily

79,92 Intersect Post Thorand South  
line 15 fms South of post,  
corner for sections 25, 26, 35 & 36  
from which I run  
S 89° 54' W on true line,

39,96 Set  $\frac{1}{4}$  Section post corner,  
on land sloping to the West,  
Drove charred stake dug pit  
and raised mound as per  
instructions,

79,92 To post corner,  
Land broken good  
grass soil 2 $\frac{1}{2}$  ft,

North between sections  
26 & 27, T. 5 N. R. 34 E,  
Bar 21° East

40.00 Set  $\frac{1}{4}$  section post Drove  
charred stake, dug pit,  
and raised mound as  
per instructions,



Township R5 N, R34 E, W11, Mer,  
 80.00 Set a post corner for sections  
 22, 23, 26 & 27. Land ascends  
 gradually to the west,  
 Drive charred stake, dug pit  
 and raised mound as per  
 instructions,  
 Land broken grass good soil  
 2<sup>nd</sup> rate,

East on random between  
 sections 23 & 26, T5 N, R, 34 E.

40.00 Set temporary 1/4 section post  
 79.70 Intersect North & South line  
 30 fms North of post corner for  
 sections 23, 24, 25 & 26, from  
 which I run N89°47' W. on  
 true line,

39.85 Set 1/4 section post corner  
 on level, Drive charred  
 stake dug pit & raised  
 mound as per instructions



66 206

Township No 5 N, R, 34 E, Will, Mer,  
79.70 To post corner,

Land rolling good grass  
soil good 2<sup>nd</sup> rate,

North between sections 22 & 23.

T, 5 N, R, 34 E,

Cor 21° E

40.00 Set  $\frac{1}{4}$  section post, on level,  
Drove charred stake, dug pits,  
and raised mound as per  
instructions.

80.00 Set a post corner for sections  
14, 15, 22 & 23, on level, Land  
gently rolling good grass  
soil good 2<sup>nd</sup> rate,

April 12<sup>th</sup> 1865,

Post on random between  
sections 14, & 23, T, 5 N, R, 34 East,

40.00 Set temporary  $\frac{1}{4}$  section post  
79.58 Intersect P & S line 42 lks

North of post, from which  
I run S 85° 42' West  
East on true



Township N. N. R 34 E 34 E. Will, Mer,  
39.79 Set 1/4 section post, on level,

79.58(?) Drove charred stake, dug pit and  
raised mound as per instructions

79.85 To post corner,

Found gently rolling  
good grass soil 2<sup>nd</sup> date,

North between sections 14 & 15,  
T 5 N R 34 E

Bar 21° E

40.00 Set 1/4 section post, found 50  
sloping to the S. E.,  
Drove charred stake, dug  
pit and raised mound  
as per instructions.

80.00 Set post corner for sections  
10, 11, 14 & 15 on steep hillside  
sloping to the north 30°  
Drove charred stake,  
dug pit, and raised  
mound as per instructions  
Good grass soil



68 208

Township #5 N, R. 34, W. 11, Mer,  
2<sup>nd</sup> rate, Land on last  
half ascending;

Coast on random between  
sections 11 & 14 T5 N R 34 E,

40.00 Set temporary  $\frac{1}{4}$  section  
post,

79.84 Intersect North & South <sup>+</sup> 60

line 20 lbs North of post,  
corner for sec 11, 12, 13 & 14,  
from which I run  
N 85° 51' West on true line

39.92 Set  $\frac{1}{4}$  section post corner,  
on side hill facing the  
North, Drive charret stake,  
dig pits and raised  
mound as per instruction,

79.84 To post corner,  
Land broken soil hardly  
2<sup>nd</sup> rate,



294

Township 5 N, R 34 E, Will, Mer,  
North between sections 10 & 11  
T 5 N, R 34 E,  
Rur 2<sup>d</sup> East

40.00 Set 1/4 section post,  
Drive charred stake, dug  
pit & raised mound as  
per instructions

80.00 Set a post corner for  
sections 2, 3, 10 & 11, Drive  
charred stake dug pit  
and raised mound as  
per instructions.

Land broken soil  
hardly 2<sup>nd</sup> rate,

Cont on random between  
sections 2 & 11 T 5 N R 34 E

40.00 Set temporary 1/4 section  
post,

79.48 Intersect North & South  
line 10 Lhs south of  
post corner for



Township No 5 N, R. 34 E, Will. Mer,  
 sections 1, 2, 11 & 12, from  
 which I run  $S 89^{\circ} 56' W$   
 on true line

39,74 Set  $\frac{1}{4}$  section post  
 Drove charred stake, dug  
 pits, and raised

<sup>79.48</sup> mound as per instructions  
 78,88 To post corner  
 Land broken soil  
 2<sup>nd</sup> rate, grass good.

North on random between  
 sections <sup>210</sup> 5 N, R. 34 E,  
 Run  $29^{\circ}$  East

40,00 Set  $\frac{1}{4}$  section post 50

80,15 Intersect East & West  
 Township line 2000  
 East of post, from  
 which I run  $39^{\circ} E$ ,  
 on true line

40,15 Set  $\frac{1}{4}$  section post  
 corner Drove charred



200  
71

Township No. 5 N, R. 34 E, Mill, Mer,  
stake, dug pits, and raised  
mound as per instructions  
8015 To post corner,  
Land broken grass  
good soil 2<sup>d</sup> rate,

---

+

April 13<sup>th</sup> 1865

North between sections 33 & 34  
T. 5 N R. 34 E,  
var 20° East

40.00 Set 4 sections post corner  
Drove charred stake, dug pits  
and raised mound as per  
instructions,

80.77 Set a post corner for sec,  
27.28.33 & 34, on level,  
Drove charred stake, dug  
pits, and raised mound  
as per instructions,  
Land broken, grass  
good soil good 2<sup>d</sup> rate,



Township 5 N, R 34 E, Will. Mer,  
East on random between secs  
27 & 28 T 5 N, R 34 E.

40.00 Set temporary 1/4 Section  
post.

79.70 Intersect North & South line  
40 lbs south of post corner  
for secs 26, 27, 34 & 35 from  
which I run,

S 89° 43' W on true line

39.85 Set 1/4 section post in T 5  
sawing Drove charred  
Stake Aug pits and  
raised mound as per  
instructions.

79.70  
X

To Post corner  
Land calling zones  
good soil gravel 2<sup>nd</sup> rate.

North between secs  
27 & 28 T 5 N R 34 E,  
Bearing 20° East

40.00 Set 1/4 section post, on level,  
Drove Charred Stake,



Township No 5 N, R, 34 E, Will. Merz  
Dug pits, and raised mound  
as per instructions

80.00 Set a post corner for  
sec, 21. 22. 27 & 28. Drove  
churned stakes, dug pits  
and raised mound as per  
instructions,

Land broken soil 2<sup>nd</sup>  
rate grass good,

East on random between  
sec, 22. 27 T, 5 N, R, 34 E,

40.00 Set 1/4 sec post, temporarily  
Drove churned stakes, dug  
pits and raised mound  
as per instructions.

79.92 Intersect North & South  
line 26 Ths South of post  
from which run  
S 89° 49' W on true line

39.96 Set 1/4 section <sup>post</sup> Land slopes  
to the S, E, Drove churned  
dug pits & raised mound as per instructions



74 204

Township No 5 N R 34 E, Will Mer,  
7992 To Post, corner,

Land broken grass  
good soil 2<sup>nd</sup> rate,

North between sections 21 & 22,

Township 5 N, R, 34 E,

Var 20° East

40.00 Set 4 section post corner,  
on level, drove charred stake,  
dug pit, and raised mound  
as per instructions

80.00 Set a post corner for sections  
15, 16, 21 & 22, on level, Drove  
charred stake, dug pit and  
raised mound as per instructions

Land gently rolling.  
good grass soil 2<sup>nd</sup> rate,

East on boundary between  
section 15 & 22, T 5 N, R, 34 E,

40.00 Set temporary 1/4 section post,

79.50 Intersect N & S line 46 lbs



Township 5 N R 34 E Well Mer  
South of post, from which  
I run, S 89° 40' W on true line

39.75 Set 1/4 Section post, corner  
on level Drove charred stake,  
dug pits and raised mound  
as per instructions.

79.50 To post corner  
Panel gently undulating  
good grass soil good  
2<sup>d</sup> rate,

~~North~~ ~~Range~~ between  
sections 15 & 16 T 5 N Range 34 E  
variation 20° East

4000 Set 1/4 Section post corner  
on level Drove charred stake 800  
dug pits, and raised  
mound as per instructions

8000 Set post corner for  
sections 9, 10, 15 & 16  
Drove charred stake,  
dug pits and raised



Township No 5 N, R, 34 East Will, Mer,  
 mound as per instructions  
 This line passes down steep  
 hill good grass soil 2<sup>nd</sup> rate,

East on random between  
 sections 10 & 15, 5 N, R, 34 E,  
 4000 Set temporary 1/4 section  
 post corner  
 7974 Intersect N 78. line 37 lbs  
 south of post corner,  
 from which I run  
 S 89° 44' West on true line  
 39,82 Set 1/4 section post Grove  
 Charred stake, dug pits,  
 and raised mound as  
 per instructions,  
 7974 To post corner,  
 found broken good  
 grass soil 2<sup>nd</sup> rate,



Township 5 N R 34 East Will, Mer,  
North between sections 3 & 10  
Township 5 N, R, 34 E, Will, Mer,  
Var 20° East

40,00 Set 14 section post, drove  
charred stake, dug pits  
and raised mounds as  
per instructions.

80,00 Set a post corner for sections  
3, 4, 9 & 10, Drove charred  
stake, dug pits and  
raised mound as per  
instructions

Land broken soil  
2<sup>nd</sup> date goes good,

April 14<sup>th</sup> 1865

East on parcel on between  
sections 3 & 10, Township  
5 N, R, 34 E,

40,00 Set temporary 1/4 section  
posts,

7,86. Interest on 43 line



Township No. 5 N., R. 34 E., Will. Mer,  
 58 Lks South of post, corner,  
 from which I run  
 S,  $89^{\circ}35'W$ , on true line,

39,93 Set 4 Section post corner  
 Drive charred stake,  
 dug pit, and raised  
 mound as per instructions,

7986 To post corner,  
 Land broken  
 grass good, soil 2<sup>nd</sup> Rate,

North on panel, run  
 between sections 344,  
 T. 5 N., R. 34 E. (Tax  
 bar 21' East,

40,00 Set 4 section posts  
 temporarily,

80,10 Intersect North Town line  
 30 Lks East of post,  
 from which I run



Township 5-N R 34 E Will, Mer,  
 S 13' E on true line,  
 40.10 Set 1/4 Section post corner  
 Drove charred stake, dug  
 pits and raised mound as  
 per instructions,  
 80.10 Topost Corner,  
 Land very broken  
 good good soil 2<sup>nd</sup> Rate

+  
 North between sections 32 & 33  
 Township 5 N R 34 E Will, Mer,  
 40.00 Set 1/4 Section post, on level,  
 Drove charred stake, dug pits,  
 and raised mound as per instructions  
 80.00 Set a post corner for sections  
 28, 29, 32 & 33, Land facing  
 the East. Drove charred  
 stake, dug pits as per  
 instructions, Land  
 rolling good good  
 soil good 2<sup>nd</sup> Rate,



Township No. 5 N, Range 34 E Will. Mer,  
 East on Raneland between  
 sections 28 & ~~29~~<sup>33</sup>, T5 N, R34 E,  
 40,000 Set temporary 1/4 section

7290 Post trail ex. W.  
 80,22 Interest at 1/4 line 34 T5  
 South of post, corner  
 from which I run  
 S 89° 35' West on true line

41,11 Set 1/4 Sec Post & drove charred  
 stake dry pit, raised mound  
 as per instructions.

80,22 To Post corner for Secs 28, 29,  
 32 & 33. Land Rolling grass  
 good, Soil 2<sup>d</sup> Rate.

North been <sup>true</sup> Secs 28 & 29,  
 Town 5 North, Range 34 East,  
 Variation 21° East.

33,50 Trail corner North West,  
 40,00 Set 1/4 Sec Post, in level  
 drove charred stake, dry pit  
 and raised mound as per



220

Township 5, north. Range 34 East Hill, M.  
Instructions.

80,00 Set Post Corner for Rees 20, 21,  
28 + 29. Sand Slopes to the East  
Drove charred State. Dry Soil  
raised ground as per instructions.  
Sand Broken Soil 2<sup>d</sup> rate, grass  
good.

East on Random between Secs  
21 + 28. Town 5. N. Range 34, East,

40,00 Set Temporary 1/4 Sec Post.

80,16 Intersect East & West Line 18 Sicks  
South of Post, from which Arm  
S: 89° 52' West on True Line

40,08 Set 1/4 Sec Post on Sand Slope  
ing to West, Drove Charred  
State. Dry Soil - and raised  
ground as per instructions

80,16 1/4 Sec Post Corner, Sand Rolling  
grasses good. Soil 2<sup>d</sup> rate,



222  
 Township No. 5 N. R. 34 E, Will Mer  
 North between sections  
 20 & 21, T 5 N, R. 34 E,  
 P. 20

40.00 Set temporary 1/4 Sec  
 post corner, on level  
 Drove charred stake,  
 dug pit and raised  
 ground as per  
 instructions,

80.00 Set post corner for Sec,  
 16 17, 20 & 21, Drove charred  
 stake dug pit, and raised  
 ground as per instructions.

Land selling goes  
 good soil 2<sup>nd</sup> party

X

East on Randover  
 between sections 16 & 21,  
 T 5 N R 34 E,

40.00 Set temporary 1/4 Sec post  
 80.32 Intersect North & South



Township #5 N. R. 34 E. Will. Mer,  
line 26 Links South of post,  
from which I run  
S 89° 49' W on true line

40.16 Set  $\frac{1}{4}$  section post corner,  
on level, Drove charred stake,  
dug pits, and raised  
mound as per instructions.

81.32 E post corner,  
Land Broken, grass  
good, soil 2<sup>nd</sup> Rate,

North between sections  
16417, 5 N, R, 34 E, Will, Mer,  
Var 20° East,

40.00 Set  $\frac{1}{4}$  section corner post,  
Land slopes to the N, W,  
Drove charred stake, dug  
pits, and raised mound  
as per instructions

80.00 Set post corner sections  
8.9. 16417. Land slopes to the



Township 5 N, R, 34 E, Will, Mex,  
North, Drove charred stake,  
dug pits, and raised mound  
as per instructions,  
Land broken soil good 2<sup>nd</sup>  
rate,

- Post on boundary between  
sections 9 & 16 T, 5 N, R, 34 E,  
40,00 Set temporary 1/4 section  
post,  
8017 Intersect North and South  
line 20' N. South of  
post corner, from  
which I run  
S 89° 51' West on true line,  
40,08 Set 1/4 section post, on level,  
Drove charred stake,  
dug pits, and raised  
mound as per instructions,  
8017 To post corner,  
Land broken soil good.



85  
275

Township No 5 N, R 34 E, Mill, Mer,  
2<sup>nd</sup> rate,

---

North between sections 849  
T 5 N R 34 E,  
Bar, 21° East,

4000 Set 4 sections post in Ravine 150  
Drove charred stake, dug  
pits and raised mound  
as per instructions,

8000 Set a post corner for sec 4 100  
4. 5. 8 & 9. Drove charred  
stake, dug pits and raised  
mound as per instructions  
Turned broken grass  
good soil 2<sup>nd</sup> rate,

---

April 15<sup>th</sup>

East on Random between  
sections 449. T 5 N, R 34 E,  
4000 Set temporary 1/4 sec  
pivot corner,



Township 5 N, R. 34 E, Will, Mer,  
 80.06 Intersect N & S line 49 lbs  
 South of post, from which  
 I run

S 89° 42' W on true line

40.08 Set  $\frac{1}{4}$  Section post,

Drove charred stake

dug pits and raised

measured as per instructions,  
 80.06 Id post corner.

The land is quite broken  
 soil good 2<sup>nd</sup> rate.

X

North on Randon between sections

445-5 N R 34 E

Bar 21° East,

40.00 Set Temporary  $\frac{1}{4}$  Section  
 post,

80.46 Intersect North Town line 52 lbs

East of post, from which

I run S 22° E on true line

40.46 Set  $\frac{1}{4}$  Section post,

Drove charred stake,



227

Township N. 5 N. R. 34 E. Will, Mer,  
 dug pits, and raised  
 Mound as per instructions,  
 Land very broken grass good  
 soil 2<sup>nd</sup> rate,

North between sections 31 & 32  
 Township N. 5 N. R. 35 E. 34(?)

40.00 Set 4 Section post Land  
 gently sloping to the south  
 West, Doove charred stake,  
 dug pits and raised Mound  
 as per instructions.

80.00 Set a post corner for sections  
 29. 30. 31 & 32, corner slopes to the  
 West, Doove charred stake,  
 dug pits and raised Mound  
 as per instructions,  
 Land broken good grass  
 soil 2<sup>nd</sup> rate,



Townships No. 5 N R. 34 E Will. Mer,

East on Random between  
sections 29 & 32 T. 5 N R. 34 E

40.00 Set temporary  $\frac{1}{4}$  Section  
post

80.15 Intersect North and South  
line 20 lks South of post  
from which I run  
 $58^{\circ}41'$  W on true line

40.17 Set  $\frac{1}{4}$  Section post corner  
Land slopes to the South,  
Drove charred stake

80.15 To post corner  
Forest broken good  
grass Soil 2<sup>nd</sup> rate,

West on Random between  
sections 30 & 31 T. 5 N, R. 34 E,

40.00 Set temporary  $\frac{1}{4}$  section post

79.76 Intersect North & South line  
20 lks North of post,



Township #5 R3E 34 S Will, Mex,  
From which I run  
N 89° 41' E on true line

39.76 Set 1/4 Section post, in broad  
dry gulch course S.W, Drove  
churched stake, dug pits, and  
raised mound as per instructions

79.76 To post corner,  
Land broken good grass  
soil good 2<sup>nd</sup> rate.

North between sections 30429  
T. 5 N, R. 34 E,  
\* Bar 20' East.

40.00 Set 1/4 section post, Land slopes  
to the West, Drove churched stake,  
dug pits, and raised  
mound as per instructions,

80.00 Set a post corner for sec 0  
19.20. 29.430, Land slopes to the  
West, Drove churched stake, dug  
pits, and raised mound as



90 230

Township No 5 N, R 34 E Will, Mer,  
instruction,

Soil good  $2\frac{1}{2}$  rate,  
Land breaking

Post on random between sec,  
20.429. T5 N, R, 34 E,

40.00 Set temporary 4 sec, post

44.00 Soil course N, W, S, E,

80.09 Intersect North & South line

33 lbs South of post corner,

from which I run  
 $389^{\circ}46'W$  on true line,

40.04 Set 4 section post corner

Land slopes to the N, E,

Drove charred stake, Aug pits

and raised mound as  
per instruction.

80.09 To post corner,

Land rolling good

grass soil  $2\frac{1}{2}$  rate,



91  
231

Township R. 5 N, R. 34 E, Will, Minn,

West between sections 19 & 30  
on random T. 5 N, R. 34 E,

40.00 Set temporary  $\frac{1}{4}$  section  
post corner,

80.21 Intersected C. & S. Township line  
25 lbs North of post corner for  
section 19. 30. 24 & 25. from which  
I run  $N 88^{\circ} 49' E$  on true line

40.21 Set  $\frac{1}{4}$  section post cor,  
on level, Drive charred stake  
dry pits and raised  
ground as per instructions

80.21 To post corner,

Found gently rolling  
Grass good soil 2<sup>nd</sup>  
rate,

---

North between sections 19 & 20  
T. 5 N, R. 34 E,  
On 20 East,



Township 5<sup>th</sup>, Range 34<sup>th</sup> E, Will. Mer.  
 40.00 Set  $\frac{1}{4}$  Section post, ~~and~~ slopes  
 to the N.W., dug pits, drove  
 charred stake & raised mound  
 as per instructions.

80.00 Set a post corner for sections  
 17. 18. 19420. Land slopes to the  
 N.W., drove charred stake dug  
 pits, and raised mound as  
 per instructions.

Land quite broken soil  
 2<sup>nd</sup> rate grass good.

+

East on random between  
 sections 17 & 20, T. 5<sup>th</sup> N., R. 34<sup>th</sup> E,

40.00 Set  $\frac{1}{4}$  temporary section post,  
 80.01 Intersect North & South  
 line 29 lbs South of  
 post corner for section  
 16. 17. 20421, from which  
 down  $(S 89^{\circ} 48' W)$ , on true  
 line



Township N. 5 N., R. 34 E., Will. Mer,  
 40.00 Set 1/4 section post Level slopes  
 to the N Drove charred stake,  
 dug pits, and raised mound  
 as per instructions  
 80.11 To Post corner.

Land rolling good  
 grass soil  $\frac{2}{4}$  rate,

---

West on random between  
 sections 18, 19, T. 5 N., R. 34 E.,  
 40.00 Set temporary 1/4 section post,  
 80.17 Intersect West Township  
 line 11 lbs North of post,  
 corner for sections 18, 19, 13 & 24  
 from which I run  $N 89^{\circ} 55' E$   
 on true line,  
 40.17 Set 1/4 section post, on level,  
 Drove charred stake dug  
 pits and raised mound as  
 instructions  
 80.17 To post corner,



94 234

Township No. 5 N. R. 34 E. Mill, Minn.  
Land rolling good grass  
soil good 2<sup>nd</sup> date,

North between sections 17 & 18,  
Township 5 N. R. 34 E.  
Bar 20° East,

40,000 Set 4 Section post, on side hill  
sloping to the West. Drive  
churned stake, dug pits  
and raised mound as  
per instructions,

47,500 Trail course N. W.

80,000 Set a post corner for  
sections 7, 8, 17 & 18,

Land slopes to the N. E. Drive  
churned stake, dug pits,  
and raised mound as per  
instructions

Land broken good  
grass soil good 2<sup>nd</sup> date,



Township 5 N, R, 34 E, Will, Mo.,

+

East on Kearsden between sections  
8 & 17 Township 5 N, R, 34 E,

40.00 Set temporary 1/4 section post

45.25 Spring Ranch 2 lks wide course  
NW

100

79.85 Intersect N, & E, line 15 lks 150

South of post from which  
I ran S 85° 54' W on true line

39.92 Set 1/4 section post, on steep

hill side facing the East,  
Drove charred stake, dug pit,  
and raised mound as per  
instructions.

79.85 Go post corner,

Good grass  
Land broken soil  
2<sup>nd</sup> Rate,



Township No 5 N, R. 34 E, Will. Mer,

April 16<sup>th</sup> 1865,

West on random between sections

7 & 18 T 5 N. R. 34 E,

1165 Trail course N, W,

31.00 Spring branch 2 The Wide

course N, W,

150

40.00 Set temporary 4 section post

79.97 Insect West Township line

23 lbs North of post,  
from which I run  
N. 89° 50' E. on true line

39.97 Set 4 Section post, on hill

side facing the East, Drive  
charred stake, dig pits,

and raised mound as per  
instructions

79.97 To post corner,

found quite broken grass  
good soil good 2<sup>nd</sup> date,



237

Township No 5 N, R 34 E, Will, Mes,

North between sections, 7 & 8,  
Township 5 N, R 34 E,  
Var 20° East.

40.00 Set 4 Section post, on hill  
side facing the West,  
Drove Charred stake, dug  
pits, and raised  
mound as per  
instructions,

80.00 Set a post corner for  
Sections 5, 6, 7 & 8, on summit  
of ridge course N. Drove Charred  
Stake, dug pits and raised mound  
as per instructions, Land  
quite broken good grass, soil  
2<sup>nd</sup> Rate,



98 238

Township No 5 N, R, 34 E, Will, Mo,  
April 18<sup>th</sup> 1865

Cast on random between  
Sections 5 & 8, T, 5 N, R, 34 E,  
40.00 Set  $\frac{1}{4}$  Section temporary  
corner,

79.70 Intersect N. & S. Line ~~to~~ the  
South of post from which  
I run  $5^{\circ} 51'$  West on true line,

39.85 Set  $\frac{1}{4}$  section post, on side  
of hill facing the S, W,  
Drive chumrod stake & made  
mounds of stone as per  
instructions,

79.70 To Post corner  
Ground good Soil  
2<sup>nd</sup> rate, Land broken



Township  $T 5 N$  R 34 E. Will. Mex,

239

West on Random between  
Sections 6 & 7,  $T 5 N$ , R 34 E.

40.00 Set  $\frac{1}{4}$  Section Temporary  
Corner

79.82 Intersected West Township  
line 16 lbs South of post  
corner, from which I run  
 $S 89^{\circ} 53'$  East on true line,

29.82 set  $\frac{1}{4}$  section post drive  
churned stake dug pits,  
and raised mound as  
per instructions

79.82 To post corner  
Land broken soil good  
2<sup>nd</sup> date,

North on random between  
sections 5 & 6  $T 5 N$  R 34 E,  
Bar  $21^{\circ} 15'$  East,

40.00 Set  $\frac{1}{4}$  Section temporary  
corner,



100 240

Township No 5 N., R 34 E., Will, Mer,  
80.32 Intersect North Township line  
60 lbs East of post,

from which down  
S. 26' E, on town line,

40.32 Set 1/4 Section post, Drive  
Cherryed stake dug pit  
or not raised mound as

per instructions.

80.32 To West corner  
Lined broken soil hardly  
2<sup>nd</sup> Rate,

### General Remarks

There are no settlements as yet  
in this Township. The  
lands are high and to  
the north broken to the south  
rolling there is much the  
same as throughout the  
Township. The soil is of form.



ity of good <sup>low</sup> rate sustaining  
 a fine growth of grass,  
 affording excellent range  
 for stock, Persons engaged  
 in teaming or packing  
 to the Mines many of them  
 bring their stock into this  
 and adjoining Townships  
 to winter, The grass being  
 excellent and the lands suffi-  
 -ciently willing to give  
 considerable surface to the  
 southern hill sides where  
 the heat of the sun soon  
 melts the snow and leaves  
 the grass uncovered, thus  
 making it one of the best  
 winter ranges in Eastern  
 Oregon,

For summer pasturing  
 there is a scarcity of water  
 which operates against  
 the permanent settlement



of the lands, but this difficulty  
will in time be overcome by  
sinking wells, and this  
Country will soon be well  
settled.

The lines of which the  
foregoing are the field notes  
were surveyed by Deputy  
W. D. Odell assisted by  

C. C. Hascard	} Chainmen
A. A. Shubles	
William Warren	Assessor,



x

I, William H. Adell, do hereby  
certify that the foregoing are the true  
and original field notes of the  
survey of the subdivisional lines  
of Township No. 5 N, Range 34 E,  
in the State of Oregon.

Made, under contract No. 110  
bearing date February 7<sup>th</sup>  
1865, according to the laws  
of the United States and the Instruc-  
tions furnished by the Surveyor  
General, as will appear from  
Affidavits duly made  
at the close of said Contract  
and attached to the field  
Notes of Township  
No. 5 N R 36 East of Will Mer,  
William H. Adell  
Deputy Surveyor



Surveyor General's Office  
Eugene City, Aug. 23, 1865

The foregoing field notes of the Survey of  
Subdivisional lines of T. 5 N. R. 34

E. Willamette Meridian, Oregon, executed  
by Odell & Lewis, Deputy Surveyors, under  
contract No. 110, dated Feby. 7<sup>th</sup>, 1865,

having been critically examined, the  
necessary explanations and corrections

made, the said field notes and the surveys  
they describe, are hereby approved

E. L. Applegate  
Surveyor General of Oregon