





54 ~~394~~

494

Index

To Exterior lines of Township N<sup>o</sup> 5 N, R<sup>o</sup> 34 E.

See Page 67

71	72	73	73	74	75	
6	5	4	3	2	1	70
						12 69
						13 69
						24 68
						25 67
						36 67



Thursday March 23<sup>rd</sup> 1865

Commenced the survey of the Exterior  
Lines of Township No 5 North of Base  
Line in Range 35 East of Willamette  
Meridian, At the South East Cor,  
North between Ranges 35 & 36 on East  
boundary of section 36, in  
Township 5 North

Variation 20° E

2800 A Settlers house bears East about 2000

4000 Set post corner for 1/4 section on  
side hill facing the East,  
dug pits, drove charred  
stake, and raised earth mound  
as per instructions,

7300 A Wagon Road Course N. W.

8000 Set post corner for sec 25 & 36. 30 & 31,  
on hill side facing the East,  
drove charred stake, dug pits  
and raised mound as per  
instructions. This line passes  
along hill side sloping to the East  
Good Grass Soil good Good Water



Township No 5 North Range 35 East of Will, Mex.  
1912, 647. Land gently slopes to the N.E.

Drove Charred Stake, dug pits, and raised  
Mound as per instructions.

This line passes up rocky hill on the South  
half, the North half over gently rolling  
ground good grass soil Good  
2<sup>nd</sup> rate,

North, between ~~between~~ Ranges 35 & 36  
Township No 5 North, on east boundary  
of section 1.

Variation 21° East

40.00 Set post corner for  $\frac{1}{4}$  section  
on level Drove charred, stake, dug  
pits, and raised Mound as per  
instructions.

80.00 Set post corner for Township No 5 N. 6  
North, in Ranges 35 & 36 East and  
Sections 1, 6, 31, & 36.

Drove charred stake, dug pits,  
and raised Mound as per instructions  
This line passes down gently.



60 ~~400~~ 500

Township No. 5 North Range 35 East Will. Mex.  
descending grounds good grass  
Soil good 2<sup>nd</sup> Rate.

West on North boundary of sec  
1 on Random Township 5 N  
Range 35 East

Variation 21 East,

March 25<sup>th</sup> 1865,

35.50 Wagon Road Course N, E,

37.50 Enter Creek bottom 90

40.00 Set post corner for 1/4 Section  
Drove Charred Stake, and  
Raised Stone Mound as per  
instructions

43.25 Creek 75 lbs wide course North

51.60 do, 50 do, do, do, do,

65.50 Road course North,

80.00 Set temporary post corner  
for sec. 1 & 2. 35 & 36

Level, Soil 2<sup>nd</sup> Rate  
on East half, on West rocky.



Township No. 5 N. Range 35 E, Will. Mer,  
March 27<sup>th</sup> 1865

West on North boundary of sec,  
2 on Random,  
Bar, 21° East

- 4.40 Creek 25 lbs wide course North
- 9.00 do, 20 do, do, do, do,
- 17.25 do, do, do, do, do, do,
- 40.00 Set Temporary 1/4 Sec post on level
- 80.00 Set temporary post corner for  
sec 2 & 3. 34 & 35

Land level, Soil 1<sup>st</sup> Rate  
between the Creeks, west  
gravelly. but Good Grass

March 28<sup>th</sup> 1865  
West on Random on North bound-  
ary of sec 3. T. 5 N, R, 35 E.  
Bar, 21° East

- 7.60 Road course North West
- 40.00 Set Temporary 1/4 Sec post.
- 80.00 Set temporary sec. corner post
- Land level Good Grass.
- Soil 2<sup>nd</sup> Rate



62 ~~902~~ 502

Township, N<sup>o</sup> 5 N. Range 35 E, Will Mer,  
March 29<sup>th</sup> 1865,

West on Boundary on North to  
boundary of sec 4 T5N, R, 35 E,  
Var. 21° East

25.00	Foot of hill	
30.00	Summit of hill	60
40.00	Set temporary 1/4 Sec post	
74.35	Road Course N, W,	
80.00	Set temporary sec. cor. post	
	for secs 4 & 5. 3373 <del>4</del> <sup>2</sup>	70
	Land Rolling good	
	Gross Soil 2 <sup>d</sup> rate	

West on <sup>North</sup> ~~South~~ boundary of  
Sec 5 T5N, R35 E -  
Var 21° East,

31.00	Dry Creek 20 lks course N, W,	20
34.00	do, do, do, do, do, S, W,	
40.00	Set temporary 1/4 Sec post	
44.75	Same Creek Course N, W,	
60.00	Set temporary post cor,	
	for secs 5 & 6. 31732.	



Township No. 5 N. Range 35 E, Will. Mer,

The land on this line is  
broken good grass soil good  
2<sup>nd</sup> Rate.

---

West on Random on North  
boundary of sec. 6 T. 5 N. R. 35 E,  
Bar, 21° East,

40.00 Set temporary 1/4 sec post,  
78.67 Intersect North & South line  
97 lbs South of post,  
Land gently rolling  
Good Grass Soil 2<sup>nd</sup> Rate

---

East on true line on North  
boundary of Township No. 5 N  
Range 35, between Sec 3 & 6,  
Course S 89° 43' E,  
Bar, 21° East,

38.67 Move temporary 1/4 sec post  
86 lbs North Drove charred  
Stake dug pit and raised  
Mound as per instructions

---



Township N. 5th. Range 35 E. Will, Mer,  
 78.67 Set post corner for secs 5 & 6  
 31 & 32. Drove Charred Stake,  
 dug pits, and raised  
 Mound as per instructions

S 89° 43' E, on North boundary  
 of sec 5 T. 5 N. R. 35 E

40.00 Set 1/4 Sec post Drove Charred  
 Stake, dug pits, and raised  
 Mound as per instructions

80.00 Set post corner for secs  
 4 & 5. 32 & 33, Drove Charred  
 Stake, dug pits, and raised  
 Mound as per instructions

S 89° 43' E on North boundary  
 of sec, 4 T. 5 N. R. 35 E,

40.00 Set 1/4 Sec post, dug pits  
 Drove Charred Stake  
 and raised Mound as  
 per instructions

80.00 Set post corner for secs



Township 5 N, Range 35 E, Will, Mer,  
 3 & 4. 33 & 34. Drove Charred Stake,  
 Aug pits, and raised  
 Mound as per instructions.

---

S 89° 43' E on North boundary  
 of Sec 3 & 5 N, R 35 E,

4000 Set 1/4 Sec cor. post, Drove Charred  
 Stake, Aug pits and Made  
 Mound as per instructions,

8000 Set post Corner for Secs 2 & 3. 34  
 & 35, Drove Charred Stake, Aug  
 pits and Made Mound  
 as per instructions,

---

S 89° 43' E, on North boundary of  
 Section 2, T 5 N, R 35 E -

4000 Set 1/4 Sec post and Made  
 Stone Mound with Charred  
 Stake as per instructions,

8000 Set post Corner for Secs 1 & 2.  
 35 & 36 from which a  
 Cotton Wood in dia, bears S 59° 30' E 58 lbs



66 ~~406~~  
 Township 5 N. R. 35 E. Will Mer,  
 A Cotton Wood 5 in dia, bears N 76° 30' E 41 lks  
 do, do, do, 12 do, do, do, S 2° 30' W, 5-8 do,  
 Made Stone Mound no Tree near  
 in sec 2,  
 April 10<sup>th</sup> 1865

For general remarks  
 See general remarks after  
 the field notes of subdivisioinal  
 lines for T. 5 N, R. 35 E,  
 Book No                      Page

The surveys of the lines  
 of which the foregoing are  
 the field notes were made  
 by Deputy W. H. Colell  
 assisted by

Cyrus Dixon } Chainmen  
 H. C. Wallace }  
 Robert Axeman



To 419 510

Township No. 5 N, R. 34 E, Will. Mer,  
677. Dug pits drove charred  
Stake, and raised mound as per  
instructions,

Land hill grass poor Soil  
3<sup>rd</sup> Rate,

North between Ranges 34 & 35 on  
East boundary of Sec, 1 S 5 N  
Var, 2<sup>o</sup> East,

40.00 Set  $\frac{1}{4}$  Sec post corner 20  
Drove Charred Stake, dug  
pits, and raised Mound as  
per instructions

80.00 Set post Corner for Towns, 60  
546 N in Ranges 34 & 35 E  
on Secs 1. & 31 & 36. Land  
Slopes to the North  
Drove Charred Stake, dug  
pits, and raised Mound  
as per instructions,  
Land hill fair grass  
Soil 3<sup>rd</sup> Rate,



Surveyor General's Office  
Eugene City Aug 23 1865

The foregoing field notes of the Survey of the ~~the~~  
~~Standard Quarter North, through Ranges 31,~~  
~~32, 33, 34, 35, 36 & 37 East Will. Mer. Oregon,~~  
~~and of the~~ exterior lines of Tps. 5 North Ranges  
33, 34, 35 East Willamette Meridian, Oregon,  
executed by Odell & Lewis, Deputies, under con-  
tract No. 110, bearing date February 7<sup>th</sup> 1865,  
having been critically examined, the necessary ex-  
planations and corrections made, the said field  
notes and the surveys they describe, are hereby approved.

E. L. Applegate  
Surveyor General of Oregon.