

451

# Index

Township 4 N, Range 35 E, Will. Mer.

6	41	5	31	4	25	3	16	2	8	1
41		40		30		24		15		8
7	39	8	30	9	23	10	15	11	7	12
38		38		29		22		14		7
18	37	17	29	16	22	15	14	14	6	13
37		36		28		21		13		5
19	35	20	28	21	20	22	12	23	5	2 4
35		34		27		19		11		4
30	34	29	27	28	19	27	11	26	3	25
33		32		26		18		24		2
31	32	32	25	33	17	34	9	35	2	36

2

458

Township North, Range 35 East, Will, Mer,

and raised mound as per instructions,  
Land broken good grass,  
Soil 2<sup>nd</sup> rate,

X

East on random between sections

1 & 2,

Var 21° East =

40.00 Set temporary  $\frac{1}{4}$  section post corner

80.23 Intersected North and South line 10  
links south of post corner

S 89° 51' W on true line

40.11 Set post corner for  $\frac{1}{4}$  section.

drove charred stake, and raised stone

mound as per instruction

60.25 <sup>60.25</sup> East branch of Dry Creek, 5 lks wide 60  
course N, W,

80.23 To post corner,

Land broken, good grass

Soil 2<sup>nd</sup> rate,

North between sections 1 & 2,

13.00 Dry Creek course N, W, 5 lks wide 60

459

Township 4 North, Range 35 East, Will. Mer

40.00 Set post corner for 1/4 section on hill to  
side facing the South, drove  
charred stake, dug pit and  
raised mound as per  
instructions,

63.10 Intersected 1<sup>st</sup> Standard Parallel  
North 8.30 links west of Standard  
corner for sections 35 & 36 T 5 N. R 35 E,

At point of intersection set closing  
corner for sections 1 & 2. Drove  
charred stake dug pit and raised  
mound as per instructions

Land broken good grass  
Soil 2<sup>d</sup> rate,

+

North between sections 34 & 35

40.00 Set post corner for 1/4 section, on  
land that slopes to the North,  
drove charred stake, dug pit,  
and raised mound as per instructions

80.00 Set post corner for sections  
26.27.34 & 35 drove charred stake

80

Township 4 North, Range 35 East, Will, Mer  
Cor 21 East

- 40.00 Set temporary 1/4 section post corner,
- 79.87 Intersected North and South Line  
10 links North of Post corner,  
N 89° 56' W on true Line
- 33.67 W's branch of Dry Creek 4 links wide  
course North, +  
40
- 36.80 Boise City and Walla Walla Stage  
Road course North,
- 39.93 Set post corner for 1/4 section, above  
Charred Stake dug pit and raised  
mound as per instructions,
- 79.87 To post corner, +  
30  
Land broken good grass  
Soil good 2 1/2 rate,

North between sections 243,

- 40.00 Set post corner for 1/4 section, on level  
above charred Stake dug pit  
and raised mound as per  
instructions,
- 64.35 Intersected 1/11 Standard Parallel

17 2467

Township 4 North, Range 35 East, Will, Mer,

North 8.65 links West of Standard  
Corner for sections 34 and 35,

At point of intersection set  
Closing corner for sections 273,  
Arvoe charred Stake, dug pit,  
and raised mound as per  
instructions.

Land broken, good grass  
Soil 2<sup>d</sup> Rate.

August 21<sup>st</sup> 1866.

x

North between Sections 33 & 34.

5.25 Ditch fence course E, W,

22.50 Horse bears West 40 links

26.25 Leave field

40.00 Set post corner for 4 section drove  
charred Stake dug pit and raised  
mound as per instructions

60.55 Boise City and Walla Walla, Stage  
Road, course N, E, & S, W,

80.00 Set post corner for sections 27.28  
33 & 34, on level, drove charred

Township 4 North, Range 35 East, Will, Mer,

North between sections 3 & 4,

4000 Set  $\frac{1}{4}$  section corner, drove charred stake dug pit and raised mound as per instructions

6509 Intersected 1<sup>st</sup> Standard Parallel

North 8.30 West of Standard Corner for sections 33 & 34 T. 5 N. R. 35 E.

At Point of intersection set post closing corner for sections 3 & 4, drove charred stake dug pit and raised mound as per instructions,

Land rolling good  
grass & soil 2<sup>d</sup> rate,

North between sections 32 & 33,

2250 Wild Horse Creek 4 links wide course N. W. and enter field

3075 Leave field,

4000 Set  $\frac{1}{4}$  section post corner,

drove charred stake dug pit

Township 4 North Range 35 East Will, Nev,

80,09 Intersected ~~North~~ and south  
Line 43 links South of post  
Corner,

S 89° 42' W. on true line,

40,04 Set post corner for 1/4 section  
above charred stake Myca's Stone  
mound as per instructions 300

59,00 Pine Creek 10 links wide course N, W, 300

80,09 To post Corner 300 + 300.

Land broken good grass

X Soil 2<sup>d</sup> rate,

North between sections 4 & 5,

12,10 Pine Creek 10 links wide course N, W, 315

40,00 Set post corner for 1/4 section, in  
small ravine course S, W, above  
charred stake dug pits and raised  
mound as per instructions. 315 + 315

65,49 Intersected 1<sup>st</sup> Standard Parallel  
7.98 links West of Post corner

for sections 32 & 33. S 5 N. 12, 35 E,

At point of intersection set

Township 4 North Range 35 East

Closing corner for sections 4 & 5,  
drove charred stake dug pits and  
raised mound as per instructions,  
Land broken, good grass, soil  
2<sup>d</sup> rate,

X

North between sections 31 & 32.

4000 Set post corner for 1/4 section, drove  
charred stake dug pits and raised  
mound as per instructions,

15

8000 Set post corner for sections  
29, 30, 31 & 32, drove charred stake dug  
pits and raised mound as per  
instructions,

Land rolling, good grass,  
Soil good 2<sup>d</sup> rate,

X

East on random between sections  
29 & 32,

Bear 20° 30' East -

40.00  
4100 Set temporary 1/4 section post corner,  
79.78  
79.78 Intersected North and South line



41 491

Township North, Range 35 East, Will. Mer,

West on random between sections 64 & 7

40.00 Set temporary 1/4 section corner

77.33 Intersected North and South line

23 links North of Post

Corner,

$N 89^{\circ} 50'$  East on true line

37.33 Set post corner for 1/4 section

above charred stake by pits

and raised ground as per

instructions,

77.33 To post corner,

Land broken

75

+ Soil 2<sup>nd</sup> rule

North between sections 546.

34.00 Small Spring track course  $N 10^{\circ} E$ ,

40.00 Set post corner for 1/4 section  $\overline{40}$   $\overline{40}$ .

on side hill facing the South

above charred stake by

pits and raised

ground as per instructions:

$N 19^{\circ} 30'$  East,

65,52 Intersected ~~Point~~ Standard

6552 Parallel North 7, 8 & 9

West of Standard corner for sections 31 & 32, S, 5 N, R, 35 E,

At point of intersections

Set Closing corner for sections

5 & 6. Above charred stake by

spits and raised mound

as per instructions.

Land Broken.

Sail 2<sup>nd</sup> Rate,

All the lands in this Township are well adapted to stock raising and much of the lands in the Southern and Eastern portions are good for agricultural purposes. A considerable settlement has already been made,

August 25<sup>th</sup> 1866.

+

A list of the names  
of the persons employed to  
assist in running, measuring  
or marking the lines and corners  
described in the foregoing field  
notes of Township No 4 North of  
the Base line of Range 35 East of  
the Willamette Meridian  
Showing the respective capacities  
in which they acted.

J. J. Henderson }  
John A. Bigg } Chairman  
P. M. Dunney } Axeman,

We hereby certify that we assisted  
William H. DeBell, deputy surveyor,  
in surveying the subdivisive  
lines of Township No 4 North of  
the Base Line of Range No, 35 East  
of Willamet Meridian, and that said  
Township has been in all respects, to  
the best of our knowledge and belief  
well and faithfully surveyed and  
the boundary monuments planted  
according to the instructions furnish  
by the Surveyor General,

J J Henderson                      Chairman  
J A Figg                              Chairman  
P A Demney                         Axeman

State of Oregon }  
County of Multnomah } S.S. Subscribed  
and sworn to before me this  
22 day of September 1866

William Linnell  
Justice of the Peace

x

495

I William H. Odell,

Deputy Surveyor, do solemnly swear that,  
in pursuance of a contract with O. L.  
Applegate, surveyor of the public lands of the  
United State in the State of Oregon,  
bearing date July 2<sup>d</sup> 1866, and in strict  
conformity to the laws of the United State  
and the instructions furnished by said  
Surveyor General, I have faithfully  
surveyed the subdivisions of Township  
No 4 North of the Base Line of Range 35 East  
of Willamette Meridian in the State  
aforesaid, and do further solemnly  
swear that the foregoing are the true  
and original field notes of such survey  
William H. Odell

State of Oregon 3<sup>ps</sup>  
County of Lane 3<sup>ps</sup>

Subscribed and sworn to before  
me this 27<sup>th</sup> day of December 1866  
Loel Ware  
Notary Public.

Surveyor General's Office

Engene City January 17 1867

The foregoing field notes of the survey  
of the subdivisional lines of Township N<sup>o</sup>  
4 North Range N<sup>o</sup> 35 East Will. Mer.

Oregon, executed by William H. Odell, Dept.  
Surveyor under his contract N<sup>o</sup> 114 bearing  
date July 2nd. 1866, having been critically  
examined, the necessary corrections and  
explanations made the field notes and  
the surveys they describe are hereby approved

C. I. Applegate

Surveyor General of Oregon.