

Index

Page	10	10	11	12	12	13	14	15	15	16	17	17	18
31	32	33	34	35	36	31	32	33	33	35	36	31	32
Range 31 East													
18	20	20	21	22	23	24	24	25	26	27	28	29	30
33	34	35	36	39	32	33	34	35	36	31	32	33	34
Range 33 East													
34	32	33	34	34	35	36	36	37	38	40	40	41	42
35	36	37	32	33	34	35	36	31	32	33	34	35	36
Range 36 East													
Range 37 East													

445

copying this

6 446

We William H. Odell and William S.
 Lewis, having been appointed deputy
 Surveyors of the lands of the United
 States in Oregon, do solemnly
 swear that we will well and faith-
 fully, and to the best of ~~our~~ skill
 and ability, execute the duties
 confided to us pursuant to a
 contract with B. J. Pengra,
 surveyor general of the public
 lands in Oregon bearing date
 the seventh day of February 1865
 according to the laws of the
 United States and the instructions
 received from the said surveyor
 general.

William H. Odell,
 William S. Lewis,

State of Oregon }
 County of Washtilla } ss

sworn and subscribed
 to before me this 13th day March
 1865

J. W. Northrup
 A Justice of the Peace

447
7

We Cyrus Dixon and D. C. Wallace
do solemnly swear that we will
faithfully execute the duties of
chain carriers; that we will level
the chain upon uneven ground,
and plumb the tally pins,
whether by sticking or dropping
the same, that we will report
the true distance to all notable
objects, and the true length of
all line that, ^{we} assist in measuring,
to the best of our skill and ability

Cyrus Dixon
D. C. Wallace

State of Oregon }
County of Wmatilla } ss Sworn and
subscribed to before me this
13th day of March 1865

J. W. Northrup
A Justice of the Peace

448

~~8~~ 348

I Robert Cook do solemnly
swear that I will well and
truly perform the duties of
Axeman, according to instruc-
tions given me, and to the
best of my skill and
ability.

Robert Cook

State of Oregon }
County of Yamhill } 38 Sworn
and subscribed to before
me this 13th day of
March 1865.

J. W. Northrup
A Justice of Peace

March 15th 1865.

Commenced the survey of the first
Standard Parallel North of Base Line
and East ~~between~~ ^{through} Ranges 31. 32. 33.

34. 35. 36 & 37. between Township 4 & 5

North, at the North East Corner of
Township No 4 North in Range No 30

East of Willamette Meridian, Thence

East on South boundary of section

31 Town ⁵ North in Range 31 East,

Variation 20° East.

40.00 Set Standard corner for 1/4 sec,

Drove charred Stake and dug
Pit & constructed Mound as per
Instructions

73.00 Dry Gulch course North West 100

80.00 Set post ^{Standard} corner for sec 31 & 32. 60

Drove charred Stake and raised
Mound with pits as per Instruction

This line passes over Rolling
grounds good grass see
Timber Soil 2nd Rate

First Standard Parallel South Between
8000 Set post Standard corner for
sections 35 & 36. Land slopes to
the South, Drive Cherrred Stake
Aug pits and raised Mound
as per instructions

Land Broken good
Grass Soil good Low Rate

Cast on South boundary
of section of 36 Township
No 5 North Range 34 East,
Variation 20 East,

4000 Set post, Standard corner for
1/4 Section on level,

Drive Cherrred Stake
Aug pits and raised
Mound as per instructions,

8000 Set post Standard
Corner for sections
31 & 36, Township 5 North
in Ranges 34 & 35 East,

Townships 48 5 N, Range 34 E.

Land slopes to the North
Drove Charred Stake dug
pits and raised Mound as
per instructions.

Land on this Mile Rolling
Good Grass Soil 2nd Rate

East on South boundary of sec
31 Township 35 E N. 5 N.

Var 20° E -.

40.00 Set post Standard corner for
1/4 Sec. Land slopes to the East
Drove Charred Stake, dug pits,
and raised Mound as per
instructions.

80.00 Set Standard Corner for sections
31 & 32, on hill slope to the E 100
From which a Pine
20 in in dia, B ~~Set~~ S 88° E 57 1/2 ths
A Balm 10 in do to N 60° E 3 1/3 "

The pine stands on opposite
side of pine Creek in edge.

First Standard Parallel North between
 of Water Back - too steep
 and the Water too deep
 to put the proper
 Markers on the Pine
 dug pits and made
 Mound as per instructions
 Land quite broken
 Good Grass Soil 2nd Note

East on South boundary of
 Sec 32 Township No. 5 N, R. 35 E,
 Bar 20th.

500 Pine Creek 25 lbs wide Course 20

N. Some scattering
 timber along Creek

40.00 Set post corner for 1/4 sec 140

Drape Charred Stake

Dug pits and made

Mound as per instructions

80.00 Set post Standard Corner

for sections 32 & 33, on level

Township 445 North Range 35 East Will. Mer,
Drove Charred Stake dug pits and
raised mound as per
instructions.

Land on last half mile
gently rolling good grass
Soil good 2nd rate.

East on South boundary of section
33 Township N^o 50. R 35 East
Bar 20° E.

40.00 Set standard corner for 1/4 Sec
on level, Drove Charred
Stake, dug pits, and raised
Mound as per instructions

59.00 Blage road from Walla Walla
to Grand Round
Course c. E. 43. N.

80.00 Set post corner for sections
33 & 34, on level, Drove
Charred stake, dug pits
and raised mound as per
instructions

First Standard Parallel North Bet
Land Rolling good grass
Soil 2nd Rate

East on South boundary of
Section 34 Township N^o 5 N,
Range 35 East
Bar 20^o East

40.00 Set post Standard corner for
1/4 Section on level,
Drove charred Stake dug
pits and raised Mound
as per instructions.

80.00 Set post Standard corner for
Sections 34 & 35. on level,
Drove charred Stake, dug
pits, and raised Mound.
as per instructions.

Land on this line
gently undulating
good grass Soil
good 2nd Rate

even Townships 445 N. R 35 E. Will, Mer,
East in South boundary of
section 35 Township 45 N.
Range 35 East

Bar 20° E.

3750 Wagon Road up Dry Creek 120
Course South

3850 One division of Dry Creek 12
Course North

4000 Set post Standard corner
for 1/4 section, Drove charred
Stake and Made Mound
of Stones as per instructions

4050 The remaining portion of
Dry Creek 20 fms Wide Course
North.

4400 Commence to ascend hill

8000 Set post Standard corner
for sections 35 & 36 +
130
Drove charred Stake,
dug pit and raised
Mound as per
instructions

First Standard Parallel North Between
This line passes over
Broken Land good grass
Soil good 2nd Rate

East on South boundary of
Section 36 Township 5 N. R. 35 E.
Cor 20 E.

40.00 Set post Standard Corner 30
for 4 Section on Ridge
Drove charred Stake, dug
pit and raised mound
as per Instructions.

80.00 Set Standard Corner for sections
36 & 37 in Townships 5 North
Ranges 35 & 36 E. on side
hill sloping to the North
Drove charred Stake
dug pits, and raised
mound as per
instructions

Land Broken good
grass Soil good 2nd Rate

Townships 4+5 north In Range 34 East.

Fir Tree 20 inches in diam N. 24° 31' E. 19 Sinks

Fir Tree, 10 do do do S. 4° 30' W. 80 do

Fir Tree 8. do do do N. 73° W. 60 Sinks.

This Line Passes through Heavy
Timber Fir, Pine & Larch.

Undergrowth Same & Vine
Maple. Land gently rolling.

This Standard line passes
over high rolling lands
covered with good grass
along the whole extent
affording an extensive
range for stock, But
from the fact that water
is scarce over most of the
distance the land will
not be considered very
valuable until enterprise
shall sink wells to
give water to stock,

which can be done
 at very little expense,
 The timbered lands
 in the Mountains
 are considered valuable
 and would soon be
 entered by the settlers
 in the Valley if offered
 at public or private
 sale.

The Standard Parallel of
 which the foregoing are the
 field notes was surveyed
 Deputy W. H. Odell assisted
 through Ranges 31, 32, 33, 34, 35
 & 37 by Cyrus Dixon } Chairman
 D. C. Wallace }
 Robert Cook } Axeman
 Through Range 36 by
 W. W. Johnson Compassman
 C. C. Harcane } Chairman
 A. Shibles }
 William Warren Axeman

I William H. Odell, do hereby
certify that the foregoing are
the true and original field notes
of the survey of the First
Standard Parallel North
between Townships 5 & 6
North and East through
Ranges 31, 32, 33, 34, 35, 36 & 37,
East of Willamette Meridian,
made under contract No. 110,
bearing date February 7th 1865,
in accordance with the laws
of the United State and the
Instructions furnished by the
Surveyor General, as will appear
from affidavits duly made out
and attached to the field notes
of Township No. 5 North of Range
~~36~~ East of Will; Mer;
William H. Odell
Deputy Surveyor

Surveyor General's Office
Eugene City, Aug. 23, 1865

The foregoing field notes of the survey of
the 1st Standard Parallel North through
Ranges 31, 32, 33, 34, 35, 36 and 37 E
Will. Mer. Oregon, executed by Odell &
Lewis, Deputy Surveyors, under their con-
tract No. 110, bearing date Feby. 7th
1865, having been critically examined
the necessary explanations and corrections
made, the said field notes and the Sur-
veys they describe are hereby ap-
proved.

E. L. Applegate
Surveyor General of Oregon.