

54 ~~394~~

494
Index

To Exterior lines of Township N^o 5 N, R^o 34 E.

See Page 67

71	72	73	73	74	75	
6	5	4	3	2	1	70
						12 69
						13 69
						24 68
						25 67
						36 67

Thursday March 23rd 1865

Commenced the survey of the Exterior
Lines of Township No 5 North of Base
Line in Range 35 East of Willamette
Meridian, At the South East Cor,
North between Ranges 35 & 36 on East
boundary of section 36, in
Township 5 North

Variation 20° E

2800 A Settlers house bears East about 2000

4000 Set post corner for 1/4 section on
side hill facing the East.

dug pits, drove Charred
Stake, and raised earth Mound
as per Instructions,

7300 A Wagon Road Course N. W.

8000 Set post corner for sec 25 & 36. 30 & 31,

on hill side facing the East,

drove Charred Stake, dug pits
and raised Mound as per
instructions. This line passes

along hill side sloping to the East

Good Grass Soil good ^{good} ~~good~~ Kaley

Township No 5 North Range 35 East of Will, Mex.

1912, 647. Land gently slopes to the N.E.

Drove Charred Stake, dug pits, and raised Mound as per instructions.

This line passes up rocky hill on the South half, the North half over gently rolling ground good grass soil Good 2nd rate,

North, between ~~between~~ Ranges 35 & 36 Township No 5 North, on east boundary of section 1.

Variation 21° East

40.00 Set post corner for 1/4 section on level Drove charred, stake, dug pits, and raised Mound as per instructions.

80.00 Set post corner for Townships 5 & 6 North, in Ranges 35 & 36 East and Sections 1, 6, 31, & 36.

50

Drove charred stake, dug pits, and raised Mound as per instructions This line passes down gently.

60 ~~400~~ 500

Township No. 5 North Range 35 East Will. Mex.
descending grounds good grass
Soil good 2nd Rate.

West on North boundary of sec
1 in Random Township 5 N
Range 35 East

Variation 21 East,

March 25th 1865,

35.50 Wagon Road Course N, E,

37.50 Enter Creek bottom 90

40.00 Set post corner for 1/4 Section
Drove Charred Stake, and
Raised Stone Mound as per
instructions

43.25 Creek 75 lbs wide course North

51.60 do, 50 do, do, do, do,

65.50 Road course North,

80.00 Set temporary post corner
for sec. 1 & 2. 35 & 36

Level level, Soil 2nd Rate
on East half, on West rocky.

Surveyor General's Office
Eugene City Aug 23 1865

The foregoing field notes of the Survey of the ~~the~~
~~Standard Quarter North, through Ranges 31,~~
~~32, 33, 34, 35, 36 & 37 East Will. Mer. Oregon,~~
~~and of the~~ exterior lines of Tps. 5 North Ranges
33, 34, 35 East Willamette Meridian, Oregon,
executed by Odell & Lewis, Deputies, under con-
tract No. 110, bearing date February 7th 1865,
having been critically examined, the necessary ex-
planations and corrections made, the said field
notes and the surveys they describe, are hereby approved.

E. L. Applegate
Surveyor General of Oregon.