

Index
 To the Field notes to the
 Exterior lines of Township No. 5
 North. Range 36 East Will. Mer.

51	52	53	54	55	56
6	5	4	3	2	1

49

 12 48

 13 48

 24 47

 25 46

 36 46

Copy this

Township 5 North Range 36, East,
Township 5 North Range 31, East
Variation 21° East.

40,000 Set 1/4 Sec Post Drove Charred
Stake, Dug Pit - raised
mound as per instructions.

80,000 Set Post Corner for Sec 1, 12,
64, on Hill Side facing
East, Drove Charred Post,
Dug Pit - raised mound
as per instructions.

North on east boundary
of section 1, T5N, R36E,
Var 21° E.

28,000 Road course N, W,

40,000 Set 1/4 Section post,
Drove Charred Stake
Dug pits and
raised mound as per
instructions.

80,000 Set post corner for
Townships 5 & 6 North.

50 574

674

Township 5 N Range 36 East
Ranges 36 & 37 East
Drove chert
Stake dug pits and
raised mound as
per instructions.
Land Rolling
Grass good
Soil good 2 $\frac{ac}{11}$
Route

West on Buncom
on North boundary
of Township 15 N
Range 36 East,
Bar 21^o 9,

April 4th 1865
On North town
at 40 and 80 chs
set temporary
 $\frac{1}{2}$ mile and still
post, 478.44

Township 5 N, R. 36 E, Will. Mer,
 Intersected North and
 South Town Line 2, 24 chs
 South of post, hence the
 correction will be 37 the
 North per mile, Course
 S, 89° 44' E.

S 89° 44' E on true line
 on North boundary of
 Section 6 5, 5 N, R, 36 E,
 Var, 21° E,

35 22
~~28 56~~

Set 1/4 Sec post on level
 Drove Charred Stake,
 dug pits, and raised
 Mound as per instructions

28 44

Set post corner for Secs
 5, 6, 31, & 32, on level,
 Drove Charred Stake,
 dug pits and raised
 Mound as per
 instructions
 Land gently

Township 5 N R 36 E Willkie,
 Rolling Good
 Grass Soil good
2^d Rate

3,89° 44' E, on true
 line on North
 boundary of
 Section 5
 T 5 N, R 36 E,
 bar 21° E,

40,00 Set 14 Dec post on
 level, Drove
 Charred post, dug
 pits, and raised
 mound as per
 instructions

80,00 Set post corner for
 sections 4, 5, 32 & 33
 Drove Charred stake
 dug pits and
 raised mound
 as per instruction

Township 5 N, R. 36 E, With Mer,
 Land gently rolling
 Good grass soil
Good 2nd Rate

S 89° 44' E on true line
 on ~~North~~ boundary of
 Section 4 T. 5 N, R. 36 E,
 Var, 2.1° E,

- 40.00 Set 4 Sec, post on level
 Drove charred stake, dug
 pits, and raised mound
 as per instructions,
- 45.40 Road course N, & S,
- 80.00 Set post corner for sections
 3, 4, 33, & 34. Drove charred
 stake, dug pits, and raised
 mound as per instructions,
 Land Rolling
 Grass Good Soil
 Good 2nd Rate

Township 50 N, R. 36 E, Will, Mer,
 S 89° 44' E on true line
 on North boundary of
 Section 35 N, R. 36 E,
 Var 21° E -

340 Road Course N,
 40,00 Set 1/4 sec post, Drove
 Charred Stake, dug pits,
 and Raised Mound as
 per instructions,

80,00 Set post corner sections
 2, 3, 34 & 35. Drove Charred
 Stake, dug pits, and
 Raised Mound as per
 instructions,
 Land slopes to the
 West,

Grows good soil
 Good 2nd Rate,

Township 5 N, R 36 E, Will, Mer,
S, 89° 44' E, on true line on North
boundary of section 2 T 5 N, R 36 E,
Lat 21° E.

40.00 Set 1/4 Section post. Drove +
60
charrred stakes, dug pits,
and raised mound as
per instructions.

~~80.00 Set post corner for Townships
5 & 6 N Ranges 36 & 37 East,
Land broken Grass
Good Soil 2nd Rate~~

W. H. H. H.

80.00 Set post corner for sections 1. 2. 35 & 36
Drove charrred stake, dug pits and
raised mound as per instructions
Land broken Grass good
soil good 2nd Rate

Township 5 N R 36 E, Will, Minn,
 S. 89° 44' E, on true line
 on North boundary of
 section 1 T 5 N R 36 E,
 Var 29° E.

4000 Set 4 Section post
 Drove charred stakes,
 Dig pits and raised
 shown as per
 instructions,

80.00 Set post corner of
 Townships 5 & 6 N
 Ranges 36 & 37 E.

Land broken
 Grass good soil
Good Land Rate,

For General remarks see
 Note for subdivisional lines
 The survey of the foregoing
 lines was made by
 Deputy W. H. Bell
 assisted by

Cyrus Dixon
D. C. Wallace
Robert Cook
Chairmen
Herman

I William H. Odell do hereby certify
that the foregoing field notes of the survey
of the Exterior Lines of Township No. 5
North of Base Line of Range No. 36 East of
Will. Mer., in State of Oregon, made under Contract
No. 110 with B. J. Perry as Surveyor general and
bearing date Feb. 7th 1865, in accordance
with the Laws of the United States and the
Instructions furnished by the Surveyor
General; as will appear from affidavits
duly made out at the close of said
Contract and attached to the field
notes for the survey of Township No. 5
N Range 36 East Will. Mer.,
William H. Odell
Deputy Surveyor

624

Surveyor General's Office
Eugene City, Aug. 23^d 1865

The foregoing field notes of the Survey of the Exterior
lines of ~~Tps. 4 N. R. 31, 32, 33, & 4 East; and of~~
Tps 5 N. Ranges 31, 32 and 36 East; and of
Tps 6 N. Ranges 34, 35 and 36 East, Will. Mer,
Oregon, Executed by Odell and Lewis under contract
No. 110 bearing date February 7th 1865, having
been critically examined, the necessary explanations
and corrections made, the said field notes and
the surveys they describe are hereby approved.

E. L. Applegate
Surveyor General.