

501

Index

Township 4 North, Range 36 East, Will, Mer,

6	41	5	31	4	24	3	16	2	8	1
40		39		30		23		16		8
7	39	8	29	9	22	10	15	11	7	12
38		37		29		22		14		7
18	37	17	28	16	21	15	14	14	6	13
36		36		28		21		13		6
19	35	20	27	21	20	22	12	23	5	24
34		34		27		19		12		4
30	33	29	26	28	19	27	11	26	4	25
32		32		25		18		10		3
31	31	32	25	33	17	34	9	35	2	36

Field Notes of the
 Subdivision lines in Township
 4 North of the Base Line of Range
 36 East of Willamette Meridian

Commence at post corner for
 sections 1, 2, 3, 5 & 36, on south
 boundary of Township

Hence

North between sections 35 & 36,

15.00 Pine Creek channel dry course W, 140

40.00 Set post corner for $\frac{1}{4}$ section from 130

Which a Pine 30 in dia bears N 85° W 165 Links

do. do, 36 do-do-do- South 300 do-

80.00 Set post corner for sections 25, 26, 35 & 36.

from which

a Fir 24 in dia bears N 40° W, 22 links

do, do, 7 do, do, do, S 15° E 13 do,

do, do, 10 do, do- do- S 20° W, 19 do,

do- Willow 4 do- do- do- N 35° E, 21 do-

The north $\frac{1}{2}$ of this mile passes

9 ⁵⁰⁹
Township 4 North, Range 36 East, Will. Mer,

North between sections 1 & 2,

37.25 Creek channel dry course West 500

40.00 Mound Stone corner for $\frac{1}{4}$ section 775

on steep hill side, facing the South, set Bassalt Stone

6 x 12 x 18,

68.44 Intersected 1st Standard North 400

12.87 West of Standard corner for sections 35 & 36, T. 5 N, R. 36 E.

Set Closing corner above channel stake, and raised Stone Mound as per instructions,

Land very broken
good grass, soil stony,
X September 27th 1866,

North between sections 34 & 35,

40.00 Set post corner for $\frac{1}{4}$ section from which

A Pine 36 in-dia-bears S. 60° W, 26 links

do - do - 10 do - do - do - N. 62° E, 18 do -

55.00 Pine Creek channel dry course W 250

Township 4 North, Range 36 East, Will, Mer.

16
516

X Soil 2^d rate,

East on random between sections 2 & 11
Bar 20° East

40.00 Set temporary $\frac{1}{4}$ section corner

8066 Intersected North and South line

49 North of post corner,

N 89° 39' W on true line

35.00 Bottom of ravine course North

500

40.33 Made ^{Corner on} Bassalt Boulder 36 x 42. and

as deep as may be, on steep hillside ⁴⁰
facing the East,

8066 To post corner,

Land broken, good grass,

X Soil 2^d rate,

North between sections 2 & 3.

20.75 Creek 5 links wide course West

500

40.00 Set Bassalt Stone 7 x 9 x 14 corner
for $\frac{1}{4}$ section.

150

68.50 Intersected 1st Standard

170

Parallel North 1273 West

17/2 517

Township 4 North, Range 36 East, Will. Mer,

of corner for sections 33 & 35

T5 NR 36 East

Set post Closing corner
for sections 2 & 3, drove charred
stake, and raised mound of stones
as per instructions,

Land broken, good grass,

Soil 2^d rate,

+ October 4th 1866.

North between sections 33 & 34,

375.0 Pine Creek channel dry course W, 275 275

40.00 Set post corner for $\frac{1}{4}$ section + 15

drove charred stake, raised mound
stone mound as per instructions

80.00 Set post corner for sections 27, 28,

33 & 34, from which

A Pine 30 in dia bears - S 37° E 119 links

do - do - 36 do - do - do - N 1° E 106 do -

do - do - 24 do - do - do - N 85° W 144 do -

no tree near in section

35, Land broken,

Township 4 North, Range 36 East, Will, Mo.

60.00	Summit of ridge course North	300
77.50	Bottom of drain course North	340
79.67	To post corner	30

Land very broken

X good grass Soil 2^d rate

North between sections 3 & 4.

15.75	Crack 5 links with course West.	50
40.00	Set Bassalt Stone 6 x 12 x 14. for $\frac{1}{4}$ section corner	300

68.23 Intersected the 1st Standard Parallel North 12 30 West of post corner for sections 33 & 34 T. 5 N. R. 36 East, Set post Closing corner for sections 3 & 4. Above churruet stake dry pits and raised mound as per instructions.

Land broken good grass Soil 2^d rate

X October 5th 1866.

Township 4 North, Range 36 East, Will. Mer,
 good grass soil 2^d rate,

North between sections 4 & 5,

1.50 Creek 5 links wide course West 50

40.00 Set Basalt Stone 6x9x15 +
 200

for $\frac{1}{4}$ section corner,

6.9.10 Intersected 1st Standard Parallel

North 12.43 West of post corner

for sections 32 & 33,

Set post Closing corner for

sections 4 & 5 drove churred

stake dug pits and raised

ground as per instructions.

Land broken

good grass, Soil 2^d rate,

October 7th 1866,

X

North between sections 31 & 32,

17.00 Pine Creek course West 300

40.00 Set Basalt stone 5x9x15 corner +
 300

for $\frac{1}{4}$ section,

80.00 Set post corner for sections

414 541
Township 4 North, Range 36 East, Will. Mer,

Stake, clay pits and raised
mound as per instructions

76.80 To post corner,

Land broken, good
grass Soil 2 $\frac{1}{2}$ rate,
X

North between sections
5 & 6.

26.00 Enter field course of fence 70
N. W.

40.00 Set post corner for $\frac{1}{4}$ section ²⁰ 70
drove charred stake dug pits
and raised mound as
per instructions,

57.75 Creek 6 links wide course West 60

64.00 Leave field.

68.41 Intersected 1st Standard 30

Parallel 1271 links West
of post corner for sections
31 & 32 T5 N Range 36 East,
Set closing corner for
sections 5 & 6. Deposited

Y
 Township 4 North, Range, 36 East, Will, Mer.

marked Stone and Mark
 Stone Monnet as per
 instructions.

Land broken good
 grass. Soil good
 L. & W. note,

X

These are some six or seven
 settlers in this Township holding
 Claims under the preemption
 law and a considerable
 portion of the Township
 will be entered whenever
 there is an opportunity given
 to the Farmers in Walla Walla
 Valley for the timber;
 which is very palatable,
 October 10th 1866.

543

Names of the persons employed

to assist in running
measuring or marking the
lines in corners of the
Subdivisions of Township
No. 4 North of Range 36 East
of Willamette Meridian
Showing the respective
capacities in which
they acted.

John A. Bigg } Chairman
Charles D. Harchitz }
Samuel C. Harchitz Assessor

I hereby certify that I assisted
 William H. Odell, Deputy Surveyor
 in surveying the exterior boundary
 and subdividing Township
 number four (4) North of Base
 Line of Range thirty seven (37)
 East of Willamette Meridian,
 and that said Township
 has been in all respects to the
 best of my knowledge and
 belief well and faithfully
 surveyed and the boundary
 monuments planted accord-
 -ing to the instructions
 furnished by the Surveyor General
 of A. Trigg Chairman

State of Oregon }
 County of Umatilla } SS Subscribed
 and sworn to before me this
 25th day of October 1866.

William Senallen Justice of the Peace

We hereby certify that we assisted
 William H. Odell Deputy Surveyor
 in surveying the exterior boundaries
 and subdividing Township number
 four North of the Base Line of Range
 No, thirty six East of Willamette
 meridian, and that said
 Township has been in all respects
 to the best of our knowledge
 and belief, well and faithfully
 surveyed and the boundary
 monuments planted according
 to the instructions furnished
 by the Surveyor General.

C. D. Hardisty Chairman

J. C. Hardisty Assessor

State of Oregon

Umatilla County ss. Subscribed and

sworn to before me this

22 day of November 1866.

+ William L. S. Allen J. P.

I William H. Odell, Deputy surveyor,

do solemnly swear that, in pursuance of a contract with C. F. Applegate surveyor of the public lands of the United States in the State of Oregon, bearing date July 2nd 1866, and in strict conformity to the laws of the United States and of the instructions furnished by said Surveyor General, I have faithfully surveyed the subdivisions of Township No 4 North of the Base Line of Range 36 East of the Willamette Meridian, in the State aforesaid, and I do further solemnly swear that the foregoing are the true and original field notes of such survey

William H. Odell

State of Oregon }
County of Lane } ss.

Subscribed and Sworn to before me this 12th day of January 1867,

Joel Ware
Notary Public

Surveyor General's Office
 Eugene City Jan 17, 1869

The foregoing field notes of
 the survey of the subdivisions
 of Town 4 N R 3 E & W 1/2
 nor are executed by Wm
 McCall dep Sur under
 contract No 114 dated
 July 2nd 1866. Having
 been critically examined
 the necessary explanations
 and corrections made the
 said field notes and the
 surveys they describe are
 hereby approved

E. L. Applegate
 Sur Genl of Ore