

40390

General Remarks,

This Township is well adapted to grazing, the grass is excellent, and abundant, There are several good Springs one of which is at the point selected for a Stage station on the route from Wallula to Rainier Town in Grande Ronde Valley,

This Route passes nearly diagonally through the Township from the N. W. to the S. E.,

The Lands are high and broken, not suited to Cultivation,

I William S. Lewis do hereby certify that the foregoing are the true and original field notes of Township No. 1, R. 33 E., as will appear from Affidavits duly made, at the Close of Contract No. 119, and attached to the field notes of the Exterior Lines

Commenced the Survey of the Subdivis-
ional lines of Township 5. North
Range 36, East of Willamette Meridian,
May 12th 1865

North between Secs 35 & 36,
Town 5. N., Range 36. E.
Var 21° E

4000 Set 1/4 Sec Post on top Hill side
facing deep Canyon to the West.
Drove Charred Stake, Dug Pit
and raised mound as per Instruc-
tions.

8000 Set Post corner for Secs 35, 36,
35 & 36, on High Hill sloping
to the north, Drove Charred
Stake, Dug Pit & raised
mound as per Instructions.
Land Broken Grass 2^d Rate
Soil poor 2^d Rate,

East on Random between Secs
35 & 36, Town 5. N., R. 36. East,

4000 Set temporary 1/4 Sec Post

46 396

Township 5. N. R. 36, East Hill, M.
79.70 Intersect north & south town line
30 Sinks north of Post from
which I run N. 89° 47' W.
on a true line.

89.75 Set 1/4 Sec Post on east side
of Steep Hill, one chain from
summit, drove chand
stake, dry & set pit raised
ground as per instructions

51.00 Crossed Walla Walla River from
north West.

79.70 To Post corner.

Saw Broken, soil good
on River bottom, quite plenty
of Timber. Palm, Birch,
Alder, Pine.

X

North between Secs 25 & 26,
Town 5. N. Range 36, East
1/4 Sec 21, East.

2450
~~XXXX~~ Crossed Walla Walla River
from N.W.

Township No 5 North Range 3, E. Hill, Mex.
 4000 Set 1/4 Sec Post. Made Stone
 mound, and drove chanced
 stake as per instructions
 8000 Set Post Corner for Secs 23, 24,
 25 & 26, Near Summit of Hill +100,
 facing the East, drove chanced
 stake, Dug pits & raised
 mounds as per instructions
 Sand Broken, Soil on River
 Bottom 2^d Rate, Timber on
 flat Balsam, Birch, Alder,
 and some Pine.

East on Raudem between Secs 24 & 25
 Town 5 N, R 3 E, East

4000 Set temporary 1/4 Sec Post.
 7990 Intersect, north to South Town line
 40 Sinks, north of Post, from
 which I run N, 89° 43' W,
 on a true line.

3995 Set 1/4 Sec Post. Drove chanced
 stake, Dug pits & raised

48
398

Township No 5 North R. 36. E. Mill. M.
Mound as Per Instructions

79,900 To Post corner,

Land Very Broken, Grass
Poor. Soil 3rd Rate.

North between Secs 23 & 24
Town 5 N. Range 36, East
Var 21^o East.

40,000 Set 4 Sec Post Wore Chased
Stake Dry Pits & raised
Mound as Per Instructions

51,250 To north Fork of Malla Wella
River

80,000 Set Post Corner for Secs 13, 14,
23 & 24. Wore Chased Stake
Dry Pits & raised Mound as
Per Instructions.

Land Broken, Soil on Flat,
1st Rate, Some timber
Balm, Alder, Birch
& Pine.

Township No 5. N. Range 36. E. Hill. Min.

East on Random between Secs 13 & 24,
Town 5. N. Range 36. E.

40,000 Set temporary 1/4 Sec Post.
8000 Intersect north & south town line
at Post, from which I run
N. on a true line

40,000 Set 1/4 Sec Post on side Hill
facing to the South East,
Wrote Chas. State, Wright
and raised mound, as per
instructions.

8000 To Post Corner
Land very broken soil
good 2nd Rate good grass.

North between Secs 13 & 14,
Town 5. N. Range 36. East.
Tan 21° E.

40,000 Set 1/4 Sec Post on top Hill
side facing East, few chains
from Summit.

51, 469

Township T. 5. N., Range 36, East, Hill, Mo.,
Drove Charred Stake, Dry
Pit & raised mound as
Per Instructions.

8000 Set Post Corner near ⁺¹⁰⁰ Summit
of Hill, on side facing
west & north, for Secs 11, 12,
13 & 14, Drove Charred Stake
Dry Pit & raised mound
as Per Instructions.

Said Broken Grass
good. Soil D. Rate.

East on Random between Secs 12 & 13,
Town 5. N., Range 36, East,

4000 Set Temporary 1/4 Sec Post.

8010 Intersect North & South Town line.

40 Sinks South of Post, from
which I run, S. 89. 37. W.,
on a true line.

4005 Set 1/4 Sec Post Drove
Charred Stake, Dry Pit &
raised mound as Per Instructions.

51
400

Township No. 5. N., Range 36, East, Hill, Mo.,
S. 10 Post Corner

Sand Rolling, grass good
Soil 2^d Rate,

North between Secs 11 & 12,

Town 5. N., R. 36, East.

Var 21st C.

4000 Set 1/4 Sect Post Wore Chared
Stake, Dry Pits - raised
Mound as Per Instructions

8000 Set Post Corner for Sect 1, 2, 11 & 12
South of Ravine near foot of Hill
Sloping to the North, Wore
Chared Stake, Dry Pits
raised Mound as Per
Instructions. Sand
Rolling grass good
Soil 2^d Rate,

East on Random between 11 & 12,

Town 5. N., R. 36, East.

4000 Set temporary 1/4 Sect Post.

52 402

Township No 5 N, Range 36 E Mill, W,
79.90 Intersect north & south Town line,
60 Sinks south of Post, from
which I run S. 89° 34' N. on
true line.

39.95 Set 1/4 Sec Post & were changed
Stake, dry pit & raised
mound as Per Instructions.

79.90 To Post corner.
Land Rolling, grass good,
Soil 2^d Rate.

May 15th 1865.

North on Random between Sec 1 & 2,
Town 5 N, Range 36 East,
Variation N. East.

44.00 Set Temporary 1/4 Sec Post.

79.60 Intersect north & south Town line
50 Sinks west of Post, from
which I run S. 22' N. on a
true line

39.60 Set 1/4 Sec Post & were changed
Stake dry pit & raised
mound as Per Instructions.

Township No 5 North, Range 36, E. Will, M.
7960 To Post Comm.

Land Broken, grass good
Soil 2^d Rate,

North between Secs 34 & 35,
Town 5, North, Range 36, East,
Van 21^o East.

40,000 Set 1/4 sec Post Drive Chama
Stake Dry Pits & raised
mounds as per Instructions
80,000 Set Post Comm for Secs 26, 27,
34 & 35, Drive Chama Stake
Dry Pits & raised mounds
as per Instructions,
Land Broken, grass good,
Soil 2^d Rate,

Eastern Radium between Secs 26 & 35,
Town 5, N., R., 36, E.
~~Van 21^o E.~~

40,000 Set temporary 1/4 Sec Post,
80,000 Intersect north & south line.

574 404

Township No 5 N, R 36, E, Mill, M.
at Post, from which I run
N. on a true line.

4000 Oct 14 Dec Post, I run chain
Stake by Pils; & raised
Mound as Per Instruction.

5000 To Summit of Hill.

7800 to foot of Hill

8000 To Post corner

Land Broken, grass good,
Soil 2^d Rate.

North between Decs 26 & 27,
Town 5, North, R, 36, E,
Twp 21^o E.

4000 Oct 14 Dec Post on steep Hill + soft
side facing River on the East,
made stone mound, set chain
Stake as Per Instruction.

7300 To South, Foot of Wall of Hill,
River corner NW.

8000 Set Post corner for Decs 22, 23,
26 & 27, I run chain stake

Township 5 S, R 36 East Will, Mo.
and made Stone Mound as
Per Instructions. Sand Very
Broken, Soil good on River
Bottom, Timber Balm, Birch
Alder & Pine.

+ North between Sec
East on R and on between Sec
23+26, Town 5, N, R 36, East.

40,000 Set temporary 1/4 sec Post.
80,20 Intusect north & south line
30 links south of Post. from which
I run S. 89° 47' W. on true
line.

40,10 Set 1/4 sec Post. Wove changed
state. Wny Pil & raised mound
as Per Instructions.

~~70,000~~ ~~Full North North River South Fork,~~
80,20 To Post corner,
Sand Rolling. Grass good
Soil 2^d Rate.

51 406

Township No 5, N, R, 36, East Hill, M.

North between Secs 22 & 23.

Town 5, N, R, 36, East,

Variation 21° East.

40,000 Set 1/4 Sec Post near Run ⁺²⁵⁰ =
mit of divide between north
& south forks of Mallakalla
River Drove Chained Stake
& made Stone Mound as
Per Instructions.

56,000 North fork of Mallakalla River ⁺²⁵⁰
50 Sinks wide Corns West.

80,000 Set Post corner for Secs 14, 15,
22 & 23, Drove Chained Stake
Dug pits & raised Mound
as Per Instructions.

Sand & broken Soil on Bottom
1st rate. Some Timber
Balm, Birch, & Alder.

57
407

Survey m. S. N. R 36, East, Hill, Tenn.

East on Random between Sec 14 & 23 & 14, Town S. N. R 36, East,

4000 Set temporary 1/4 Sec Post
8000 Intersect north & south line
at Post, from which I run
W. on a true line.

~~4000~~ To South West Corner of field
bearing north 10 Links.

4000 Set 1/4 Sec Post, Drive chain
Stake, Dry Pile & raised mound,
as per Instructions.

8000 To Post corner.

This line passes over spurs of
ridges running to the Wallaces
River. good grass.

North between 15 & 14,
Town S. N. Range 36, E.
Var 21° E.

4000 Set 1/4 Sec Post, Drive chain
Stake, Dry Pile & raised

58 408

Township 5 N, R. 36, E. Mill, Mo.
ground as per instructions

54.50 To Road. Cross West of North,
8440 Set Post corner for 8440

~~4445~~ find ~~4445~~

75.00 crossed Road again.

80.00 Set Post corner for Sec 10, 11.

14+15, drove chanced stake
Dug Pili & raised mound,
as per instructions.

Land gently rolling, grass
good Soil 2. Rate.

+

East on Radium between Secs
11+14, Town 5 N, R, 36, E.

40.00 Set temporary 1/4 sec Post

79.90 Intused north-south line
in Sink, south of Post, from
which corner S. 89° 57' N,
on a true line.

39.95 Set 1/4 sec Post drove chanced
stake, dug Pili & raised
mound as per instructions

59
409

Township No 5, N, R, 36, E, Mill, Minn,
79,90 To Post Corner

Sand Broken, Soil 2^d Rate
Good grass,

North between Secs 10 & 11,
Town 5, N, R 36, E,
Twp 21, E.

40,000 Set 1/4 Sec Post Stone Choned
Stake, Dug Pits & raised mounds
as per instructions.

80,000 Set Post Corner for Secs 7, 8,
10 & 11, Stone charred stake
Dug Pits & raised mounds as
per instructions.

Land gently Rolling. Grass
good, Soil 2^d Rate,

~~West~~ East
Random between Secs 2 & 11,
Town 5, N, Range 36, E.

40,000 Set temporary 1/4 Sec Post.

80,300 Intersect north & south line

40 40 Sink South of Post, from

which I run S. 89° 43' W.
on a true line

40.15 Set 1/4 Sec Post Drive Chano
Stake, Dry Pit - raised
mound as per instructions.

81.30 To Post corner

Sand Rolling, grass good,
Soil 2nd Rate.

x

May 16th 1865

North on Raudon between Sec
20th. Town S. N., Range 36, East
7th 21st East.

40.00 Set temporary 1/4 Sec Post.

79.50 Intersect East & West Town line
30 Links West of Post, from
which I run S. 13' W. on
true line

39.50 Set 1/4 Sec Post, Drive Chano
Stake, Dry Pit - raised
mound as per instructions

79.50 To Post corner. Sand Rolling
grass good, Soil 2nd Rate.

61
411

Township T5. N. Range 36. E. Hill, Mo.

North between Secs 33 + 34,
Town 5. N. Range 36. E.
Var 21° East.

4000 Set 1/4 Sec Post near Ravine
Hill side facing both West.
Drove Chared Stake, Wry's
+ raised Mound as Per Instruc

8000 Set Post corner for Secs 27, 28,
33 + 34, Drove Chared Stake
Day's Pil. + raised mound, as
Per Instructions. Sand Rolling
Grass good Soil 2' Red,

East on Radium between Secs
27 + 34, Town 5. N. R. 36. E.

4000 Set temporary 1/4 Sec Post
8000 Intersect with south line
50 Sinks north of Post, from
which I run N. 89° 38' W.
on two lines.

4010 Set 1/4 Sec Post. Drove chared

62 412

Township No 5, N. R 36, East Hill, Minn
Stake, dug pits & raised
ground as per instructions,
8000 To Post corner.

Sand Rolling grass good
Soil 2^o Rate, This line
Passes near some springs,

North between Secs 27 & 28,
Town 5, N. Range 36, E,
Twp 21, E.

4000 Oct 14 Sec Post Drove Charred
Stake, dug pits & raised
ground as per instructions

8000 Oct Post corner, for Secs 21, 22,
28 & 27, Drove charred stake,
dug pits & raised ground
as per instructions, Sand
Broken, Soil good 2^o Rate, &
good grass,

63
413

Township No 5, N, R 36, E, Mill, Mo.

East on Raudon between Secs 22, 27
Town 5, N, Range 36, E.

40.00 Set temporary Post.

80.19 Intersect with south line

40 links south of Post, from
which I run N. $89^{\circ} 43'$ W. on
true line.

11.00 Crossed Road. Course S, E.

40.09 Set $\frac{1}{4}$ Sec Post & were changed
State by Pitt & raised
marked as per instructions

70.00 Mallakalla River south fork.
50 links wide Course N, W.

80.19 To Post corner

Sand Broken Soil 2nd Rate
grass, good, Sand along
River timbered.

64 404

Township No 5, N., R 36, East Hill, M.

North on East boundary Sec
between Secs 21 & 22,

Town 5, N., Range 36, E.

var 21^o E.

8,70 To Road corner South, East,

34,00 To Road corner N., E.

34,50 Center field at S. E. corner

37,00 Lease field

40,00 Set 1/4 Sec Post. on level,

at North East corner of

Darret's House, drove channel

stake, dug pits & raised

ground as per instructions,

48,80 South Branch of Walla Walla,

52,35 North Branch do, do,

62,00 Foot of Hill

80,00 Set Post Corner for Secs 15, 16, ⁺⁷⁰

21 & 22, on Hill side facing

the West, drove channel

stake, dug pits & raised

ground as per instructions.

Township No 5 N, R 36, E, Hill, M.

Some timber along River
Alder, Birch, Balsam, and
Maple. Undergrowth,
Soil in Bottom 1st Rate,

East on Raudon between sec 15 &

22, Town 5 N, R 36, East

40,00 set temporary 1/4 Sec Post
80,00 ~~Set~~ set north and south line
30 Sunk, South of Post, from
which I run S. 89° 47' W. on
true line,

40,00 set 1/4 Sec Post drove chained
stake, Duffiti & raised mound
as per instructions

52,50 Road corner at,

80,00 to Post corner

Land Broken grassy,
Soil 2nd Rate,

66 416

Township 5 N, R. 36, East Hill, M.

x

North between Secs 15 & 16,
Town 5 N, R. 36, East,
Nas 21° E.

4000 Set 1/4 Sec Post on side - 40
Hill facing the West.

52,50 To Trail house N. W.

8000 Set Post corner Secs 9, 10, - 20
15 & 16, on South side of

Round Butte Butte, W. W. W. W.
Chained Stake, Dry Pit
raised marked as per
Instructions. Sand broken
grass, soil 2' Rate,

May 17th, 1865,
East on Random between Secs
10 & 15, Town 5 N, R. 36, E.

4000 Set Temporary Post 1/4 Sec Post

79, 18 Intersect north & south line
10 Sinks North of Post, from
which I run N. 89° 51' W.
on true line

3984 Set 1/4 Sec Post Drive corner
Stake, Dug Pit - & raised
mound as Per Instructions.

7050 Road corner north,
79.18. Post corner. Sand Rolling
grass good, Soil 2, Rate,

Conto between Secs 9 & 10,
Town 5. N, Range 36, E.
var 21. E.

4000 Set 1/4 Sec Post, Sand descending
to the east. Drive corner
stake, Dug Pit raised
mound, as Per Instructions

8000 Set Post corner for Secs 3, 4,
9 & 10, Drive corner stake
Dug Pit - & raised mound
as Per Instructions. Sand
Rolling, grass good, Soil
2 Rate,

Township No 5. N. Range 36, E. Mill, Mo.,

East on Random between Secs 34 & 40,
Town 5. N. Range 36, East.

4000 Set temporary 1/4 Sec Post,

79.88 Intersect ~~&~~ North & South line
28 Links South of Post, from
which I run S. 89° 48' ~~W.~~
on a true line.

34.94

34.50 To Road course North West,

39.94 Set 1/4 Sec Post on East - 20

Side Hill of Dry Prairie

Settin' House South about
40 Chains,

79.88 To Post Corner

Land Rolling, Soil 2^d Rate,
grasses good.

North on Random between Secs

32 & 40 Town 5. N. R. 36, East,

var. 21° E.

4000 Set temporary 1/4 Sec Post,

81.00 Intersect East & West Town line

Township No 5 N. Range 31 E. Hill, Mo.
50 Sink West of Post from
which I run S. 77' W. on a
true line.

40.50 Set 1/4 Sec Post Drove Chained
Stake. Dwy Pitt raised
ground as Per Instructions

81.00 To Post corner.

Land Rolling. Gran good
Soil 2^d Rate.

+

North between Secs 32 + 33.

Town 5, North, R. 36, East.

Var 2^d East.

40.00 Set 1/4 Sec Post on side Hill
facing South. Drove Chained
Stake. Dwy Pitt raised
ground as Per Instructions.

80.00 Set Post corner for Secs 28, 29,
32 + 33. Drove Chained Stake
Dwy Pitt raised ground as
Per Instructions Land
Better Gran good Soil 2^d Rate

70 420

Township No 5, N. R. 36, E. Hill, Minn.

East on Random between Sec 28 &
33, Town 5, N. R. 36, E.

4000 Set Temporary $\frac{1}{4}$ Sec Post.
8009 Intersect north & south line
35 Sinks north of Post from
which I run N. 89° 45' W.
on true line.

4004 Set $\frac{1}{4}$ Sec Post on Hill side
facing the West. Wore
chained stake, Dye $\frac{1}{2}$ and
raised mound as per
Instruction.

8009 To Post corner. Sand
Broken. Good grass.
Soil 2^d Rate.

North between Sec 28 & 29,
Town 5, N. R. 36, East,
Var 21° East.

4000 Set $\frac{1}{4}$ Sec Post on Hill
side sloping to North East.

Township No 5. N. R. 36. East Hill. Mer.
Drove chared stake dug
Pit & raised mound as
Per Instructions

80.00 Set Post Corner for Recs 20, 21,
28 & 29 Drove chared stake
dug pit & raised mound as
Per Instructions. Sand
Rolling grass good soil
2^d Rate.

East on Raudon between secs 21 & 28
Town 5. N. Range 36. East.

40.00 Set temporary 1/4 sec Post.
79.69 Intersect north & south line
32 Sinks south of Post, from
which drawn S. 89. 46. W. on a
true line

39.84 Set 1/4 sec Post on Hill
sloping to the north, drove
chared stake, dug pit & raised
mound as Per Instructions

79.19 To Post Corner, Same Broken

72 422

Township No 5, N. R 36, E. Hill, Mo.
Grass Good, Soil 2^d Rate,

x

North between Secs 20 + 21,
Town 5, N. Range 36, East,
Meridian N. East,

40.00 Set 1/4 Sec Post Wrote
Chained Stake, Dug Pit
raised mound as per
Instructions.

42.00 To Edge of Bluff — 80 ft
58.70 To Wall Halla River 109 Sinks
Wide, Lower North, West,

80.00 Set Post Corner for Secs + 175 ft.
16, 17, 20 + 21. Wrote Chained
Stake, Dug Pit raised
mound as per Instructions
Sand in Creek bottom, timbered
with Balm, Birch, and
Alder, Soil 1st Rate,

73
423

Township No 5, North, R 31, E. Hill, Minn.

East on Random between Secs
16 & 21. Town 5, N, R 31, East.

4000 set temporary 1/4 Sec Post
79.71 Intersect north & south line
42 Sinks South of Post, from
which I run, S. 89° 42' N,
on a true line.

39.88, Set 1/4 Sec Post Sand facing
to the East. Drove Chared
stake. Dug pit & raised
ground as per Instructions

79.71 To Post Corner, Sand
Broken. Grass good. Soil
2^d Rate.

May 18th, 1865,
North between Secs 16 & 17,
Town 5, N, R, 31, East,
Twp 21° East.

4000 set 1/4 Sec Post ~~was~~ on
Sand according to S. N.
8000 set Post Corner for Secs 9, 10,

74 424

Township No. 5, N., R. 36, East Hill, Mo.
16077. Drove Chained Stake,
Dry Hills & raised ground
as Per Instruction.

Sand Broken grass
good, Soil 2^d Rate.

East on Reuben between Dec
9th, Town 5, N., R. 36, E.

4000 Set Temporary 1/4 Sec Post,

79,83 Intused with South line

24. Sink, north of Post,

from which I run, N. 89° 50' W.,

on true line

39,91 Set 1/4 Sec Post, on Hill side

slapping to the west. Drove

chained stake, Dry Hills

raised ground, as Per

Instruction.

79,83 To Post Corner, Sand

Rolling, grass good, Soil

2^d Rate.

75
425

Township No 5, N, R 36, East, Hill, Mo.

North between Secs 879,
Town 5, N, R, 36, East,
Twp 21st East.

4000 Set 1/4 Sec Post East - 15
Side of Prairie corner N, W,
Drove Charred stake, Dwyll's
raised mound as Per
Instructions.

8000 Set Post Corner for Secs 485
879, on land sloping to the
north, Drove Charred stake
Dwyll's raised mound as
Per Instructions.

Land Rolling grass good
soil 2nd Rate.

East on Random between Secs
409, Town 5, N, R 36, East,
4000 Set temporary 1/4 Sec Post,
79, 72 Intersect north & south line
32 Sinks north of Post.

76 436

Township 5. N., R. 36, E. Mill. Mer,
from which I run N. 89° 44' W.
on true line,

39,86 Set 1/4 Sect Post, Drove Chamo
Stake, Dug Pit & raised
Mound as per Instructions

49,72 To Post Corner, Land
Rolling, Grass good
Soil 2^d Rate,

North on Random between Secs.
405. Town 5. N., R. 36, East,
Var 21° East,

40,00 Set Temporary ^{1/4 Sect} Post,

80,00 Intersect East West Town Line
28 links West of Post, from
which I run S. 12' W. on
true line

40,00 Set 1/4 Sect Post on level,
Drove Chamo Stake, Dug
Pit & raised Mound as
per Instructions,

80,00 To Post Corner, Land

77
429

Township No 5, N. R. 31, East, Mill, Minn.
Gently undulating good
grass. Soil 2^d Rate.

North between Secs. 31 & 32,
Town 5, N. R. 36, East,
Van N^o East.

4000 Set 1/4 Sec Post Grove Chared
Post, Dry Pits & raised mounds
as per instructions

55,25 Crossed Trail, corner S. N.

8000 Set Post Corner for Secs. 29, 30,
31 & 32 from Chared. State

Dry Pits & raised mounds
as per instructions

Land Rolling, grass good,
soil 2^d Rate.

East on Raudon between Secs

29 & 32, Town 5, N. R. 31, East,

4000 Set Temporary 1/4 Sec Posts,

8000 Intersect north & south line

28 Sinks north of Post, from

78 428

Township No. 5, N., R. 36, East, T11, M.
which I run N. 89° 48' W.
on true line

40.00 Set 1/4 Sec Post, drove
Chum stake, Dwy Pit
raised ground as per Instructions
8000 To Post corner, Land
Rolling, Soil 2 Rate,
Grass good,

Nest on Ransom between Secs
30 & 31, Town 5, N., R. 36, E.

40.00 Set Temporary 1/4 Sec Post,
79.90 Intersect north & south Town line,
79 Sink, north of Post, from,
which I run N. 89° 48' E.
on true line

39.90 Set 1/4 Sec Post drove Chum
stake, Dwy Pit raised
ground as per Instructions
79.90 To Post corner, Land
Broken, Grass good,
Soil 2 Rate,

Township T5, N, R 36, East Hill, M.

79
429

North between Decs 29 + 30,
Towns. N, R 36. East,
Var 21° East.

4000 Set 1/4 Sec Post Drove Chained
Stake, dug pits & raised
mound. as per Instructions

8000 Set Post Corner for Decs 19, 20,
29 + 30. Drove Chained Stake
dug pits & raised mound,
as per Instructions.

Sand Rolling, Grass, good
Soil 2^d Rate.

East on Random between Decs
20 + 29 Towns. N, R, 36. East.

4000 Set temporary Post.

79.88 Intersect north & south line
at Post, from which N,
on true line

39,94 Set 1/4 Sec Post Drove Chained
Stake dug pits & raised mound

80 430

Township No. 5, N., R. 36, East, Will. Mer,
as Per Instructions,

7988 To Post corner, Sand
Rolling grass good,
Soil 2^d Rate,

West on Random between Secs 19 & 30

Town 5, N., Range 36, East,

4000 Set temporary 1/4 Sec Post,
8000 Intersect North South Town line
18 Links south of Post, from
which I run S. 89° 52' E.
on true line,

4000 Set 1/4 Sec Post Iron Chained
Stake, Wry Pit & raised
mound, as Per Instructions,

8000 To Post corner, Sand Rolling
grass good, Soil 2^d Rate,

May 19th, 1865,

North between Secs 19 & 20
Town 5, N., R. 36, East,
Range 36, East,

4000 Set 1/4 Sec Post Iron Chained

Township No 5 North R. 36, E. Hill, Minn,
State, dug pits & raised
mound as per instructions

1600 To Bank of Step Hill. — 30

Hill to top to descend,

Thence down west, 550,

from which point a small
tree on north & south line

bear north 29° East, making
distance from offset to tree,

9.93. Thence south to River

4.67. Hence 7x°

7126 North Bank of Kallakalla

River about 200 Supt. wide

course North West. — 50p.

8000 Set Post corner for Decs 17, 18.

1920. Deposited marked stone

dug pits & raised mound as

per instructions. Sand on

River Bottom 1st Rate, Timber

Birch, Balm, & Alder.

Township 5 N, R 36, East Hill, W.

East on Random between Secs 17 & 20

Town 5, N, Range 36, East.

4000 Set temporary $\frac{1}{4}$ Sec Post.

79.78 Intersect north & south line
at Post, from which I run
N. on true line

31 30 Leave field course, north west,
79.89 Set $\frac{1}{4}$ Sec Post & drove Chained
Stake. Dug Pit & raised
ground as per instructions.

79.78 To Post Corner. Land
Broken. Grass good soil 2. Plat.

X

West on Random between Secs 18 & 19,

Town 5, N, R 36, East.

4000 Set temporary $\frac{1}{4}$ Sec Post,

79.63 Intersect north & south Town line
20 Sinks north of Post, from
which I run N. $89^{\circ} 57' E$.

4.00 To Chase Creek 30 Sinks, wide ⁴⁰
Course north

79.63 Set $\frac{1}{4}$ Sec Post, No stake

Township No. 5, North, R 36, E, Hill, Mex,
 Hill side, Facing North East,
 Drove Charred Stake, Dug Pits
 & raised mound as per instructions
 79, 13 To Post corner, Sand Rolling
 Level on River Bottom, 1st Rate
 Soil. Good timber for Rails
 and Fire Wood.

North between Secs 18 & 17,
 Towns. N. R. 36, East.
 Variation N. East.

- 200 Square field corner of fence East.
- 300 Road, course West.
- 500 Foot of Hill.
- 25.00 Summit of do.
- 4000 Set of 4 Sec Post on level Drove
 Charred Stake, Dug Pits
 & raised mound as per
 instructions.
- 8000 Set Post Corner, for sec
 7, 8, 17 & 18, Drove Charred Stake,
 dug Pits & raised mound as

84 434

Township No 5, N. R 36, E. 11th, M.

Per Instructions

Land from Summit gently

Rolling, grass good, Soil

2^d Rate

East on Random between Secs

847, Town 5, N. R 36, East

4000 Set Temporary 1/4 Sec Post.

7980 Intused North & South line

15 Links South of Post, from

which I run S. 89° 54' W.

on true line.

~~4000~~

1400 Road course north,

3985 Set 1/4 Sec Post & drove chain

Stake dug pits & raised

marked as Per Instructions

7980 To Post corner, Land

Rolling, grass good,

Soil 2^d Rate.

Township No 5, N, R 36, E, Mill, W.

West on Random between Dec 7 & 18,
Town 5, N, R, 36, East

4000 Set Temporary 1/4 Sec Post
79,18 Intersect north & south town line
72 Sinks north of Post, from
which I run N. 89° 19' E. on
true line

39,84 Set 1/4 Sec Post drove chanced
stake, dug pit & raised mound
as per instructions

79,18 To Post corner,

68,00 Enter River Bottom,

72,50 Road course North West.

79,18 To Post corner, Saw a River
flat 1st Rate, Timber,
Palm, Birch & Alder.

May 20th, 1865,
North between Dec 7 & 18,
Town 5, N, R 36, East,
var 20° East.

4000 Set 1/4 Sec Post, on level, drove

Township no 5, N. R. 36, East Hill, Mo,
Charred Stake, Red Pitt,
raised Mound as per
Instructions,

8000 Set Post corner for Secs 5, 6,
7 & 8, on land gently ascending
Drove Charred Stake, Red
Pitt raised Mound, as per
Instructions, This line passes
over land ascending to the
north, good grass, Soil
L. Rate,

East on Random between Secs 5 & 8.

Town 5, N. Range 36 East

4000 Set temporary 1/4 Sec Post,

7992 Intusick North & South Town line 2 1/2 Sicks,
South of Post from which I. P. W.
S. 89° 49' N. on a true line,

3996 Set 1/4 Sec Post on land gently sloping
Drove Charred Stake, Red Pitt raised
Mound as per Instructions.

~~From which~~

87
437

Township No 5. N. R. 36, East Mill, Trus,
79.90 to Post corner. Sand Rolling,
grass good, Soil 2^d Rate.

West on Random between Secs 4 & 5
Town 5. N. R. 36, East.

40.00 Set temporary 1/4 Sec Post
79.60. Intersect north & South Town line,
46 Sinks, south of Post, from
which B run S. 89° 32' E. on
a true line.

39.60 Set 1/4 Sec Post, more changed
Stake dug it & raised ground
as per instructions

79.60 to Post corner. Sand Rolling
grass good, Soil 2^d Rate.

North on Random between Secs 5 & 6,
Town 5. N. R. 36, East
Var 21° East.

40.00 Set temporary 1/4 Sec Post.

80.50 Intersect East West Town line

41 Sinks, west of Post, from which

89

439

Township No 5, N, R, 36, East, Hill, Minn,
 Town S, 18, N, on true line

40.50 Set $\frac{1}{4}$ Sec Post Wagon corner
 Stake. dug pit & raised mound
 as per instructions

80.50 S^o Post corner

Sand Rolling grass good,
 Soil 2^o Rate.

The foregoing field notes
 and surveys were made by Deputy
 William S. Lewis assisted by
 Cyrus Dixon }
 J. C. Wallace } Chairmen,
 Robert Cook Assessor,

I, William S. Lewis, do
 hereby certify that the foregoing
 are the true and original field notes
 of the subdivisional lines of
 Township No 5, N, R, 36 E,
 as will appear from
 Affidavits duly made

and attached to the field notes
for Township N. 5 N., R. 3 E.,
Exterior Lines.

William S. Lewis.

Deputy Surveyor.

1874 13

440 1/2

+ 440 A

Surveyor General's Office
Eugene City, Aug 23^d 1865

The foregoing field notes of the surveys of
subdivisional lines in Township 5 North
Range 36 East Willamette Meridian, Oregon,
executed by Odell & Lewis, Deputy Surveyors, under
their contract No. 110, dated February 7, 1865,
having been critically examined, the necessary
explanations and corrections made, the said
field notes and the surveys they describe
are hereby approved.

E. L. Applegate
Surveyor General of Oregon.