

54 ~~394~~

494

Index

To Exterior lines of Township N^o 5 N, R^o 34 E.

See Page 67

71	72	73	73	74	75	
6	5	4	3	2	1	70
						12 69
						13 69
						24 68
						25 67
						36 67

Thursday March 23rd 1865

Commenced the survey of the Exterior
Lines of Township No 5 North of Base
Line in Range 35 East of Willamette
Meridian, At the South East Cor,
North between Ranges 35 & 36 on East
boundary of section 36, in
Township 5 North

Variation 20° E

2800 A Settlers house bears East about 2400

4000 Set post corner for 1/4 section on
side hill facing the East,
dug pits, drove charred
stake, and raised earth mound
as per instructions,

7300 A Wagon Road Course N. W.

8000 Set post corner for sec 25 & 36. 30 & 31,
on hill side facing the East,
drove charred stake, dug pits
and raised mound as per
instructions. This line passes
along hill side sloping to the East
Good Grass Soil good Good Water

~~346~~ 496

Township 5 North Range 35 East of Will. Mer,
North between Ranges 35 & 36 East
on East boundary of section 25
T 5 North,

Azimuth 20° East.

40.00 Set post corner for 1/4 section

Land gently sloping to the
East, Drove charred Stake, dug
pits, and raised mound as
per instructions.

80.00 Set post corner for sections 24 & 25.

19 & 30. Land slopes to the East 30°
Land ascending to the
North East good grass
Soil good 2nd Rate,

North between Ranges 35 & 36
Townships 5 N. on East boundary
of section 24.

Azimuth 21° East

40.00 Set post corner for 1/4 section
on hill side facing the East,
Drove Charred Stake dug

Township 5 North Range 35 East of Will. Mer,
 pits, and raised Mound as per
 instructions.

80.00 Set post corner for sections 13 & 24.
 18 & 19, on steep hill side facing the
 East. Drove charred stake, dug pits,
 and raised Mound as per
 instructions.

This line passes along
 hill side facing the East,
 bordering on Small Creek,
 Good grass, Soil good 2nd Rate

North between Ranges 35 & 36 Townships
 5 North on East boundary of section
 13.

Bar 21° E,

40.00 Set post corner for 14 Section
 Land gently, sloping to the N, E,
 49.75 bank of the Walla Walla River to
 150 yds wide course N, W,

52.25 Enter Timber

80.00 Set post corner for sections

Township No. 5 North Range 35 East of W.D. Mo.,
 12413. 7418 from which

- A Balun 10 in, dia, bears N, 34° E, 81 lbs
- do, do, 6 do, do, do, N, 62° W, 97 do,
- do, do, 6 do, do, do, S, 36° 15' W, 124 do,
- do, do, 7 do, do, do, S, 45° 30' E, 117 do,

This line for the first half passes
 down Eastern slope of hill good grass
 Soil 2^{ow} Rate, From river the
 line passes over low bottoma land
 Stony Timber Balun,

North, between Ranges 35 & 36 East
 Townships 5 North, on East boundary
 of section 12.

Variation 21° East,

23.00 Leave timber and commence to
 ascend hill,

40.00 Set post corner for 1/4 Section
 on ridge, Drive Churred
 Stake, dug pit, and raised
 Mound as per instruction

+
100

80.00 Set post corner for sections

50

Township No 5 North Range 35 East of Will, Mex.
1912, 647. Land gently slopes to the N.E.

Drove Charred Stake, dug pits, and raised
Mound as per instructions.

This line passes up rocky hill on the South
half, the North half over gently rolling
ground good grass soil Good
2nd rate,

North, between ~~between~~ Ranges 35 & 36
Township No 5 North, on east boundary
of section 1.

Variation 21° East

40.00 Set post corner for $\frac{1}{4}$ section
on level Drove charred, stake, dug
pits, and raised Mound as per
instructions.

80.00 Set post corner for Township No 5 N. 6
North, in Ranges 35 & 36 East and
Sections 1, 6, 31, & 36.

50

Drove charred stake, dug pits,
and raised Mound as per instructions
This line passes down gently.

60 ~~400~~ 500

Township No. 5 North Range 35 East Will. Mex.
descending grounds good grass
Soil good 2nd Rate.

West on North boundary of sec
1 in Random Township 5 N
Range 35 East

Variation 21 East,

March 25th 1865,

35.50 Wagon Road Course N, E,

37.50 Enter Creek bottom 90

40.00 Set post corner for 1/4 Section
Drove Charred Stake, and
Raised Stone Mound as per
instructions

43.25 Creek 75 lbs wide course North

51.60 do, 50 do, do, do, do,

65.50 Road course North,

80.00 Set temporary post corner
for sec. 1 & 2. 35 & 36

Level, Soil 2nd Rate
on East half, on West rocky.

Surveyor General's Office
Eugene City Aug 23 1865

The foregoing field notes of the Survey of the ~~the~~
~~Standard Quarter North, through Ranges 31,~~
~~32, 33, 34, 35, 36 & 37 East Will. Mer. Oregon,~~
~~and of the~~ exterior lines of Tps. 5 North Ranges
33, 34, 35 East Willamette Meridian, Oregon,
executed by Odell & Lewis, Deputies, under con-
tract No. 110, bearing date February 7th 1865,
having been critically examined, the necessary ex-
planations and corrections made, the said field
notes and the surveys they describe, are hereby approved.

E. L. Applegate
Surveyor General of Oregon.