

Index
 To the Field notes to the
 Exterior lines of Township No. 5
 North. Range 36 East Will. Mer.

51	52	53	54	55	56	
6	5	4	3	2	1	49

12 48

13 48

24 47

25 46

36 46

copy this

May 14th 1865

Commenced the survey of Exterior Lines
 Township 5 North Range 31 East
 North on East boundary of Sec 30
 Town 5 North Range 30 East
 Variation 21° East

31

40.00 Set 1/4 Sec Post on Side Hill
 Sloping to the East Drove Charred
 Stake dug Pit & raised mound
 as per Instructions.

61.11 Walla Walla River (South Fork)
 Course West.

80.00 ~~Set~~ Set Post Corner for Secs 25,
 31, 31 & 30, Drove Charred Stake
 dug Pit & raised mound as
 per Instructions. Land very
 broken. Grass poor Soil 2°
Rate,

North on East Boundary of Sec
 25, Township 5 North Range 31, E.

40.00 Set 1/4 Sec ^{Variation 21° East} Post Drove Charred
 Stake, dug Pit & raised mound

Township 5 North Range 36, East
as per instructions + 200ft

8000 Sec Post Corner for Secs 24, 25
19 + 30, on Steep Hill Side
facing the north. Above
Charred Stake Nug. Pil. &
raised Mound as per instructions
This line passes over high ridge
Divide between the North & South
Forks of the Walla Walla River
grass good soil 2^o Rate.

North on East Boundary of Sec 24,
Town 5 North Range 36, East,
Variation 21^o East,

- 2340 Walla Walla River corner ^{200ft} West
- 2900 Road Corner West
- 4000 Sec 14 Sec Post on Ridge
facing South West + 100ft.
Drove Charred Stake, Nug. Pil.
& raised Mound as per instructions
- 5400 Spring Branch Corner South
West - 90ft

Township 5 North Range 36, East
 S.W. Sec Post Corner for Secs 13, 24¹⁰⁰
 18 & 19, Drove Charred Stake
 Dug Pit, & raised Mound
 as Per Instructions
 Sand Broken grass good
Soil 2^o Rate,

North on East Boundary of Sec
 13, Town 5 North Range 36, East,
 Variation 21^o East,

40, 111 Set 4 Sec Post on Hill side
 facing East, 10 Chains from
 Summit Drove Charred
 Stake. Dug Pit, & raised ^{mound} as
 Per Instructions.

S.W. Sec Post Corner for Secs 12, 13,
 17 & 18, Drove Charred Stake
 Dug Pit, & raised Mound as
 Per Instructions, Sand Broken
 grass good, Soil 2^o rate.

North on East Boundary of Sec 12,

Township 5 North Range 36, East,
Township 5 North Range 31, East
Variation 21° East.

40,000 Set 1/4 Sec Post Drove Charred
Stake, Dug Pit - raised
mound as per instructions.

80,000 Set Post Corner for Secs 1, 12,
6 & 7, on Hill Side facing
East, Drove Charred Post,
Dug Pit - raised mound
as per instructions.

North on East boundary
of section 1, T5N, R36E,
Var 21° E.

28,000 Road course N, W,

40,000 Set 1/4 Section post,
Drove Charred Stake
Dug pits and
raised mound as per
instructions.

80,000 Set post corner for
Townships 5 & 6 North

50 574

674

Township 5 N Range 36 East
Ranges 36 & 37 East
Drove chert
Stake dug pits and
raised mound as
per instructions.
Lavel Rolling
Grass good
Soil good 2 $\frac{ac}{11}$
Route

West on Buncom
on North boundary
of Township 5 N
Range 36 East,
Bar 21^o 9,

April 4th 1865
On North town
at 40 and 80 chs
set temporary
 $\frac{1}{2}$ mile and still
post, 478.44

624

Surveyor General's Office
Eugene City, Aug. 23^d 1865

The foregoing field notes of the Survey of the Exterior
lines of ~~Tps. 4 N. R. 31, 32, 33, & 4 East; and of~~
Tps 5 N. Ranges 31, 32 and 36 East; and of
Tps 6 N. Ranges 34, 35 and 36 East, Will. Mer,
Oregon, Executed by Odell and Lewis under contract
No. 110 bearing date February 7th 1865, having
been critically examined, the necessary explanations
and corrections made, the said field notes and
the surveys they describe are hereby approved.

E. L. Applegate
Surveyor General.