

INDEX DIAGRAM

Township 5 South, Range 31 East,

6	5	4	3	2	1
	<u>10</u>				
7	8	9	10	11	12
<u>9</u>		<u>4</u> <u>4</u>			
18	17	16	15	14	13
	<u>9</u>	<u>3</u> <u>3</u>			
19	<u>8</u> 20	<u>2</u> 21	22	23	24
<u>8</u>	<u>7</u> <u>7</u>	<u>2</u>			
30	<u>6</u> 29	28	27	26	25
<u>6</u>	<u>5</u>				
31	<u>5</u> 32	33	34	35	36

1

T. 5 S., R. 31 E., Willamette Meridian, Oregon

CHAINS

The following field notes describe the remonumentation of certain original corner points, township 5 south, range 31 east, Willamette Meridian, Oregon, as provided for in the General Special Instructions, Group Number 350, Oregon, dated May 3, 1957, "Investigation of Collateral or Physical Evidence of Corner Positions and Accessories Followed by Remonumentation of Corner Points, with New Accessories when Needed".

The remonumentation of original corner points was made at the request of the United States Forest Service, in conjunction with their Land Line Location Program.

The mean magnetic declination is 20° E.

South Boundary, T. 5 S., R. 31 E.,
(First Standard Parallel South)
Willamette Meridian, Oregon

(Remonumenting a corner established by George S. Pershin,
U. S. Deputy Surveyor, in 1880)

The standard cor. of secs. 31 and 32, on the S. bdy. of the Tp., monumented with the original basalt stone, 16 x 10 x 6 ins., firmly set 8 ins. in the ground, and in a mound of stone, 3 ft. base, 1 ft. high, mkd. with 2 notches on E. edge, from which the remains of the original bearing trees:

A pine, 26 ins. diam., bears N. 66° E., 125 lks. dist., with scribe marks T5S R31E S32 visible on open blaze.

A pine snag, 22 ins. diam., bears N. 50° W., 78 lks. dist., with scribe marks T5S R31E S31 SC BT visible on open blaze.

At the corner point

Set an iron post, 28 ins. long, 2½ ins. diam., 22 ins. in the ground, and in a mound of stone, 3 ft. base, to top, with brass cap mkd.

S C
T 5 S R 31 E
S 31 | S 32
1978

from which a new bearing tree

A ponderosa pine, 13 ins. diam., bears N. 50½° W., 48 lks. dist., mkd. T5S R31E S31 SC BT.

Deposit corner stone alongside iron post.

Subdivisions, T. 5 S., R. 31 E.,
Willamette Meridian, Oregon

(Remonumenting corners established by George S. Pershin,
U. S. Deputy Surveyor, in 1880)

CERTIFICATE OF SURVEY

(I) (~~WX~~), Craig L. Wanless, Cadastral Surveyor, , HEREBY CERTIFY upon honor that, in pursuance of special instructions bearing date of the 3rd day of May , 19 57, (I) (~~WX~~) have remonumented certain original corner points, township 5 south, range 31 east,

of the Willamette Meridian, in the State of Oregon , which are represented in the foregoing field notes as having been executed by (me), (~~WX~~) and under (my) (~~own~~) direction; and that said survey has been made in strict conformity with said special instructions, the Manual of Instructions for the Survey of the Public Lands of the United States, and in specific manner described in the foregoing field notes.

October 13, 1978
(Date)

Craig L. Wanless
(Cadastral Surveyor)

(Date)

(Cadastral Surveyor)

CERTIFICATE OF APPROVAL

BUREAU OF LAND MANAGEMENT
~~Washington, D.C.~~
Denver,, Colorado

The foregoing field notes of the remonumentation of certain original corner points, township 5 south, range 31 east, Willamette Meridian, Oregon,

executed by Craig L. Wanless, Cadastral Surveyor, having been critically examined and found correct, are hereby approved.

FEB 07 1980
(Date)

J. Voorhees
(Chief, Division of Cadastral Survey)
Chief, Cadastral Survey Examination and Approval Staff

CERTIFICATE OF TRANSCRIPT

I CERTIFY That the foregoing transcript of the field notes of the above-described surveys in , is a true copy of the original field notes.

(Date)

(Chief, Division of Cadastral Survey) GPO 849-626