

FIELD NOTES

Of the survey of the Subdivision
Lines of Township 5 South
Range 33 East, Willamette Meridian,
Oregon, as surveyed by George S.
Pershine, U. S. Deputy Surveyor,
under his Contract No. 430, dated
March 23rd, 1882

Survey commenced, May 29 1882

Survey completed, June 8th 1882

NAMES AND DUTIES OF ASSISTANTS.

George S. Pershine, Compassman.

James B. Ellis, Chainman.

Frank F. Ellis, Chainman.

, Chainman.

, Chainman.

Valentine Brown, Axeman.

, Axeman.

, Flagman.

297

PRELIMINARY OATHS OF ASSISTANTS:

We,

James B. Ellis and
Frank F. Ellis

do solemnly swear that we will faithfully execute the duties of Chain Carriers, that we will level the chain over even and uneven ground, and plumb the tally pins, either by sticking or dropping the same; that we will report the true distance to all notable objects, and the true length of all lines that we will assist in measuring, to the best of our skill and ability, and in accordance with the instructions given us in

the survey of the

Subdivision

lines of Township No 5 South

Range 33 East

Willamette Meridian, Oregon.

James B. ^{John} Ellis, Chainman.

Frank F. ^{Mark} Ellis, Chainman.
~~Mark~~

, Chainman.

, Chainman.

Subscribed and sworn to before me, this

fifteenth

day of May 1882

[SEAL.]

George S. Perskin

A U. S. Deputy Surveyor

we, J. Valentine Brown and

do solemnly swear
that we will well and truly perform the duties of Axemen in the establishment of corners and other duties, according to instructions given us, and to the best of our ^{own} _{skill} and ability, in the survey of the Subdivision lines of

Township 5 S. R. 33 East Willamette Meridian Oregon.

Valentine Brown, Axeman.

, Axeman.

Subscribed and sworn to before me, this

fourteenth

day of May 15 1882

[SEAL.]

George S. Perskin a
U. S. Deputy Surveyor

See note page 3

INDEX.

Referring the Lines to the Pages of the Field Notes.

T. 5 South R. 33 East Will. Mer.

6	120	5	88	4	66	3	44	2	22	I
118		116		86		64		42		20
7	114	8	84	9	62	10	40	11	18	12
112		110		82		60		38		16
18	108	17	86	16	58	15	36	14	14	13
106		104		78		56		34		12
19	102	20	76	21	54	22	32	23	16	24
100		98		74		52		30		8
30	96	29	72	28	50	27	28	26	6	25
94		92		70		48		26		4
31	90	32	68	33	44	34	24	35	2	36

Meanders of ----- Pages ----- to -----

Meanders of ----- Pages ----- to -----

Sold this corner of T. 5 S. and R. 33 E.
Willamette Meridian, Oregon.

Preliminary to commencing Survey I run
North on the East Boundary of Sec. 36
and at 79.92 The cor to Sec. 25 & 36
Then West on the South Boundary
of Sec. 36 and at 39.98 the $\frac{1}{4}$ sec. cor
and at 79.95 the sec. cor. to 35 & 36
My compass runs the same
lines and my chaining is prac-
tically the same as that of the
Standard and exterior

Survey commenced May 29-1882
With Bunts improved Solar
compass - Young of Philadelphia
maker - in good order and
adjustment.

I begin at the stone (about
6 inches out of ground) cor to Sec. 35 &
36. on South Boundary of Township
A Tamarack 16 in. di. lrs. N. $75^{\circ} E$. 211 lbs
dist marked T 5 S. R. 33 E. S. 36 B.T. S.C.
Pine 6 in. di. lrs. N. $38^{\circ} W$. 76 lbs dist
marked T 5 S. R. 33 E. S. 35. S.C. B.T.

Subdivisions of T. 5 South R. 33 East

Willamette Meridian, Oregon.

North between Sec. 35 and 36
Va.

Ascending

18.00 Top of irregular ridge co. 68° N. 200. ft. hi,

27.50 A ravine co. S. N. 150 descent

40.00 Top of ridge co. 68° N. Set Pine post
marked $\frac{1}{4}$ S. on west side
on level for $\frac{1}{4}$ sec. cor. from which

A Fir 24 in. diam. brs. S. 38° E marked $\frac{1}{4}$
B. T. 16 chs. dist

A Pine 22 in dia. brs. A. 72° N. 59. chs. dist
marked $\frac{1}{4}$ S. B. T.

80.00 Set a Basalt stone 14 x 10 x 8 in. in
ground for cor. to sec. 25, 26, 35 & 36.

Marked with one notch on S. and one on
E edges. south slope from which

A Pine 10. in. dia. brs. A. 84° E. 63 chs. dist

Marked T 5 S. R. 33 E. S. 25. B T

A Fir 8 in. dia. brs. S. 48° E. 68 chs dist

marked T 5 S. R. 33 E. S. 36. B T

A Pine 14 in. dia. brs. S. 82° N. 34 chs dist

Marked T 5 S. R. 33 E. S. 35. B T

Subdivision of T. 5 South R. 33 East

Willamette Meridian, Oregon.

North between Sec. 34 & 35

va. $19^{\circ} 15'$ East

The cor to this line is a post on North slope from which

A Tamarack 18 in. di. hrs. N. $28^{\circ} E$ 42 lbs dist

marked T 5 S. R. 33 E. S. 35 S. C. B.T

A Tamarack 10 in di. hrs. N. $46^{\circ} W.$ 51 lbs dist

marked T 5 S. R. 33 E. S. 34. S. C. B.T

18.00 A brook 6 lbs wide co west

descent about 50 ft

39.00 Spring branch co. S. W.

40.00 Set post 4 ft long 4 in diam
on level at spring branch
for $\frac{1}{4}$ sec. cor. Marked $\frac{1}{4}$ S
on west face from which

A Pine 7 in. diam. hrs. N. $66^{\circ} E$, 23 lbs dist

marked $\frac{1}{4}$ S. B.T.

A Pine 11 in. di. hrs. S. $72^{\circ} W.$ 30 lbs dist

marked $\frac{1}{4}$ S. B.T.

74.00 Top of hill 150 ft above brook

Subdivisions of T. 5 South R. 33 East
Willamette Meridian, Oregon.

North between Sec. 33 & 34
Rd. $19^{\circ}15'$ East

This cor. is a stone about 6 m
above ground from which a
A Pine 5 in. dia. lrs. N. $52^{\circ}E$ 35 lrs dist
Marked T 5 S. R. 33 E. S. 34 S. C. B.T
A Pine 10 in dia. lrs. N. $34^{\circ}W$. 11 lrs dist
Marked T 5 S. R. 33 E S. 33 S. C. B.T

Ascending

40.00 A point about 100 ft above sec. cor
Set post 4 ft long 4 in diam
2 ft in ground
on level for $\frac{1}{4}$ sec. cor. marked
 $\frac{1}{4}$ S. on West side

A Pine 5 ins. dia. lrs S. $12^{\circ}E$ 20 lrs dist
Marked $\frac{1}{4}$ S. B.T.

A Pine 44 ins dia lrs N. $68^{\circ}W$. 27 lrs dist
Marked $\frac{1}{4}$ S. B.T.

80.00 Set basalt stone 12 x 10 x 7 ins
8 ins in ground on level for
cor. to Sec. 27, 28, 33, & 34,
Marked with one notch

Subdivisions of T. 5 South R. 33 East-

Willamette Meridian, Oregon.

North between Sec. 32 & 33
Ra. $19^{\circ} 10' E$ ast -

This cor. is a post in mound of
Stone from which

A Pine 10 in. di. brs. N. $70^{\circ} E$ 32 lbs dist.

marked T 5 S. R. 33 E 5. 33 S. C. B.T

A Pine 12 in dia. brs. N. $17^{\circ} W.$ 70 lbs dist

marked T 5 S. R. 33 E 5 32. S. C. B.T'

rolling and slightly ascending

40.00 Set a basalt Stone 15 x 8 x 7 ins. 10 ins.
in ground on level for $\frac{1}{2}$ sec.

cor. marked $\frac{1}{4}$ on West face

A Pine 4 ins. di. brs. N. $76^{\circ} E$ 61 lbs dist.

Marked $\frac{1}{4}$ S. B.T.

A Pine 14 in. dia. brs. S. $78^{\circ} W.$ 61 lbs dist

Marked $\frac{1}{4}$ S. B.T.

80.00 Set a basalt Stone 15 x 9 x 7 ins.
10 ins. in ground on level for
cor to Sec. 28, 29, 32 and 33

Marked with 1 notch on S. and 4
notches on E. Edges

~~330~~
Subdivisions of T. 5 South R. 33 East -
Willamette Meridian, Oregon.

North between Sec. 31 & 32
Lat. $45^{\circ} 00' N$ Ealt-

This cor. is a basalt stone in
mound of stone projecting about 6 in.
A Pine 6 in. dia. hrs. N. $46^{\circ} E$. 19 lbs dist

Marked T 5 S. R. 33 E. S. 32 S. C. B.T.
A Pine 40 in. dia. hrs. N. $67^{\circ} W$. 39 lbs. dist
Marked T 5 S. R. 33 E. S. 31 S. C. B.T

14.50 Leave timber co. E & N. enter
small prairie

40.00 Set a basalt stone $14 \times 10 \times 6$ ins
10 ins. in ground on level
for $\frac{1}{4}$ sec. cor. Marked
 $\frac{1}{4}$ on W. face

A Pine 20 in. dia. hrs. N. $48^{\circ} E$ 28 lbs dist.
Marked $\frac{1}{4}$ S. B.T.

A Pine 42 ins dia hrs. N. $46^{\circ} W$. 92 lbs. dist
Marked $\frac{1}{4}$ S. B.T

40.50 Enter timber co. S. E & N. W

FINAL OATHS FOR SURVEYS.

A list of the names of the individuals employed by George S. Pershing, U. S. Deputy Surveyor, to assist in running, measuring and marking the lines and corners described in the foregoing field notes of the survey of the Subdivision lines of Township 5 south Range 33 East, Willamette Meridian, Oregon, showing the respective capacities in which they acted:

Geo. Pershing, Compassman.
James B. Ellis, Chainman.
James B. Ellis, Chainman.
Frank F. Ellis, Chainman.
Frank F. Ellis, Chainman.
Valentine Brown, Axeman.
Valentine Brown, Axeman.
Valentine Brown, Flagman.

FINAL OATHS OF ASSISTANTS.

We hereby certify that we assisted George S. Pershing, U. S. Deputy Surveyor, in surveying all those parts or portions of the Subdivision lines of Township 5 South Range 33 East, Willamette Meridian, Oregon,

as are represented in the foregoing field notes as having been surveyed by him and under his direction; and that said survey has been in all respects, to the best of our knowledge and belief, well and faithfully surveyed, and the corner monuments established, according to the instructions furnished by the U. S. Surveyor General of Oregon.

Geo. Pershing, Compassman.
James B. Ellis, Chainman.
Frank F. Ellis, Chainman.
Frank F. Ellis, Chainman.
Valentine Brown, Chainman.
Valentine Brown, Axeman.
Valentine Brown, Axeman.
Valentine Brown, Flagman.

Subscribed and sworn to before me, this Eighth day of

June

1882

George S. Pershing

A. U. S. Deputy Surveyor

[SEAL.]

FINAL OATH OF DEPUTY SURVEYOR.

I, George S. Pershing

United States Deputy Surveyor, do solemnly swear that in pursuance of instructions

received from James C. Tolman

U. S. Surveyor General for Oregon, bearing date of the 23rd day of

March, 1889, I have well, faithfully, and truly,
in my own proper person, and in strict conformity with the instructions furnished
by the U. S. Surveyor General for Oregon, the Surveying Manual, and the laws of

the United States, surveyed all those parts or portions of the Subdivis-

ion lines of Township 5 South Range 33 East

Willamette Meridian, in the State of Oregon, as are represented in the foregoing
Field Notes as having been surveyed by me and under my directions; and I do
further solemnly swear that all the corners of said survey have been established and
perpetuated in strict accordance with the Surveying Manual, printed instructions,
the special written instructions of the U. S. Surveyor General for Oregon, and in the
specific manner described in the field notes, and that the foregoing are the *true* field
notes of such survey, and should any fraud be detected I will suffer the penalty of
perjury under the provisions of an Act of Congress approved August 8, 1846.

George S. Pershing
U. S. Deputy Surveyor.

Subscribed and sworn to before me, this 30th

day of June, 1889.

James C. Tolman
Surveyor General O.

Office U. S. Surveyor General,

Portland, Oregon, August 12, 1882.

The following Field Notes of the Survey of
the Subdivisional lines of
Township 5 South, Range 33 East
Willamette Meridian Oregon

executed by George S. Pershing U.S. Dept.
Surveyor under his contract No 430
dated March 23, 1882, having been

critically examined, the necessary corrections and explanations made, the said field notes and the survey they describe, are hereby approved.

James C. Tolman
Surveyor General.