

FIELD NOTES

Of the survey of the Subdivision
Lines of Township 5 South
Range 33 East, Willamette Meridian,
Oregon, as surveyed by George S.
Pershine, U. S. Deputy Surveyor,
under his Contract No. 430, dated
March 23rd, 1882

Survey commenced, May 29 1882

Survey completed, June 8th 1882

NAMES AND DUTIES OF ASSISTANTS.

George S. Pershine, Compassman.

James B. Ellis, Chainman.

Frank F. Ellis, Chainman.

, Chainman.

, Chainman.

Valentine Brown, Axeman.

, Axeman.

, Flagman.

297

PRELIMINARY OATHS OF ASSISTANTS:

We,

James B. Ellis and
Frank F. Ellis

do solemnly swear that we will faithfully execute the duties of Chain Carriers, that we will level the chain over even and uneven ground, and plumb the tally pins, either by sticking or dropping the same; that we will report the true distance to all notable objects, and the true length of all lines that we will assist in measuring, to the best of our skill and ability, and in accordance with the instructions given us in

the survey of the

Subdivision

lines of Township No 5 South

Range 33 East

Willamette Meridian, Oregon.

James B. ^{John} Ellis, Chainman.

Frank F. ^{Mark} Ellis, Chainman.
~~Mark~~

, Chainman.

, Chainman.

Subscribed and sworn to before me, this

fifteenth

day of May 1882

[SEAL.]

George S. Perskin

A U. S. Deputy Surveyor

We, J. Valentine Brown and

do solemnly swear
that we will well and truly perform the duties of Axemen in the establishment of corners and other duties, according to instructions given us, and to the best of our ^{own} _{skill} and ability, in the survey of the Subdivision lines of

Township 5 S. R. 33 East Willamette Meridian Oregon.

Valentine Brown, Axeman.

, Axeman.

Subscribed and sworn to before me, this

fourteenth

day of May 15 1882

[SEAL.]

George S. Perskin a
U. S. Deputy Surveyor

See note page 3

INDEX.

Referring the Lines to the Pages of the Field Notes.

T. 5 South R. 33 East Will. Mer.

6	120	5	88	4	66	3	44	2	22	I
118		116		86		64		42		20
7	114	8	84	9	62	10	40	11	18	12
112		110		82		60		38		16
18	108	17	86	16	58	15	36	14	14	13
106		104		78		56		34		12
19	102	20	76	21	54	22	32	23	16	24
100		98		74		52		30		8
30	96	29	72	28	50	27	28	26	6	25
94		92		70		48		26		4
31	90	32	68	33	44	34	24	35	2	36

Meanders of ----- Pages ----- to -----

Meanders of ----- Pages ----- to -----

Subdivisions of T. 5 South R. 33 East

Willamette Meridian, Oregon.

West on a random line
between Sec. 30 & 31
pa. $20^{\circ} 30'$ East

38.00 begin steep descent
40.00 set temporary $\frac{1}{4}$ sec. cor.
68.50 creek 40 lks wide co. N. W.
descent 300. ft

79.42 Intersected west boundary
28 lks North of cor. to Sec. + 120
30 and 31 which is a stone
projecting about 6 inches

A Tamarack 8 in. di. lrs. N. 30° E. 10 lks dist

Marked T 5 S. R. 33. E. S. 30 BT

A Tamarack 6 in. di. lrs. S. 30° E. 19 lks dist

Marked T 5 S. R. 33 E S. 31. BT

A Tamarack 16 in. di. lrs. S. 32° W. 72 lks dist

Marked T 5 S. R. 32 E. S. 36 BT

A Tamarack 17 in. di. lrs. N. 25° W. 43 lks dist

Marked T 5 S. R. 32 E. S. 25 BT

from which cor I run
 $N. 89^{\circ} 48'$ East on a true
line between Sec 30 & 31

100

100

Subdivisions of T.5 South R.33 East

Willamette Meridian, Oregon.

West on a random line
between Sec. 19^o & 30
va. 20° 00' East

Slightly descending

4000 Set temporary 1/4 sec. cor.

79.20 Intersected West Boundary 72 ebs
north of cor. to Sec. 19. & 30.
descent about 100 ft - which
cor. is a stone set in a
mound of stone

A Pine 28 in di. hrs. S. 4° E. 146 ebs dist
Marked T 5 S. R. 33 E S. 30° BP

A Pine 26 ins. dia hrs. S. 12° W. 177 ebs dist
Marked T 5 S. R. 32 E. S. 25 BP.

from which I run.

N. 89° 29' East on a true line
between Sec. 19° and 30

va. 20° 15' East

39.20 Set a basalt stone 18 x 12 x 10 ins

101

401

Subdivisions of T. 5 South R. 33 East

Willamette Meridian, Oregon.

12 ins. in ground on slight N. W.
slope for $\frac{1}{4}$ sec. cor. marked
 $\frac{1}{4}$ on N. face
raised a mound of stone
along side in lieu of
pits

7920 The cor to see 19. 20. 29 & 30

Land: Surface undulating;
soil 2^m & $\frac{1}{2}$ rate good grass
no timber on line

8/8

906 406

Subdivisions of T. 5 South R. 33 East
Willamette Meridian, Oregon.

West on a random line
between Sec. 18 and 19

va. $18^{\circ} 15'$ East

4000 Set temporary $\frac{1}{4}$ Sec. cor.

78,84 Intersected West Boundary 78 lks
north of cor. to Sec 18 and 19 which
is a post and stone in
a mound of stone in
open prairie on slight
N. W. slope

from which I ran
 $N. 89^{\circ} 27'$ East on a true line
between Sec. 18 & 19

va $19^{\circ} 30'$ East -

3884 Set basalt stone 18 x 8 x 7 ins
12 ins in ground on level

Subdivisions of T. 5 South R. 33 East
Willamette Meridian, Oregon.

West on a random line
between Sec. 7 & 18

ra. $19^{\circ} 15'$ East

24.00 Enter strip of timber S & W.

28.00 Spring branch co. N. W.

40.00 Set temporary $\frac{1}{4}$ sec. cor.

78.76 Intersected west boundary
82 ebs north of cor. to Sec.

7 and 18. which is a stone
in mound of stone

A Pine 10 in. di. lbs. N. 70° E. 56 ebs dist
marked. T 5 S. R. 33 E. S. 7 BTP

A Pine 7 in di. lbs. S. 18° E. 60 ebs dist
marked. T 5 S. R. 33 E S. 18 B.T

from which cor. I run
 $N. 89^{\circ} 25'$ East on a true line
between Sec 7 and 18
ra. $18^{\circ} 45'$ East

Subdivisions of T. 5 South R. 33 East -
Willamette Meridian, Oregon.

West on a random line
between Sec. 6 and 7

Rd. $19^{\circ} 30'$ East

20.50 creek 60 lks wide co. N. W.
descent 180 ft -

32.00 On spur extending North

36.00 A ravine do North

40.00 Set temporary $\frac{1}{4}$ sec. cor.

44.00 Leave timber co. & go south

79.12 Intersected west Boundary

58 lks north of cor. to Sec

6 and 7 which cor. is a

post in mound of stone

all in good repair (ascent 100 ft)

From wh cor. I run
Rd. $89^{\circ} 35'$ East on true line

between Sec. 6 & 7

rd. $20^{\circ} 45'$ East -

39.12 Set basalt stone 20x8x6 ins. in
mound of stone on E slope
of bluff for $\frac{1}{4}$ sec. cor
marked $\frac{1}{4}$ on N face

FINAL OATHS FOR SURVEYS.

A list of the names of the individuals employed by George S. Pershing, U. S. Deputy Surveyor, to assist in running, measuring and marking the lines and corners described in the foregoing field notes of the survey of the Subdivision lines of Township 5 south Range 33 East, Willamette Meridian, Oregon, showing the respective capacities in which they acted:

Geo. Pershing, Compassman.
James B. Ellis, Chainman.
James B. Ellis, Chainman.
Frank F. Ellis, Chainman.
Frank F. Ellis, Chainman.
Valentine Brown, Axeman.
Valentine Brown, Axeman.
Valentine Brown, Flagman.

FINAL OATHS OF ASSISTANTS.

We hereby certify that we assisted George S. Pershing, U. S. Deputy Surveyor, in surveying all those parts or portions of the Subdivision lines of Township 5 South Range 33 East, Willamette Meridian, Oregon,

as are represented in the foregoing field notes as having been surveyed by him and under his direction; and that said survey has been in all respects, to the best of our knowledge and belief, well and faithfully surveyed, and the corner monuments established, according to the instructions furnished by the U. S. Surveyor General of Oregon.

Geo. Pershing, Compassman.
James B. Ellis, Chainman.
Frank F. Ellis, Chainman.
Frank F. Ellis, Chainman.
Valentine Brown, Chainman.
Valentine Brown, Axeman.
Valentine Brown, Axeman.
Valentine Brown, Flagman.

Subscribed and sworn to before me, this Eighth day of

June

1882

George S. Pershing

A. U. S. Deputy Surveyor

[SEAL.]

FINAL OATH OF DEPUTY SURVEYOR.

I, George S. Pershing

United States Deputy Surveyor, do solemnly swear that in pursuance of instructions

received from James C. Tolman

U. S. Surveyor General for Oregon, bearing date of the 23rd day of

March, 1889, I have well, faithfully, and truly,
in my own proper person, and in strict conformity with the instructions furnished
by the U. S. Surveyor General for Oregon, the Surveying Manual, and the laws of

the United States, surveyed all those parts or portions of the Subdivis-

ion lines of Township 5 South Range 33 East

Willamette Meridian, in the State of Oregon, as are represented in the foregoing
Field Notes as having been surveyed by me and under my directions; and I do
further solemnly swear that all the corners of said survey have been established and
perpetuated in strict accordance with the Surveying Manual, printed instructions,
the special written instructions of the U. S. Surveyor General for Oregon, and in the
specific manner described in the field notes, and that the foregoing are the *true* field
notes of such survey, and should any fraud be detected I will suffer the penalty of
perjury under the provisions of an Act of Congress approved August 8, 1846.

George S. Pershing
U. S. Deputy Surveyor.

Subscribed and sworn to before me, this 30th

day of June, 1889.

James C. Tolman
Surveyor General O.

Office U. S. Surveyor General,

Portland, Oregon, August 12, 1882.

The following Field Notes of the Survey of
the Subdivisional lines of
Township 5 South, Range 33 East
Willamette Meridian Oregon

executed by George S. Pershin U.S. Dept.
Surveyor under his contract No 430
dated March 23, 1882, having been

critically examined, the necessary corrections and explanations made, the said field notes and the survey they describe, are hereby approved.

James C. Tolman
Surveyor General.