

Field Notes of the Subdivision  
Lines in Township No 5 N R 30  
E of the Willamette Meridian in  
the State of Oregon, Surveyed by  
Leopoldus S. Payne deputy Surveyor  
under his contract No 1000 dated  
August 1<sup>st</sup> 1861

Box 20-

Commenced September 18<sup>th</sup> 1861  
Completed September 25<sup>th</sup> 1861

page 5  
" 7  
" 13  
" 18  
" 20  
" 22  
" 29  
" 30  
" 31  
" 35

Payne  
No. 1000

220

220

# Index

Subdivision Lines in Township  
No 5. N R 30 E

<i>Columbia River</i>									
6	5	5	4	4	3	10	2	7	1
<del>34</del>	35	25	18	12	7				
7	33	8	24	9	10	12	11	6	12
32	32	24	17	11	6				
18	31	17	23	16	17	15	11	14	5
31	30	23	16	10	4				
19	29	20	22	21	16	22	10	23	3
29	28	21	15	9	3				
30	28	29	31	28	15	27	9	26	2
27	27	20	14	8	2				
31	26	32	10	33	14	34	3	35	36

Township 5 N R 30 E T 11 S

Chains

East on random between Secs 1, 12

40.00 Set Iron  $\frac{1}{4}$  sec corner.

78.50 Intersect Iron line 50 links

North of post corner to Secs 1, 12.

$N 89^{\circ} 39' 11''$  on true line between Secs 1, 12

39.25 Set Charred Stake with mound  
pinch and pits as per notes for  
 $\frac{1}{4}$  sec corner.

78.50 Corner to Secs 1, 2, 11, 12.

Soil 2<sup>d</sup> rate

Closing corner in sight - run

North  $1^{\circ} 21' 11''$  on true line between  
Secs 1, 2

25.00 Begin to descend Hill.

40.00 Set Charred Stake with mound  
pinch and pits as per notes  
for  $\frac{1}{4}$  sec corner.

79.50 Intersect Iron line at post  
corner to Secs 1, 2, 3 and 35.

36 T 6 N R 30 E -

Soil somewhat sandy - 2<sup>d</sup> rate

233  
233

Township 5 N R 30 E M 11

Chains

N 89° 30' W on true line between Secs 2, 11  
10.00 Begin to descend hill towards  
the river.

40.00 Set charred stake with  
mound trench and pits  
as per notes for 1/4 sec corner.

64.50 Indian trail N 40° W

80.00 Corner to Secs 2, 3, 10, 11

Soil somewhat sandy. 3<sup>d</sup> rate

Closing corner being in sight use

North 1° 21' W on true line between  
Secs 2, 3

40.00 Set charred stake with  
mound trench and pits  
as per notes, for 1/4 sec corner.

57.00 Indian trail N 20° W

62.00 Descend rocky bluff.

(Variation at this point  
23° 30' E)

79.50 Intersect town line at post  
corner to Secs 2, 3.

Land for -

Township 5 N R 30 E T11

Chains

80.12 Corner to Secs 2, 3, 10, 11

At 50' Won true line between Secs 3, 4

10.50 Begin to descend steep hill.

37.50 Indian trail, E & W.

40.00 Set Charred Stake with ground  
bench and pits as per notes  
for 1/4 Sec Corner.

47.70 Ascend perpendicular Bluff  
Rocks about 10 feet high.

65.10 Descend perpendicular rocky  
Bluffs about 50 feet high  
bar at this point  $29^{\circ}$  E.

74.00 Descend steep rocky Bluff  
about 30 feet high.

76.60 Descend another Bluff about  
25 feet high.

79.40 Descend rocky Bluff about  
50 feet high.

79.60 Enter set-Town line at  
first Corner to Secs 3, 4

## List of Names

A list of the names of the individuals employed to assist in running measuring or marking the subdivision lines and corners described in the foregoing field notes of Township No 5 North of Range No 30 East of the Willamette Meridian showing the respective capacities in which they acted.

John Brattain, Channerman  
William B. Penger, Channerman  
John L. Luckey, Axeman

I hereby certify that the  
assisted by George S. Payne

560

260

deputy surveyor. in surveying  
the subdivision lines in  
Township No 5 North Range  
30 East of the Willamette  
Meridian and that said  
Township has been in all  
respects to the best of our  
knowledge and belief well  
and faithfully surveyed  
and the boundary monuments  
planted according to the  
instructions furnished by  
the Surveyor General.

John Brattain, Chairman  
W. B. Rogers - Chairman  
John L. Luckey, Assessor.

Subscribed & Sworn by the above named  
persons before me, a Justice of the Peace in  
& for the County of Lane, State of Oregon  
this 1<sup>st</sup> day of November A.D. 1861

R. St. Parsons  
Justice of Peace

I, Golshus S. Payne deputy Surveyor  
do solemnly swear that in pursuance  
of a contract with B. J. Pengra Surveyor  
of the public lands of the United States  
in the State of Oregon bearing date the  
first day of August 1861, and in strict  
conformity to the laws of the United States  
and the instructions furnished by the  
said Surveyor General I have faithfully  
surveyed the subdivision lines in  
Township No 5 North of the base line  
of Range No 30 East of the Willamette  
Meridian in the State of Oregon,  
and do further solemnly swear  
that the foregoing are the true and  
original field notes of such  
survey.

Golshus S. Payne,

Subscribed and sworn  
before me this 4<sup>th</sup> day  
of November A.D. 1861

B. J. Pengra, Sur. General of Oregon



262

Paynes - Notes ...

262

Surveyors Office at  
Eugene City Oreg Dec 5<sup>th</sup> 1861

The foregoing field notes of the  
Survey of the Subdivisions  
Township number  
5 North of the base line and  
Range 30 East of the Meridian  
in the State of Oregon executed  
by Delphus S Payne under  
his Contract Number 100 dated  
August 1<sup>st</sup> 1861 having been  
critically examined the  
necessary corrections and  
explanations made the  
said field notes and the  
surveys they describe are  
herby approved.

H. B. Payne  
Surveyor General