

Field Notes of the Resurvey  
of Exterior boundary lines of Townships  
4 North of Range 27 East Township  
5 North, Ranges 31 & 32 East and  
fractional Townships, 6 North of the  
Base line of Ranges 31, 32 & 33 East  
of the Willamette Meridian, executed  
by Nicholas O. Walden, Deputy  
Surveyor under his contract No  
209, bearing date the 6<sup>th</sup> day of  
July 1874.

Commenced Oct. 23<sup>d</sup> 1874.

Completed Decemb. 9<sup>th</sup> 1874.

Index.

Referring the lines to the pages of the Field notes

T. 5 N. R. 31 E.

6.	5	4.	3	2	1	6.	
						12	5
						13	5
						24	5
						25	4.
31	32	33	34.	35	36	4	
8	8	9	9	9	9.		

Index:

Referring the lines to the pages of the Field notes

T. 5. N. R. 32. E.

6	5	4	3	2	1	12
					12	11
					13	11
					24	11
					25	10
31	32	33	34	35	36	10
14	14	15	15	15	15	

## Index:

Referring the lines to the pages of the Fieldnotes.

J. H. N. R. 27. C.

				27	27.
25	6.			2	1. 21.
24.	7				12. 20
23	18				13. 20
23	19.				24. 19
22	30.				25. 19
22	31.				36. 18.

6. 8  
Resurvey of the Exterior Boundaries of Township

North on a blank line along the East boundary of Sec. 1  
Var.  $22^{\circ} 06'$  East.

44.77 A point - 65 lks. East of the  $\frac{1}{4}$  Sec. Cor.

81.07 A point - 291 lks East of the corner to  
Townships 5 and 6 North, Ranges 31  
and 32 East

---

From the established corner to Townships  
5 and 6 North, Ranges 31 + 32 East -  
A run

West on a blank line along the North boundary of Sec. 1  
Var.  $20^{\circ} 30'$  East

40.41 A point - 58 lks, North of the  $\frac{1}{4}$  Sec. Cor.

80.00 A point - 86 lks East and 58 lks.  
North of the corner to Secs. 1 & 2

---

West on a blank line along the North boundary of Sec. 2  
Var.  $21^{\circ} 00'$  East

41.05 A point - 39 lks. North of the  $\frac{1}{4}$  Sec. Cor.

80.00 A point - 123 lks. East and 88 lks. North  
of the corner to Secs. 2 & 3

---

5 North Range 31 East Will. Mer. Oregon.

West on a blank line along the N. boundary of Sec. 3  
Var. 21° 15' East.

41.87 A point 88 lks. North of the 1/4 Sec. Cor.

80.00 A point 245 lks East and 88 lks. North of  
the corner to Secs. 3 + 4

West on a blank line along the N. boundary of Sec. 4  
Var. 21° 30' East

43.20 A point 125 lks. North of the 1/4 Sec. Cor.

80.00 A point 369 lks East and 104 lks North  
of the corner to Secs. 4 + 5

West on a blank line along the N. boundary of Sec. 5  
Var. 21° 15' East

44.33 A point 141 lks. North of the 1/4 Sec. Cor.

76.98 A point 780 lks. South of the corner to  
Secs. 5 + 6

80.00 A point 302 lks. West and 780 lks.  
South of the corner to Secs 5 + 6

October 23<sup>d</sup> 1874

10  
Perjury of the Exterior Boundaries of Township 5

West on a blank line along the N. boundary of Sec. 6  
Var. 22° 00' East -

37.48 A point - 780 lbs. South of the 1/4 Sec. Cor.

77.98 A point - 780 lbs South of the corner  
to Townships 5 + 6 North, Ranges  
30 + 31 East,

---

From the Standard Corner to Township 5 North  
Ranges 30 + 31 East - From

East on a blank line along the South boundary of Sec. 31  
T. 5 N. R. 31 E.

40.23 A point - 86 lbs. North of the 1/4 Sec. Cor.

80.00 A point - 23 lbs. West - and 86 lbs. North  
of the corner to Secs. 31 + 32

---

East on a blank line along the South boundary of Sec. 32

40.35 A point - 180 lbs. N. of the 1/4 Sec. Cor.

80.00 A point .69 lbs. West and 303 lbs North  
of the corner to Secs. 32 + 33

---

## List of Names

A list of the names of the individuals employed to assist in running, measuring and marking the lines and corners described in the foregoing field notes of the resurvey of the Exterior Boundary lines of Townships 4 North of Range 27 East, Townships 5 North of Ranges 31 & 32 East and Fractional Townships 6 North of the base line of Ranges 31, 32 & 33 East of the Willamette Meridian showing the respective capacities in which they acted.

Rufus S. Moore	Chairman
Henry Meldrum	Chairman
William H. Cooper	Assessor



We hereby certify that we assisted  
 Nicholas O. Madden, Deputy Surveyor in  
 resurveying the Exterior boundary line  
 of fractional Townships N<sup>o</sup>. 6 North of  
 the Ranges Nos. 31, 32 and 33 East of  
 Townships No. 5 North, Ranges Nos 31 and  
 32 East, and Township N<sup>o</sup>. 4 North of  
 the base line of Range No. 27 East of  
 the Villanette Meridian in the capaci-  
 ties indicated by our respective signa-  
 tures, and that said Exterior bound-  
 ary lines have been in all respects  
 to the best of our knowledge and belief  
 well and faithfully surveyed and  
 the boundary monuments placed accord-  
 ing to the instructions furnished by  
 the Surveyor General.

Rufus S. Moore Chairman  
 Henry Melvin Choquier  
 William H. Cooper Clerk

Subscribed and sworn to before me a Notary  
 Public, this 12<sup>th</sup> day of December 1874

John W. Eldrum  
 Notary Public

John W. Eldrum  
 Notary Public

U.S. Surveyor General's Office  
Eug. Portland Oregon  
June 23<sup>d</sup> 1875

The foregoing field notes of the survey ~~made~~  
the Re-Survey of the Exterior lines of T 4 N  
R 27 E Will. Mer. Oregon and of the  
Standard Parallel in R 27 E have  
executed by N. O. Walden U.S. Deputy  
Surveyor having been critically ex-  
amined the necessary corrections and  
explanations made the said field  
notes and the surveys they describe  
are hereby approved

Ben Simpson  
Sur Gen of Or.

33

I Nicholas O. Walden, Deputy Surveyor do solemnly swear that in pursuance of a contract with Benjamin Simpson W. S. Surveyor General for the State of Oregon bearing date the 6<sup>th</sup> day of July 1874, and in strict conformity to the laws of the United States and the instructions furnished by the said Surveyor General, I have faithfully resurveyed the Exterior Boundaries of Township 4 North, Range 27 East; Townships 5 North, Ranges 31 & 32 East and ~~Township~~ Townships 6 North of the base line of Ranges 31, 32 and 33 East of the Willamette Meridian in the State aforesaid, and do further solemnly swear that the foregoing are the true and original field-notes of such Survey.

Nicholas O. Walden  
Deputy Surveyor

Subscribed and sworn to by the above named Nicholas O. Walden, Deputy Surveyor before me a Notary Public on this the 12<sup>th</sup> day of December 1874

John W. Meldrum  
Notary Public.

Meldrum  
Notary Public