

North, Range No. 31 East Will. Mer. Oregon.

North between Secs. 13 & 14  
 Nav.  $21^{\circ} 45'$  East -

40.00 Drove cleared state and raised mound  
 of earth with pits &c as per instruc-  
 tions for  $\frac{1}{4}$  Sec. Cor.

42.50 Intersect State Boundary line 892  
 lbs. West of sta 4 Mill Corner.

Drove cleared state and raised mound  
 of earth with pits &c. as per instruc-  
 tions for closing corner to Tract, Secs.  
 13 & 14. Drove Pine State 2 ft long 2 in  
 square in East-pit. Sound rolling. Soil good.

Note.

The East boundary of Sec. 13 is 39.15 chas.  
 in length. Remeasured also the 5<sup>th</sup> mile  
 on the State Boundary line and find it  
 to be 80.60 chas. in length.

Nov. 13<sup>th</sup> 1874.



6 North Range No. 31 East Willamette, Oregon

89° 45' N, on true line

39.87 Drove charred stake and raised mound of earth with pits &c as per instructions for 1/4 Sec. Cor, - 50

79.75 The Corner.  
Sand rolling; Soil 2<sup>nd</sup> rate + 50

North between Secs. 14 & 15

Var. 21° 30' East

40.00 Drove charred stake and raised mound of earth with pits &c. as per instructions for 1/4 Sec. Cor.

43.00 Intersect State Boundary line 823 links West of the 3 Mile Corner.

Drove charred stake and raised mound of earth with pits &c. as per instructions for closing corner to fractional Secs. 14 & 15

Drove line stake 2 ft long 2 in square in East pit

Sand rolling; Soil good.



North Range No. 31 East Will Mer. Oregon

Sand rolling; soil 1<sup>st</sup> rate.

East on random line between Secs 15 + 22

40.00 Set temporary 1/4 Sec. Corner.

80.70 Intersect N & S line 14 Secs South of the corner.

S 89° 57' N. on true line

40.35 Drove charred stake and raised mound of earth with pits &c. as per instructions for 1/4 Sec. Cor.

80.70 The Corner.

Sand rolling; soil good.

North between Secs. 15 + 16

Var. 21° 30' East.

40.00 Drove charred stake and raised mound of earth with pits &c. as per instructions for 1/4 Sec. Cor.

43.33 Intersect State Boundary line 800 lbs West of the 2-mile corner, where Drove charred stake and raised mound



## Subdivisional lines of Fract. Township No.

of earth with pins, &c. as  
per instructions for corners  
to fractional Secs. 15 & 16

Drove Pine Stake 2 ft long 2 in  
square in East pit.

Sand rolling; soil good.

Note I remeasured the 3<sup>d</sup> mile  
on the State Boundary line  
and find it to be 80.80 chains  
in length.

---



19  
169

Subdivisional lines of Tract Township No 6

Drove Pine stake 2 ft. long 2 in  
square in S.E. pit  
Land rolling; soil good

---

East on random line between Secs. 16 & 21  
40.00 Set temporary  $\frac{1}{4}$  Sec. Cor.  
81.40 Intersect N. & S. line .40 lbs.  
South of the corner,  
889°43' W. on true line  
40.70 Drove charred stake and raised  
mound of earth with pits &c  
as per instructions for  $\frac{1}{4}$  Sec. Cor.  
81.40 The Corner.  
Land gently rolling;  
soil good

---

North between Secs 16 & 17  
Var. 21°30' East  
40.00 Drove charred stake and  
raised mound of earth with  
pits &c. as per instruc-



43170

North Range No 31 East Willaber, Oregon

tions for 1/4 Sec. Corner.

44100

Intersect State Boundary line 964  
links West of the 1<sup>st</sup> Mill Corner.

Drove chipped stake and raised  
mound of earth with pits etc. as  
per instructions for corner to frac-  
tional Secs. 16 + 17

Drove new Stake 2 ft long 2 in.  
square in East pit.

Land gently rolling.

Soil good.





North, Range N<sup>o</sup> 31 East Miller, Oregon

39.85 West on true line between Secs. 18 & 19  
 Left Bank of the Columbia River, Set  
 Poplar Post  $4\frac{1}{2}$  ft. long 4 in diam;  
 drove charred stake and raised mound  
 of earth with pits &c. as per instruc-  
 tions for corner to fractional Secs. 18 & 19 - 350  
 Sand hillside sloping to N.W.  
 Soil 2<sup>nd</sup> rate.

North between Secs. 17 & 18  
 Var.  $21^{\circ} 30'$  East -  
 35.25 Intersect - State Boundary line 568  
 lbs East of the Initial Point where  
 Set Basalt Stone  $18 \times 12 \times 5$  for closing  
 corner to fractional Secs. 17 & 18 - 300  
 Sand hillside sloping to N.W.  
 Soil 2<sup>nd</sup> rate.

(Note) I remeasured the 1<sup>st</sup> mile  
 on the State Boundary from the Initial  
 Point to the 1<sup>st</sup> mile corner and found  
 it to be 90.00 chains in length.  
 Nov. 18<sup>th</sup> 1874



## List of Names

A list of the names of the individuals employed to assist in running, measuring or marking the lines and corners described in the foregoing field notes of the Survey of the Subdivisional lines of Gerald Township No. 6 North of the Base line of Range No. 31 East of the Willamette Meridian showing the respective capacities in which they acted;

Rufus S. Moore	Chainman
J. Henry Meldrum	Chainman
William H. Cooper	Assessor



183

We hereby certify that we assisted  
Nicholas O. Walden, Deputy Surveyor, in  
surveying the subdivisional lines of Tract,  
Township No. 6 North of the base line  
of Range No. 31 East of the Willamette  
Meridian in the capacities indicated by  
our respective signatures, and that  
said fractional Township has been in  
all respects to the best of our knowledge  
and belief well and faithfully survey-  
ed and the boundary monuments plant-  
ed according to the instructions furnished  
by the Surveyor General

Henry Alderman Chairman  
Rufus S. Moore Chairman  
William H. Cooper Chairman

Subscribed and sworn to before me a

Notary Public this 12<sup>th</sup> day of Dec. 1874

John W. Alderman  
Notary Public.

W. Alderman  
Notary Public



I, Nicholas O. Walden, Deputy Surveyor do solemnly swear that in pursuance of a contract with Benjamin Simpson U. S. Surveyor General for the State of Oregon bearing date the 6<sup>th</sup> day of July 1874, and in strict conformity to the laws of the United States and the instructions furnished by the said Surveyor General, I have faithfully surveyed the subdivision and boundary lines of Frazer Township No. 6 North of the base line of Range No. 31 East of the Willamette Meridian in the State aforesaid and do further solemnly swear that the foregoing are the true and original field notes of such such Survey.

Nicholas O. Walden

Deputy Surveyor

Subscribed and sworn to by the above named Nicholas O. Walden Deputy Surveyor on this the 12<sup>th</sup> day of December 1874

John W. Meldrum  
Notary Public

W. Meldrum

NOTARY PUBLIC  
WILLAMETTE COUNTY  
OREGON



U S Surveyor Generals Office  
Portland Oregon June 25 1875

The foregoing field notes of the survey of the subdivisional lines of Township 6 North Range  
3 East Willamette Meridian Oregon executed by N. O. Walden D. S. under Contract  
No 209 bearing date July 6 1874 having been critically examined the necessary  
corrections and explanations made the said field notes and the surveys they  
describe are hereby approved

Ben Simpson  
Sur Genl of Oregon