

151

Subdivisional Lines of Tract Township No 6

Begin at the corner to Secs 35 & 36
in the South Boundary of the Town-
ship and run

North between Secs. 35 & 36

12.00 Juniper Canyon Course West - 200

40.00 Drove charred stake and raised
mound of earth with pits 4c as
per instructions for $\frac{1}{4}$ Sec. Cor. + 250

80.00 Drove charred stake and raised
mound of earth with pits 4c.
as per instructions for corner to
Secs. 25, 26, 35 & 36 - 60

Drove Willow Stake 2 ft. long 2
in square in S.E. pit.
Sand lily; Soil good

East on random line between Secs. 25 & 36

40.00 Set temporary $\frac{1}{4}$ Sec. Cor.

81.00 Intersect East boundary of Township
200 lbs. South of the Corner

This close not being within the limits

North, Range No. 31 East - Will. Mer. Oregon

required by the instructions I retrace this line and the line between Secs. 35 & 36 and find no error.

I therefore begin at the corner to Townships 5 & 6 North, Ranges 31 & 32 East and run thence

North on a blank line along the East boundary of Sec. 36
T 6 N. R. 31 E.

40.46 The 1/4 Sec. Cor.

81.44 The corner to Secs. 25 & 36

Note The South boundary of Sec. 36 in this Township is 80.86 chains in length and has a bearing to the South of West 58 lbs. (See field notes of Resurvey of Exterior Boundaries of T. 5 N. R. 31 E.) therefore

88° 34' W. on true line between Secs 25 & 36

49.50 Drove charred stake and raised mound of earth with pits &c as per instructions for 1/4 Sec. Cor.

- 100

81.00 The Corner to Secs. 25, 26, 35 & 36

- 150

Land hilly Soil good

Subdivisional lines of Frac. Township No. 6

North between Secs. 25 + 26

Var. $21^{\circ}30'$ East -

40.00 Drove charred stake and raised mound
of earth with pits &c as per instruc-
tions for $\frac{1}{4}$ Sec. Cor. + 100

80.00 Drove charred stake and raised mound
of earth with pits &c as per instruc-
tions for corner to Secs. 23, 24, 25 + 26 + 30

Drove Pine Stake 2 ft long 2 in
square in S.E. pit.

Sand rolling; Soil good.

East on random line between Secs. 24 + 25 -

40.00 Set temporary $\frac{1}{4}$ Sec. Cor.

81.60 Intersect East Boundary of Township
278 lbs. South of the corner.

$88^{\circ}01'$ W. on true line

40.80 Drove charred stake and raised mound
of earth with pits &c. as per in-
structions for $\frac{1}{4}$ Sec. Cor.

81.60 The corner.

Sand rolling; Soil 1st rat.

North Range No. 31 East Will. Mer. Oregon

North between Secs. 23 + 24,

Var. $21^{\circ} 30'$ East -

40.00 Drove Churred Stake and raised mound of earth with pits &c. as per instructions for $\frac{1}{4}$ Sec. Cor.

80.00 Drove Churred Stake and raised mound of earth with pits &c. as per instructions for corner to Secs. 13, 14, 23 + 24

Drove Pine Stake 2 ft. long 2 in square in S.E. pit -

Sand rolling; Soil 1st rate.

Nov 12th 1874.

East on random line between Secs. 13 + 24,

40.00 Set temporary $\frac{1}{4}$ Sec. corner,

82.00 Intersect East Boundary of Township

346 lbs. South of the corner,

This close being out of the required limits and finding no error in my own work I began at the corner to Secs.

25 + 26 in the East Boundary of the Township and run North on the East boundary of Secs. 25, 24 + 13 as follows,

155

Subdivisional Lines of Tract Township No. 6

North on a blank line along the East boundary of Sec 25

40.46 The $\frac{1}{4}$ Sec. Corner80.00 A Point 66 lbs West and 90 lbs South of
the corner to Secs. 24 + 25

Continuing on same line

North on a blank line along the E. boundary of Sec. 24

40.47 A point 103 lbs West of the $\frac{1}{4}$ Sec. Cor.80.00 A point 126 lbs West and 184 lbs. South
of the corner to Secs. 13 + 24

This result very nearly corresponding
with the close, as above I conclude
that - it is right. Therefore,

887°31' W. on true line between Secs. 13 + 24

41.00 Drove sharpened stake and raised mound
of earth with spade &c, as per instruc-
tions for $\frac{1}{4}$ Sec. Cor.

82.00 The corner

Soand rolling;

Soil $\frac{1}{2}$ rot.

North, Range No. 31 East Will. Mer. Oregon.

North between Secs. 13 & 14
 Nav. $21^{\circ} 45'$ East -

40.00 Drove cleared state and raised mound
 of earth with pits &c as per instruc-
 tions for $\frac{1}{4}$ Sec. Cor.

42.50 Intersect State Boundary line 892
 lbs. West of sta 4 Mill Corner.

Drove cleared state and raised mound
 of earth with pits &c. as per instruc-
 tions for closing corner to Tract, Secs.
 13 & 14. Drove Pine Stake 2 ft long 2 in
 square in East-pit, sound rolling. Soil good.

Note.

The East boundary of Sec. 13 is 39.15 chas.
 in length. Remeasured also the 5th mile
 on the State Boundary line and find it
 to be 80.60 chas. in length.

Nov. 13th 1874.

725
157

Subdivisional Lines of Tract, Township No.

North between Secs. 34 & 35-

40.00 Set Basalt Stone 20 x 8 x 5, 10

in ground for $\frac{1}{4}$ Sec. Corner. - 300

41.00 Bed of Juniper Canyon Course West - 50

80.00 Drove charred stake and raised mound
of earth with pits &c, as per in-
structions for corner to Secs. 26, 27,
34 & 35-

+ 350

Drove Willow stake 2 ft long 2 in
square in S.E. pit
Land hilly; Soil 2nd rate

East on random line between Secs. 26 & 35

40.00 Set temporary $\frac{1}{4}$ Sec. Cor.

80.46 Intersect N & S line 35 lbs. South of
the corner.

889°45' W. on true line

40.23 Drove charred stake and raised
mound of earth with pits &c, as
per instructions for $\frac{1}{4}$ Sec. Cor.

80.46 The Corner

Land rolling; Soil good, good grass

6 North Range No. 31 East Will. Mer. Oregon

North between Secs. 26 & 27

Var. $21^{\circ}30'$ East-

40.00 Drove charred stake and raised mound of earth with pits &c, as per instructions for $\frac{1}{4}$ Sec. Cor.

53.00 Ravine Course S.W. - 150

80.00 Drove charred stake and raised mound of earth with pits &c as per instructions for corner to Secs. 22, 23, 26 & 27

Drove Pine stake 2 ft. long 2 in square in S.E. pit -

+ 150

Sand lilly; Soil good

East on random line between Secs. 23 & 26

40.00 Set temporary $\frac{1}{4}$ Sec. Corner

80.00 Intersect N & S line 10 lbs. south of the corner.

S. $89^{\circ}36'$ W. on true line

40.00 Drove charred stake and raised mound of earth with pits &c as per instructions for $\frac{1}{4}$ Sec. Cor.

Subdivisional lines of Tract Township No.

80.00 The Corner
 Sound gently rolling
 Soil 1st rate.

North between Secs. 22 & 23
 Var. 21° 30' East

40.00 Drove Churned Stake and raised mound of earth with pits &c as per instructions for 1/4 Sec. Cor.

80.00 Drove Churned Stake and raised mound of earth with pits &c. as per instructions for corners to Secs. 14, 15, 22 & 23

Drove Pine Stake 2 ft. long, 2 in. square in S.E. pit.
 Sound rolling; Soil 1st rate.

East on random line between Secs. 14 & 23

40.00 Set temporary 1/4 Sec. Cor.

79.75 Intersect N & S line 35 lbs. south of the corner.

6 North Range No. 31 East Willamette, Oregon

89° 45' N, on true line

39.87 Drove charred stake and raised mound of earth with pits &c as per instructions for 1/4 Sec. Cor.

- 50

79.75 The Corner.

+ 50

Land rolling; Soil 2nd rate

North between Secs. 14 & 15

Var. 21° 30' East

40.00 Drove charred stake and raised mound of earth with pits &c. as per instructions for 1/4 Sec. Cor.

43.00 Intersect State Boundary line 823 links West of the 3 Mile Corner.

Drove charred stake and raised mound of earth with pits &c. as per instructions for closing corner to fractional Secs. 14 & 15

Drove line stake 2 ft long 2 in square in East pit

Land rolling; Soil good.

161

Subdivisional Lines of Tract, Township N^o

	North between Secs. 33 & 34	
40.00	Drove charred stake and raised mound of earth with pits &c. as per instructions for $\frac{1}{4}$ Sec. Cor	- 50
52.50	Juniper Canyon Course West	- 300
80.00	Drove charred stake and raised mound of earth with pits &c. as per instructions for corner to Secs. 27, 28, 33 & 34	+ 300
	Drove Willow stake stake 2 ft, long 2 in. square in S.E. pit. Land hilly; soil good Good grass	

	East on a random line between Secs. 27 & 34	
40.00	Set temporary $\frac{1}{4}$ Sec. corner	
81.20	Intersect N & S line at the corner	
	West on true line	
40.60	Set Basalt stone 24 x 10 x 4 - 12 in. in ground for $\frac{1}{4}$ Sec. Cor.	- 100
81.20	The corner	+ 100
	Land rolling; soil 1 st rate; good grass.	

6 North, Range No. 31 East - Will. Mer. Oregon

Note

The South boundary of Sec. 34 is 81.22 chains in length. (See field notes of the Resurvey of Exterior Boundaries of T. 5 N. 31 E. North boundary of Sec. 3)

Nov 14th 1874.

North between Secs 27 + 28

Var. 22° 15' East

37.00 Prairie course 8 m. - 125-

40.00 Set Basalt stone 16 x 8 x 6, 8 in. in ground for 1/4 Sec. Cor. + 40

80.00 Drove chorned stake and raised mound of earth with pits &c as per instructions for corner to Secs 21, 22 27 + 28 + 100

Drove pine stake 2 ft - long 2 in square in S.E. pit -

Land rolling; soil good
Good grass.

Subdivisional lines of Tract, Township No. 6

East on random line between Secs. 22 + 27

40.00 Set temporary $\frac{1}{4}$ Sec. Cor.

80.90 Intersect N + S line at the corner

West on true line

40.45 Drove churred stake and raised mound of earth with spits &c. as per instructions for $\frac{1}{4}$ Sec. Corner.

56.00 Ravine. Course S.W.

-100

80.90 The Corner.

+100

Land rolling; Soil good

North between Secs. 21 + 22

Var. $21^{\circ}30'$ East

40.00 Drove churred stake and raised mound of earth with spits &c. as per instructions for $\frac{1}{4}$ Sec. Cor.

80.00 Drove churred stake and raised mound of earth with spits &c. as per instructions for corner to Secs. 15, 16, 21 + 22

Drove Pine Stake 2 ft. long 2 in square in S.E. pt.

North Range No. 31 East Will Mer. Oregon

Sand rolling; soil 1st rate.

East on random line between Secs 15 + 22

40.00 Set temporary 1/4 Sec. Corner.

80.70 Intersect N & S line 14 Secs South of the corner.

S 89° 57' N. on true line

40.35 Drove charred stake and raised mound of earth with pits &c. as per instructions for 1/4 Sec. Cor.

80.70 The Corner.

Sand rolling; soil good.

North between Secs. 15 + 16

Var. 21° 30' East.

40.00 Drove charred stake and raised mound of earth with pits &c. as per instructions for 1/4 Sec. Cor.

43.33 Intersect State Boundary line 800 lbs West of the 2-mile corner, where Drove charred stake and raised mound

Subdivisional lines of Fract. Township No.

of earth with pins, &c. as
per instructions for corners
to fractional Secs. 15 & 16

Drove Pine Stake 2 ft long 2 in
square in East pit.

Sand rolling; soil good.

Note I remeasured the 3^d mile
on the State Boundary line
and find it to be 80.80 chains
in length.

6 North, Range No. 31 East - Will. Mer.

North between Secs. 32 & 33

- 40.00 Drove Chopped Stake and raised mound of earth with pits &c. as per instructions for $\frac{1}{4}$ Sec. Cor. - 40
- 65.00 Juniper Canyon. Course West - -200
- 80.00 Drove Chopped Stake and raised mound of earth with pits &c. as per instructions for corner to Secs. 28, 29, 32 & 33 + 200
- Drove Pine Stake 2 ft. long 2 in square in S.E. pit.
- Sound lilly; Soil 2nd rate

East on random line between Secs. 28 & 33

- 40.00 Set temporary $\frac{1}{4}$ Sec. Cor.
- 81.26 Intersect N. & S. line 18 lbs. South of the corner.
- 889° 52' W. on true line
- 21.25 Ravine Course South - 150
- 40.63 Drove chopped stake and raised mound of earth with pits &c. as per instructions for $\frac{1}{4}$ Sec. Cor. + 150

Subdivisional lines of Tract Township No. 6

81.26 The Corner,
Sand hilly; soil good
Good grass

Note.

The South Boundary of Sec. 33.
is 81.24 chains in length. (See
field notes of the Resurvey of
the Exterior Boundaries of T. 5
N. R. 31 E., the North Boundary
of Sec. 4)

North between Secs. 28 & 29
Var. 22° East-

40.00 Drove charred stake and raised
mound of earth with pits
&c. as per instructions for
1/4 Sec. Cor.

80.00 Drove charred stake and raised
mound of earth with pits &c.
as per instructions for corner to
Secs. 20, 21, 28 & 29

Drove Red Stake 2 ft long 2 in.
square in S.E. part.

North Range No. 31 East Will. Abn.

Land rolling; soil good

East on random line between Secs. 21 & 28

40.00 Set temporary 1/4 Sec. Cor.

81.20 Intersect N + S line at the corner.

West on true line

40.60 Drove charred stake and raised mound of earth with pits &c. as per instructions for 1/4 Sec. Cor.

81.20 The corner,

+ 75

Land rolling; Soil 1st rate.
Nov. 16th 1874.

North between Secs. 20 & 21

Var. 21° 45' East

40.00 Drove charred stake and raised mound of earth with pits &c. as per instructions for 1/4 Sec. Cor.

80.00 Drove charred stake and raised mound of earth with pits &c. as per instructions for corner to Secs. 16,

17, 20 & 21

19
169

Subdivisional lines of Tract Township No 6

Drove Pine stake 2 ft. long 2 in
square in S.E. pit
Land rolling; soil good

East on random line between Secs. 16 & 21
40.00 Set temporary $\frac{1}{4}$ Sec. Cor.
81.40 Intersect N. & S. line .40 lbs.
South of the corner,
889°43' W. on true line
40.70 Drove charred stake and raised
mound of earth with pits &c
as per instructions for $\frac{1}{4}$ Sec. Cor.
81.40 The Corner.
Land gently rolling;
soil good

North between Secs 16 & 17
Var. 21°30' East
40.00 Drove charred stake and
raised mound of earth with
pits &c. as per instruc-

43170

North Range No 31 East Willaber, Oregon

tions for 1/4 Sec. Corner.

44100

Intersect State Boundary line 964
links West of the 1st Mill Corner.

Drove chipped stake and raised
mound of earth with pits &c. as
per instructions for corner to frac-
tional Secs. 16 + 17

Drove new Stake 2 ft long 2 in.
square in East pit.

Land gently rolling.

Soil good.



21
171

Subdivisional lines of Fract. Township N^o

North between Secs. 31 & 32

1.25 Drive juniper Canyon, around hill cross N.E. & S.W.

40.00 Drove Chopped stake and raised mound of earth with pits &c. as per instructions for $\frac{1}{4}$ Sec. Cor. Top of hill cross. N.E. & S.W.

+ 300

80.00 Drove Chopped stake and raised mound of earth with pits &c. as per instructions for corner to Secs. 29, 30, 31 & 32

Drove Pine Stake 2 ft. long
2 in square in S.E. pit
Sand $\frac{3}{4}$ hillside sloping to S.E.
" $\frac{1}{2}$ gently rolling.
Soil 2nd rate

East on random line between Secs. 29 & 32

40.00 Set temporary $\frac{1}{4}$ Sec. corner.

73.82 Intersect N + Shue 841 lbs. north of the corner.

6 North, Range No. 31 East Will. Mer. Oregon

N 83° 30' W. on true line between Secs. 29 + 32

37.15 Drove chorned stake and raised mound of earth with spits &c. as per instructions for 1/4 Sec. Cor.

74.30 The corner.

Land rolling; Soil good

(Note) The corner to Secs. 31 + 32 on the South Boundary of this Township stands, 73.29 chains West and 884 links North of the corner to Secs. 32 + 33 on the South Boundary. (See Field notes of the Resurvey of the Exterior Boundaries of Township No. 5 North, Range No. 31 East - the North boundary of Sec. 5)

In the line above the distance 74.30 chains on the true line corresponds with the distance 73.82. chos. on the random line.



173

Sub-divisional lines of Fract. Township 58^o

West on random line between Secs. 30 + 31

40.00 Set temporary $\frac{1}{4}$ Sec. Cor.

77.83 Intersect West Boundary of Township 90 lbs. South of the corner

S 89° 21' E, on true line

37.83 Drove Chopped stake and raised mound of earth with pile etc. as per instructions for $\frac{1}{4}$ Sec. Cor.

77.83 The corner.

Sand rolling

Soil 2nd stab.

Note the above close not being within the limits required by the instructions, to ascertain the cause I began at the corner to Township 5 + 6 North Ranges 30 + 31 East and run

North on a blank line along the West boundary of Sec. 31, T. 6 N. R. 31 East,

40.30 A point - 130 lbs. West of the $\frac{1}{4}$ Sec. Cor.

80.00 A point - 300 lbs West and 80 lbs South of the corner to Secs. 30 + 31, which shows the line between Secs. 30 + 31 to be correct.

174

6 North Range No. 31 East Will Mer. Oregon.

Finding such error in this line I continued to resurvey the West Boundary of the Township, running on the same line.

North on a blank line along the W. boundary of Sec. 30
 40.75 A point 251 lbs. West of the $\frac{1}{4}$ Sec. Cor.
 80.00 A point 172 lbs. West and 80 lbs South
 of the corner to Secs. 19 + 30

From the established corner to Secs.
 19 + 30 on the West Boundary of the
 Township I run

North on West boundary of Sec. 19
 Var. $21^{\circ} 45'$ East

26.90 Left Bank of the Columbia River, the
 Nevada corner here being obliterated
 I set Cedar Post $4\frac{1}{4}$ ft. long $4\frac{1}{2}$ in
 diam. drove charred stake and raised
 mound of earth with pulps &c as per
 instructions for corner to Tract Secs.
 19 + 24

Nov 17th 1874.

Subdivisional lines of Tract Township No

North between Secs. 29 + 30

Var. $21^{\circ}30'$ East

40.00 Drove charred stake and raised mound of earth with pits &c as per instructions for $\frac{1}{4}$ Sec. Cor.

80.00 Drove charred stake and raised mound of earth with pits &c. as per instructions for corner to Secs. 19 + 20, 29 + 30

Drove Pine stake 2 ft long
2 in square in S.E. pit.
Sand rolling; Soil good

East on a road on line between Secs. 20 + 29

40.01 Set temporary $\frac{1}{4}$ Sec. Cor.

73.52 Intersect N + S line 838 lbs.

North of the corner.

N $83^{\circ}30'$ W. on true line

37.00 Drove charred stake and raised mound of earth with pits &c. as per instructions for $\frac{1}{4}$ Sec. Cor.

176

6 North Range No 31 East Will. Mer. Oregon

74.00 The corner
Land rolling; soil good

-
- West on random line between Secs. 19 + 30
 - 40.00 Set temporary 1/4 Sec. Cor.
 - 79.00 Intersect West Boundary of Town-
ship 25 lks. South of the corner.
 - 889° 19' E. on true line
 - 7.00 Leave Columbia River Bottom line N. 8. 45. W.
 - 39.00 Drove charred stake and raised mound
of earth with pits &c. as per instructions
for 1/4 Sec. Cor. +300
 - 79.00 The corner +75
Land E 1/2 gently rolling W 1/2 hillside
sloping to N.W.
Soil good, Good grass.
-

North between Secs. 19 + 20
Var. 21° 45' East

40.00 Drove charred stake and raised mound
of earth with pits &c as per instrue.

Subdivisional lines of Frack Township No 6

Trons for $\frac{1}{4}$ Sec. Cor.

80.00 Drove Charred stake and raised mound of earth with pits &c. as per instructions for corner to Secs. 17, 18, 19 & 20

Drove Willow Stake 2 ft long
2 in square in S.E. pit
Land gently rolling; soil good.

East on random line between Secs. 17 & 20

40.00 Set temporary $\frac{1}{4}$ Sec. Cor.

73.40 Intersect N & S line 902 lbs.

North of the corner.

N 83° 00' W. on true line

37.00 Drove Charred stake and raised mound of earth with pits &c. as per instructions for $\frac{1}{4}$ Sec. Cor.

74.00 The corner.

Land rolling; soil good

North, Range N^o 31 East Miller, Oregon

39.85 West on true line between Secs. 18 & 19
 Left Bank of the Columbia River, Set
 Poplar Post $4\frac{1}{2}$ ft. long 4 in diam;
 drove charred stake and raised mound
 of earth with pits &c. as per instruc-
 tions for corner to fractional Secs. 18 & 19 - 350
 Sand hillside sloping to N.W.
 Soil 2nd rate.

North between Secs. 17 & 18
 Var. $21^{\circ} 30'$ East -
 35.25 Intersect - State Boundary line 568
 lbs East of the Initial Point where
 Set Basalt Stone $18 \times 12 \times 5$ for closing
 corner to fractional Secs. 17 & 18 - 300
 Sand hillside sloping to N.W.
 Soil 2nd rate.

(Note) I remeasured the 1st mile
 on the State Boundary from the Initial
 Point to the 1st mile corner and found
 it to be 90.00 chains in length.
 Nov. 18th 1874

Meanders of the Left-Bank of the Columbia
River in Tract T, 6 N. R., 31 E.

Begin at the corner to Tract Secs, 19 + 24
in the West Boundary of the Township
and run thence in Tract Sec. 19

N. 33° 00' E. 17.35

N. 39° 00' E. 48.00 To the corner to Tract, Secs
18 + 19

Thence in Tract, Sec. 18

N. 29° 00' E. 18.50

N. 42° E. 15.50

N. 46° E. 11.00 To point West of Initial Point on
the State Boundary line.

East 6.32 To the Initial Point on the
State Boundary line.

Nov 18th 1874.

General Description

The land in this Township is rolling or hilly; the soil generally good and in some places 1st class. Good bunch grass grows in abundance all over the Township.

Being dry and having no facilities for irrigation it is chiefly valuable for grazing purposes.

List of Names

A list of the names of the individuals employed to assist in running, measuring or marking the lines and corners described in the foregoing field notes of the Survey of the Subdivisional lines of Gerald Township No. 6 North of the Base line of Range No. 31 East of the Willamette Meridian showing the respective capacities in which they acted;

Rufus S. Moore	Chieftain
J. Henry Meldrum	Chieftain
William H. Cooper	Assist.

183

We hereby certify that we assisted
Nicholas O. Walden, Deputy Surveyor, in
surveying the subdivisional lines of Tract,
Township No. 6 North of the base line
of Range No. 31 East of the Willamette
Meridian in the capacities indicated by
our respective signatures, and that
said fractional Township has been in
all respects to the best of our knowledge
and belief well and faithfully survey-
ed and the boundary monuments plant-
ed according to the instructions furnished
by the Surveyor General

Henry Alderman Chairman
Rufus S. Moore Chairman
William H. Cooper Chairman

Subscribed and sworn to before me a

Notary Public this 12th day of Dec. 1874

John W. Alderman
Notary Public.

W. Alderman
Notary Public

I, Nicholas O. Walden, Deputy Surveyor do solemnly swear that in pursuance of a contract with Benjamin Simpson U. S. Surveyor General for the State of Oregon bearing date the 6th day of July 1874, and in strict conformity to the laws of the United States and the instructions furnished by the said Surveyor General, I have faithfully surveyed the subdivision and boundary lines of Frazer Township No. 6 North of the base line of Range No. 31 East of the Willamette Meridian in the State aforesaid and do further solemnly swear that the foregoing are the true and original field notes of such such Survey.

Nicholas O. Walden

Deputy Surveyor

Subscribed and sworn to by the above named Nicholas O. Walden Deputy Surveyor on this the 12th day of December 1874

John W. Meldrum
Notary Public

W. Meldrum

John

U S Surveyor General's Office
Portland Oregon June 25 1875

The foregoing field notes of the survey of the subdivisional lines of Township 6 North Range
3 East Willamette Meridian Oregon executed by N. O. Walden D. S. under Contract
No 209 bearing date July 6 1874 having been critically examined the necessary
corrections and explanations made the said field notes and the surveys they
describe are hereby approved

Ben Simpson
Sur Genl of Oregon