

6232

Field notes of the Survey of
the Subdivisional lines of Twp. Township
No. 6, North of the Base line
of Range No. 32 East of the
Willamette Meridian. Executed
by Nicholas O. Walden, Deputy
Surveyor, under his Contract
No. 209, bearing date the 6th
day of July 1874.

Commenced Nov. 20th 1874

Completed Nov. 23rd 1874.

R. P. Earhart

239238

240

Index:

Referring the lines to the pages in the Fieldnotes

6	5	4	3	2	1
7	8	9	10	11	12

State Boundary lines:

18	21	17	15	16	12	15	8	14	5	13	
20		19		15		11		8		4	
19	19	20	14	21	11	22	7	23	3	24	4
18		18		14		10		7			
30	17	29	13	28	10	27	6	26	2	25	2
17		16		13		9		6		1	
31	16	32	12	33	9	34	5	35	1	36	

of R N^o 32 East Will. Mer. Oregon 242

North between Secs 25 & 26.

Var 22° 30' E.

4000 Set Basalt Stone 15 x 9 x 7. 8 in - 50
in ground for 1/4 Sec corner

8000 Set Basalt Stone 14 x 10 x 6 7/8 in - 75
in ground for corner to Secs 23 24 25 & 26.

Land rolling Soil good
Good grass.

East An random line between Secs 24 & 25

4000 Set temporary 1/4 Sec corner

8000 Intersect East boundary of Townsh.

129 Ws South of the corner.

This intersection not being within
the limits required by the instructions
I retraced this line and the line
between Secs 25 & 26: and 25 & 36 finding
no error I therefore begin at corner
to Secs 25 & 36. on east boundary
of Township and run:

North on east boundary of Sec 25.

1000 Wagon road in ravine Course NW - 200

4050 1/4 Sec Corner + 200

8085 A point 80 lbs East of corner to

24^B Subdivisional lines of Township C. North

Sec 24 & 25.

+ 150

Finding that the length of this line nearly corresponds to the close of my line between Sec 24 & 25 I therefore run:

- 389°05' W. on tree line between Sec 24 & 25
 4000 Set Basalt Stone 18 x 8 x 6.9 in
 ' in ground for $\frac{1}{4}$ Sec corner
 7000 Wagon road in ravine course N W
 ' S E.
 8000 The corner
 ' Land hilly Soil good

North between Sec 23 & 24.

Var 21° 30' E.

- 2300 Wagon road in ravine course N W,
 ' S E.
 4000 Set Basalt Stone 14 x 10 x 8.7 in in
 ' ground for $\frac{1}{4}$ Sec corner + 125
 8000 Set Basalt Stone 12 x 8 x 6.7 in in
 ' ground for corner to Secs 13, 14, 23, & 24. + 125
 Land hilly Soil 2^d rate
 Good grass

Range 32 East Will Mer Oregon ⁴ 244

East between Secs 13 & 24.

4000 Set temporary 1/4 Sec corner

7815 Intersect East boundary of Townsh.

212 lbs South of the corner

This intersection not being within the limits required by the instructions I retraced this line and the line between Secs 23, 24, 24 & 25 and finding no error I therefore begin at corner to Secs 24 & 25 on east boundary of Township and run

North on east boundary of Sec 24.

4047 A point 61 lbs East of 1/4 Sec cor

8066 A point 172 lbs East of corner to Secs 13 & 24.

Finding that the length and bearing of this line nearly corresponds to the close of my line between Secs 13 & 24 I therefore run:

18829 W. On true line bet. Secs 13 & 24.

39.07 Set Basalt Stone 13 x 10 x 9.8 in in ground for 1/4 Sec corner + 40

78.15 The corner - 100

Land rolling Soil good

6. North Range 32 East of Will. No. 2

General Description

The land in this fr. Township is generally rolling prairie, covered with good bunchgrass. The Soil is generally good sandy loam suitable for agricultural and grazing purposes. There is no timber and no water in the Township.

List of Names

A list of the names of the individuals employed to assist in running measuring and marking the lines and corners described in the foregoing field notes of the Subdivisional lines of Fractional Township No. 6 North of the base line of Range No. 32 East of the

263

Willamette Meridian, showing the
respective capacities in which they
acted)

Rufus L. Moore Chairman
Henry Meldrum Chairman
William H. Cooper Assn

We hereby certify that we assisted
 Nicholas O Walden, Deputy Surveyor, in
 Surveying the Subdivisional lines of Trac-
 tional Township No 6 North of Range 32
 East of Willamette Meridian in the capa-
 cities indicated by our respective signatures
 and that said fractional Township has
 been in all respects to the best of our
 knowledge and belief well and faithfully
 Surveyed and the boundary monuments
 started according to the instructions
 furnished by the Surveyor General

R. J. Moore Chairman

Henry Meldrum Chairman

William, H. Cooper Assman

Subscribed and sworn to before me

a Notary public this the 12th day
 of December 1874.

John W. Meldrum
 Notary Public

Meldrum
 John W.

265

I Nicholas O Walden Deputy Surveyor, do solemnly swear that in pursuance of a contract with Benjamin Simpson U S Surveyor General for the State of Oregon bearing date the 6th day of July 1874. and in strict conformity to the laws of United States and the instructions furnished by the said Surveyor General I have faithfully surveyed the Subdivisional lines of Fractional Township No 6 North of the base line of Range No 32 East of the Willamette Meridian in the State aforesaid, and do further solemnly swear that the foregoing are the true and original fieldnotes of such survey.

Nicholas O Walden

Deputy Surveyor

Subscribed and sworn to by the above named Nicholas O Walden, Deputy Surveyor this 19th day of March

1875.

John W. Melanum
Notary Public

my of

266

U.S. Surveyor General's Office
Portland Oregon June 23rd 75

The foregoing field notes of the survey of the subdivisional
lines of N. W. R. 32 East Mill New Oregon executed by
Nicholas A. Walden D. S. under contract No 209 ^{bearing date 6th July 1874} having
been critically examined the necessary corrections
and explanations made the said field notes and the
survey they describe are hereby approved

Ben Simpson
Assistant of