

Township 5 North Range 32 East
 North on East Boundary of Sec 12
 Town 5 North Range 32 East
 Variation 21° East.

40.00 Set 1/4 Sec Post in Prairie Corn
 North — 100 ft. Drive Charred
 Stake. Dug Pit raised
 mound as per instructions

80.00 Set Post Corner for Secs 1:12,
 6th on High Ridge + 75 ft.
 Drive Charred Stake. Dug Pit
 raised mound as per instructions.
 Land Broken grass good. Soil 2°
 Rate.

North on East Boundary of Sec 1.
 Town 5 North Range 32 East
 Variation 21° East.

40.00 Set 1/4 Sec Post Drive Charred
 Stake. Dug Pit raised
 mound as per instructions.

80.00 Set Post Corner for Secs Township
 5 1/2 North. Ranges 32 + 33 East

Township 5 north Range 32 East
Secs 1, 6, 36 & 37. Grove Charred
Stake Wagon Pit raised
Ground as per Instruction.
Land Broken grass good
Soil 2^o Rate.

May 9th 1845

Met on Pandora between Towns
5th north Range 32 East
Variation 21^o East.

At 40 & 80 Chains set 1/4 half
Mile Post 478 Chains 66 Sink,
Intersect North & South Line
2 Chains 150 Sink, South of Post.
Hence the Correction will be South
89^o 46' 26" East. on True Line.

S. 89^o 46' 26"

East on North Boundary of Sec
6 Town 5 north Range 32 East
Variation 21^o East.

38.66 Set 1/4 Sec Post on north side
of Big Hollow on side Hill
Grove Charred Stake Wagon

Township 5 North Range 32 East.

Pit raised ground as per instructions

57.00 dry bed of branch some water standing in holes just below the line. lower south of west

78.66

~~11.00~~

Set Post Corner Secs 5, 6,

31 + 32, on north side of Gully above Charred Stake dug pit raised ground as per instructions

Sand rolling grass good
Soil 2^o Rate

S. 89° 46' 26" East on north boundary of Sec 5 Township 5 North Range 32 East.

Variation 20" East

20.00 Deep Prairie Spring Water 15 chains south of line

40.00 Set 1/4 Sec Post on East side of Prairie above Charred Stake. Dug pit raised ground as per instructions

Township 5 North Range 32 East
8000 Set Post Corner for Secs 4, 5,
32 & 33. On east side of Prairie
near Bottom. One Charred
Stake. Very Silty - raised
mound as per instructions
Sand Broken. Grass good
Soil 2^d Rate.

$89^{\circ}46'26''$ East on north Boundary of Sec
4, Township 5 North Range 32 East
Var 21^o East.

4000 Set 4th Sec Post on East side of
Prairie. One Charred Stake
Very Silty - raised mound
as per instructions.

8000 Set Post Corner for Secs 3, 4,
33 & 34. Hill side sloping to
the west. One Charred Stake
Very Silty - raised mound,
as per instructions
Sand Rolling. Grass good
Soil 3^d Rate.

Township 5 North Range 32 East.
S. 89° 46' 26" East on North Boundary of Sec 3.

Town 5 North Range 32 East,
Variation 21° East.

4000 Set 1/4 Sec Post In Head of Small
gully East of Prairie Dug Pitt,
Drove Charred Stake, raised
mound as per instructions

8000 Set Post Corner for Secs 2, 3,
34 & 35. On Top of Ridge sloping
to the South West Drove Charred
Stake Dug Pitt, raised
mound as per instructions.

Sand Rolling. Grass good
Soil 2nd Rate.

S. 89° 46' 26" East on North Boundary of Sec
2. Town 5 North Range 32 East,
Variation 21° East.

4000 Set 1/4 Sec Post on East side of
Ridge Drove Charred Post
Dug Pitt, raised mound
as per instructions

Township 5 North Range 32 East.
8000 Set Post Corner for Secs 1, 2, 35
& 36, on High Hill sloping to
the West. Land Broken. Grass
good. Soil 2^o Pat. Wrote
Chained Stake, Dug Pitt,
raised Mound as Per Instructions.

S. 89° 46' 26" East on North Boundary of Sec 1.
Township 5 North Range 32 East.
Variation 20° 45' East.

HC. 11 Set 4 Sec Post on High Hill
sloping to the East. Wrote Chained
Stake Dug Pitt, raised
Mound as Per Instructions.

8000 Set Post Corner for Townships 5 & 6
North. Ranges 32 & 33. East.
Secs 1, 6, 36 & 37.
Land Broken. Grass good
Soil 2^o Pat

For general remarks
 for this Township see
 General remarks after the
 field notes for the subdivis-
 -ional lines,

The foregoing exterior
 lines were surveyed by
 Deputy W. H. Odell, assisted
 by Walter W. Johnson Comptroller
 C. C. Harcum } Chairman
 J. Shibles }
 William Warren Assessor

624

Surveyor General's Office
Eugene City, Aug. 23^d 1865

The foregoing field notes of the Survey of the Exterior
lines of ~~Tps. 4 N. R. 31, 32, 33, & 4 East; and of~~
Tps 5 N. Ranges 31, 32 and 36 East; and of
Tps 6 N. Ranges 34, 35 and 36 East, Will. Mer,
Oregon, Executed by Odell and Lewis under contract
No. 110 bearing date February 7th 1865, having
been critically examined, the necessary explanations
and corrections made, the said field notes and
the surveys they describe are hereby approved.

E. L. Applegate
Surveyor General.