

6232

Field notes of the Survey of
the Subdivisional lines of Twp. Township
No. 6, North of the Base line
of Range No. 32 East of the
Willamette Meridian. Executed
by Nicholas O. Walden, Deputy
Surveyor, under his Contract
No. 209, bearing date the 6th
day of July 1874.

Commenced Nov. 20th 1874

Completed Nov. 23rd 1874.

R. P. Earhart

239238

240

Index:

Referring the lines to the pages in the Fieldnotes

6	5	4	3	2	1
7	8	9	10	11	12

State Boundary lines:

18	21	17	15	16	12	15	8	14	5	13	
20		19		15		11		8		4	
19	19	20	14	21	11	22	7	23	3	24	4
18		18		14		10		7			
30	17	29	13	28	10	27	6	26	2	25	2
17		16		13		9		6		1	
31	16	32	12	33	9	34	5	35	1	36	

24 Subdivisional lines of Township 6

North ~~On random line~~ between Sects 13 & 14.

Var $21^{\circ}00' E$

4000 Set Basalt Stone $12 \times 10 \times 6$ 7 in
in ground for $\frac{1}{4}$ Sec corner

40.43 Intersect Boundary line between
Oregon and Washington Territory
60 y lks west of 10 mile corner

Set Basalt Stone $18 \times 10 \times 9.9$ in
in ground for closing corner to
Tr Sects 13 & 14.

Land slopes gently to north
Soil good.

Nov 20th 1874.

North between Sects 34 & 35

4000 Deposit Basalt Stone $5 \times 4 \times 3$
marked with a cross (+) and raised
mound of earth with pits etc as
pr instructions for $\frac{1}{4}$ Sec corner

8000 Set Basalt Stone $14 \times 12 \times 5$ 7 in
in ground for corner to Sects
26. 27. 34 & 35

Land gently rolling. Soil good.

of Range 32 East Will Mer Oregon 248

East On random line between Sec 14 & 23.
 4000 Set temporary 1/4 Sec corner
 8030 Intersect N & S line at corner
 West On true line.
 4025 Drove charred stakes and raised mound
 of earth with pits etc as per instructions + 50
 4600 Wagon road in ravine ^{for 1/4 Sec cor.} Course West - 50
 8030 The corner
 Land hilly sloping to ravine
 Soil 2^d rate. good grass

North between Sec 14 & 15
 Var 22° 00' East

4000 Set Basalt Stone 16 x 8 x 6.8.
 in in ground for 1/4 Sec corner
 4042 Intersect Boundary line between
 Oregon and Washington Territory 697.
 the west of 9. mile corner in
 canyon running West.
 Set Basalt Stone 18 x 14 x 12 for 9.
 in in ground for Closing Cor to Jr. Secs
 14 & 15
 Land hilly Soil 2^d rate

North of Range 32 East Will. Mex.

North between Sect 15 & 16.

Var 22° 30' East

4000 Interest boundary line between Oregon and Washington Territory 80y lks west of 8 mile corner.

Drove charred Stake and raised mound of earth with pits etc for closing corner to fr. Sect 15 & 16.

Drove pine Stake 2ft long 2 in square in E pit.

Land gently rolling Soil good good grass

North between Sect 32 & 33.

4000 Drove charred Stake and raised mound of earth with pits etc as per instructions for 1/4 Sec corner

8000 Drove charred Stake and raised mound of earth with pits etc as per instructions for Corner to Sect 28 29 32 & 33.

Drove Willow Stake 2ft long 2 in square in LC pit.

Land rolling Soil 1st rate good grass

Subdivisional lines of Township No 6

255

East An random line between Sec 16 & 21.

4000 Set temporary $\frac{1}{4}$ Sec corner8085 Intersect R & S line 21 lbs north of Sec
N 89° 51' W. on true line:4042 Drove charred Stake and raised
mound of earth with pits etc as
per instructions for $\frac{1}{4}$ Sec corner8083 The corner
Land rolling. Soil good. Good grass

North between Sec 16 & 17.

Var 21° 30' East

39.69 Intersect Boundary line between
Oregon and Washington Territory928 lbs West of $\frac{1}{4}$ mile corner
Set Basalt Stone 18, 10, 8 for
closing corner to Tr. Sec 16 & 17. - 100
Land rolling Soil good.Nov 22^d 1874.

Subdivisional lines of Township

North between Sec 17 & 18
 ran $21^{\circ}30'$ East

4000 Intersect Boundary line between
 Oregon and Washington Territory
 1032 lks. West of 6 Mile Corner
 Drove charred Stakes and raised
 mound of earth with pits etc
 as per instructions for closing
 corner to fractional Sec 18 & 19.
 Drove pine Stakes 2 ft long
 2 in square in East pit.

Land gently rolling. Soil 1st rate
 Good grass
 Nov. 23rd 1874.

6. North Range 32 East of Will. No. 2

General Description

The land in this fr. Township is generally rolling prairie, covered with good bunchgrass. The Soil is generally good sandy loam suitable for agricultural and grazing purposes. There is no timber and no water in the Township.

List of Names

A list of the names of the individuals employed to assist in running measuring and marking the lines and corners described in the foregoing field notes of the Subdivisional lines of Fractional Township No. 6 North of the base line of Range No. 32 East of the

263

Willamette Meridian, showing the
respective capacities in which they
acted)

Rufus L. Moore Chairman
Henry Meldrum Chairman
William H. Cooper Assn

281

We hereby certify that we assisted
 Nicholas O Walden, Deputy Surveyor, in
 Surveying the Subdivisional lines of Trac-
 tionab Township N^o 6 North of Range 32
 East of Willamette Meridian in the capa-
 cities indicated by our respective signatures
 and that said fractional Township has
 been in all respects to the best of our
 knowledge and belief well and faithfully
 Surveyed and the boundary monuments
 started according to the instructions
 furnished by the Surveyor General

R. J. Moore Chairman

Henry Meldrum Chairman

William, H. Cooper Assman

Subscribed and sworn to before me
 a Notary public this the 12th day
 of December 1874.

John W. Meldrum
 Notary Public

John W. Meldrum

265

I Nicholas O Walden Deputy Surveyor, do solemnly swear that in pursuance of a contract with Benjamin Simpson U S Surveyor General for the State of Oregon bearing date the 6th day of July 1874. and in strict conformity to the laws of United States and the instructions furnished by the said Surveyor General I have faithfully surveyed the Subdivisional lines of Fractional Township No 6 North of the base line of Range No 32 East of the Willamette Meridian in the State aforesaid, and do further solemnly swear that the foregoing are the true and original fieldnotes of such survey.

Nicholas O Walden

Deputy Surveyor

Subscribed and sworn to by the above named Nicholas O Walden, Deputy Surveyor this 19th day of March

1875.

John W. Melanum
Notary Public

my of

266

U.S. Surveyor General's Office
Portland Oregon June 23rd 75

The foregoing field notes of the survey of the subdivisional
lines of N. W. R. 32 East Mill New Oregon executed by
Nicholas A. Walden D. S. under contract No 209 ^{bearing date 6th July 1874} having
been critically examined the necessary corrections
and explanations made the said field notes and the
survey they describe are hereby approved

Ben Simpson
Assistant of