

6232

Field notes of the Survey of
the Subdivisional lines of Twp. Township
No. 6, North of the Base line
of Range No. 32 East of the
Willamette Meridian. Executed
by Nicholas O. Walden, Deputy
Surveyor, under his Contract
No. 209, bearing date the 6th
day of July 1874.

Commenced Nov. 20th 1874

Completed Nov. 23rd 1874.

R. P. Earhart

239238

240

Index:

Referring the lines to the pages in the Fieldnotes

6	5	4	3	2	1						
7	8	9	10	11	12						
<i>State Boundary lines:</i>											
18	21	17	15	16	12	15	8	14	5	13	
20		19		15		11		8		4	
19	19	20	14	21	11	22	7	23	3	24	4
18		18		14		10		7			
30	17	29	13	28	10	27	6	26	2	25	2
17		16		13		9		6		1	
31	16	32	12	33	9	34	5	35	1	36	

241 Subdivisional lines of T. N^o 6. North

From the established corner to
Sec 35 & 36 on South bound of the
Township I run:

North between Sec 35 & 36.

4000 Deposit Basalt Stone $6 \times 4 \times 3$ marked
with a cross (+) and raised mound of
earth with pits etc as per instructions
for $\frac{1}{4}$ Sec corner

8000 Set Basalt Stone $15 \times 10 \times 6.8$ in
in ground for corner to Sec 25, 26, 35 & 36.
Land gently rolling Soil good
good grass.

East On random line between Sec 25 & 36.

4000 Set temporary $\frac{1}{4}$ Sec corner

8040 Intersect E. boundary of Township 40
1/2 mi South of the corner

S. 89° 33' W. On true line

4020 Set Basalt Stone $18 \times 09 \times 6.9$ in in
ground for $\frac{1}{4}$ Sec corner

8040 The corners

Land rolling. Soil good good grass.

of R N^o 32 East Will. Mer. Oregon 242

North between Secs 25 & 26.

Var 22° 30' E.

4000 Set Basalt Stone 15 x 9 x 7. 8 in - 50
in ground for 1/4 Sec corner

8000 Set Basalt Stone 14 x 10 x 6 7/8 in - 75
in ground for corner to Secs 23 24 25 & 26.

Land rolling Soil good
Good grass.

East An random line between Secs 24 & 25

4000 Set temporary 1/4 Sec corner

8000 Intersect East boundary of Townsh.

129 Ws South of the corner.

This intersection not being within
the limits required by the instructions
I retraced this line and the line
between Secs 25 & 26: and 25 & 36 finding
no error I therefore begin at corner
to Secs 25 & 36. on east boundary
of Township and run:

North on east boundary of Sec 25.

1000 Wagon road in ravine Course NW - 200

4050 1/4 Sec Corner + 200

8085 A point 80 lbs East of corner to

243 Subdivisional lines of Township C. North

Sec 24 & 25.

+ 150

Finding that the length of this line nearly corresponds to the close of my line between Sec 24 & 25 I therefore run:

- 389°05' W. on tree line between Sec 24 & 25
 4000 Set Basalt Stone 18 x 8 x 6.9 in
 ' in ground for 1/4 Sec corner
 7000 Wagon road in ravine course N W
 ' S E.
 8000 The corner
 ' Land hilly Soil good

North between Sec 23 & 24.

Var 21° 30' E.

- 2300 Wagon road in ravine course N W,
 ' S E.
 4000 Set Basalt Stone 14 x 10 x 8.7 in in
 ' ground for 1/4 Sec corner + 125
 8000 Set Basalt Stone 12 x 8 x 6.7 in in
 ' ground for corner to Secs 13, 14, 23, & 24. + 125
 Land hilly Soil 2^d rate
 Good grass

Range 32 East Will Mer Oregon ⁴ 244

East between Secs 13 & 24.

4000 Set temporary 1/4 Sec corner

7815 Intersect East boundary of Townsh.

212 lbs South of the corner

This intersection not being within the limits required by the instructions I retraced this line and the line between Secs 23, 24, 24 & 25 and finding no error I therefore begin at corner to Secs 24 & 25 on east boundary of Township and run

North on east boundary of Sec 24.

4047 A point 61 lbs East of 1/4 Sec cor

8066 A point 172 lbs East of corner to Secs 13 & 24.

Finding that the length and bearing of this line nearly corresponds to the close of my line between Secs 13 & 24 I therefore run:

18829 W. On true line bet. Secs 13 & 24.

39.07 Set Basalt Stone 13 x 10 x 9.8 in in ground for 1/4 Sec corner + 40

78.15 The corner - 100

Land rolling Soil good

24 Subdivisional lines of Township 6

North ~~On random line~~ between Sects 13 & 14.

Var $21^{\circ}00' E$

4000 Set Basalt Stone $12 \times 10 \times 6$ 7 in
in ground for $\frac{1}{4}$ Sec corner

40.43 Intersect Boundary line between
Oregon and Washington Territory
60 y lks west of 10 mile corner

Set Basalt Stone $18 \times 10 \times 9.9$ in
in ground for closing corner to
Tr Sects 13 & 14.

Land slopes gently to north
Soil good.

Nov 20th 1874.

North between Sects 34 & 35

4000 Deposit Basalt Stone $5 \times 4 \times 3$
marked with a cross (+) and raised
mound of earth with pits etc as
pr instructions for $\frac{1}{4}$ Sec corner

8000 Set Basalt Stone $14 \times 12 \times 5$ 7 in
in ground for corner to Sects
26. 27. 34 & 35

Land gently rolling. Soil good.

North R 32 East Will Mer Or 246⁶

East An random line between Secs 26 & 35
4000 Set temporary 1/4 Sec corner
8090 Intersect A & I line 35 Ws
South of corner

8945' W On true line

4045 Deposit Basalt Stone 3x4x4.
marked with a cross (+) and raised
mound of earth with pits etc as
per instructions for 1/4 Sec corner

8090 The corner

Land gently rolling Soil good

North between Sec 26 & 27

Var 21° 00' East

4000 Deposit Basalt Stone 3x4x2 marked
with a cross and raised mound of
earth with pits etc as per instructions
for 1/4 Sec corner

8000 Drove Charred Stakes and raised
mound of earth with pits etc
as per instruction for corner to Secs

22, 23, 26 & 27. Drove pine Stakes 2ft - 30.
long 2in square pine E. pil.
Land gently rolling Soil good

Subdivisional lines of Township 6 North

East On random line between Sec 23 & 26

4000 Set temporary 1/4 Sec corner

8025 Intersect. of Line 30 Ws South
of Corner

8947 1/2 on true line

4012 Drove charred Stake and raised
Mound of earth with pits etc as per
instructions for 1/4 Sec corner

8025 The corner

Land gently rolling Soil good

North between Sec 22 & 33

Var $21^{\circ} 30' E$.

4000 Drove charred Stake and raised mound
of earth with pits etc as per instructions
for 1/4 Sec corner

8000 Drove charred Stake and raised
mound of earth with pits etc
as per instructions for corner to
Sec 14, 15, 22 & 23.

Drove pine Stake 2ft long 2in
square in I & E pit

Land gently rolling. Soil good

of Range 32 East Will Mer Oregon 248

East On random line between Sec 14 & 23.
 4000 Set temporary 1/4 Sec corner
 8030 Intersect N & S line at corner
 West On true line.
 4025 Drove charred stakes and raised mound
 of earth with pits etc as per instructions + 50
 4600 Wagon road in ravine ^{for 1/4 Sec cor.} Course West - 50
 8030 The corner
 Land hilly sloping to ravine
 Soil 2^d rate. good grass

North between Sec 14 & 15
 Var 22° 00' East

4000 Set Basalt Stone 16 x 8 x 6.8.
 in in ground for 1/4 Sec corner
 4042 Intersect Boundary line between
 Oregon and Washington Territory 697.
 the west of 9. mile corner in
 canyon running West.
 Set Basalt Stone 18 x 14 x 12 for 9.
 in in ground for Closing Cor to Jr. Secs
 14 & 15
 Land hilly Soil 2^d rate

249
Subdivisional lines of Township C.

North between Sec 33 & 34.

4000 Drove Charred Stake and raised mound of earth with pits etc as per instructions for $\frac{1}{4}$ Sec corner

8000 Drove charred Stake and raised mound of earth with pits etc as per instructions for corner to Secs 27 28 33 & 34.

Drove Willow Stake 2 ft long 2 in square in S O pit.

Land gently rolling Soil 1st rate

East An. random line between Secs 27 & 34.

4000 Temporary $\frac{1}{4}$ Sec corner

8130 Intersected N & S line at corner

West An true line:

4065 Deposit Basalt Stone 6x5x4 and raised mound of earth with pits etc as per instructions for $\frac{1}{4}$ Sec corner

8130 The corner

Land gently rolling Soil good

Note The resurvey of the South boundary of Sec 34. Shows that line to be 8129 Ch. (See Resurvey of North bound. Sec 3, T. 5 N. R. 32 E.)

North Range 32 East Will Mer Oregon 250

North between Sec 27 & 28.

Var 22°00' East

4000 Drove charred stakes and raised mound of earth with pits etc as per instructions for 1/4 Sec corner

8000 Drove charred stakes and raised mound of earth with pits etc as per instructions for corner to Sec 21, 22, 27 & 28.

Drove pine stake 2ft long 2in square in SE pit.

Land gently rolling Soil 1/2 rate good grass. Nov 21st 1874.

East On random line between Sec 22 & 27.

4000 Set temporary 1/4 Sec corner

8100 Intersect of S line at corner

West On true line:

4050 Drove charred stakes and raised mound of earth with pits etc as per instructions for 1/4 Sec corner

8100 The corner.

Land rolling. Soil good. good grass

11

251

Subdivisional lines of Township N^o 6

North between Sect 21 & 22

Var 21° 30 East

4000 Drove charred stakes and raised mound of earth with pits etc as per instructions for 1/4 Sec corner

8000 Set Basalt Stone 15x 8x 6 8 in in ground for corner to Sect 15, 16 21 & 22.

Land gently rolling Soil good

East On random line between Sect 15 & 22

4000 Set temporary 1/4 Sec corner

8120 Intersect N. & E. line 20 Wks N of cor.

N 89° 51' W On true line.

40.60 Drove charred stakes and raised mound of earth with pits etc as per instructions for 1/4 Sec corner

8120 The corner

Land rolling Soil good
Good grass

North of Range 32 East Will. Mex.

North between Sect 15 & 16.

Var 22° 30' East

4000 Interest boundary line between Oregon and Washington Territory 80y lbs west of 8 mile corner.

Drove charred Stake and raised mound of earth with pits etc for closing corner to fr. Sect 15 & 16.

Drove pine Stake 2ft long 2 in square in E pit.

Land gently rolling Soil good good grass

North between Sect 32 & 33.

4000 Drove charred Stake and raised mound of earth with pits etc as per instructions for 1/4 Sec corner

8000 Drove charred Stake and raised mound of earth with pits etc as per instructions for Corner to Sect 28 29 32 & 33.

Drove Willow Stake 2ft long 2 in square in LC pit.

Land rolling Soil 1st rate good grass

Subdivisional lines of Township No 6
-253

East On random line between Sect 28 & 33

4000 Set temporary $\frac{1}{4}$ Sec corner

8080 Intersect of S line 12 lbs South
of the corner

18935 W On true line:

4040 Drove charred Stake and raised
mound of earth with pits etc
as per instructions for $\frac{1}{4}$ Sec corner

8080 The corner

Land gently rolling Soil 1st rate Good grass

North between Sect 28 & 29.

Var $19^{\circ} 45'$ East

4000 Drove charred Stake and raised
mound of earth with pits etc
as per instructions for $\frac{1}{4}$ Sec corner

8000 Drove charred Stake and raised
mound of earth with pits etc
as per instructions for corner to
Sect - 20. 21. 28 & 29.

Drove pine Stake 2ft long 2in
square in S E pit.

Land rolling Soil 1st rate Good grass

North Range 32 East Will Mer Oregon
254

East On random line bet Sec 21 & 28.

4000 Set temporary 1/4 Sec corner

8000 Intersect at corner

West On true line:

4000 Drove charred Stake and raised mound of earth with pits etc as per instructions for 1/4 Sec corner

8000 The corner

Land rolling Soil good

North between Sec 20 & 21.

Var 21° 30' E.

4000 Drove charred stake and raised mound of earth with pits etc as per instructions for 1/4 Sec corner

8000 Drove charred Stake and raised mound of earth with pits etc as per instructions for corner to Sec 16 17 20 & 21.

Drove pine Stake 2ft long 2in square in I C pit

Land gently rolling Soil 1st rate

Subdivisional lines of Township No 6

255

East An random line between Sec 16 & 21.

4000 Set temporary $\frac{1}{4}$ Sec corner8085 Intersect R & S line 21 lbs north of Sec
N 89° 51' W. on true line:4042 Drove charred Stake and raised
mound of earth with pits etc as
per instructions for $\frac{1}{4}$ Sec corner8083 The corner
Land rolling. Soil good. Good grass

North between Sec 16 & 17.

Var 21° 30' East

39.69 Intersect Boundary line between
Oregon and Washington Territory928 lbs West of $\frac{1}{4}$ mile corner
Set Basalt Stone 18, 10, 8 for
closing corner to Tr. Sec 16 & 17. - 100
Land rolling Soil good.Nov 22^d 1874.

North Range 32 East Will Mer Oregon
256

North between Sec 31 & 32

4000 Drove charred Stake and raised mound of earth with pits etc as per instructions for 1/4 Sec Cor

8000 Drove Charred Stake and raised mound of earth with pits etc as per instructions for corner to Sec 29, 30, 31 & 32

Drove Willow Stake 2ft long 2 in square in SE pit.

Land rolling Soil good good grass

East on random line between Sec 29 & 32

4000 Set temporary 1/4 Sec corner

8070 Intersect of S line at corner

West On true line

4035 Drove charred Stake and raised mound of earth with pits etc as per instructions for 1/4 Sec corner

8070 The corner

Land rolling Soil 1st rate
Good grass

257 Subdivisional lines of Township No 6

West On random line between Sec 30 & 31.
 4000 Set temporary 1/4 Sec corner
 8083 Intersect West boundary of Townsh.
 35 W's South of the corner

S 89° 45' E. On true line:

4083 Drove charred Stake and raised
 mound of earth with pits etc.
 as pr instructions for 1/4 Sec cor.

8083 The corner

Land rolling Soil good Good grass

North between Sec 29 & 30.

Var 21° 30' E.

4000 Drove charred Stake and raised
 mound of earth with pits etc.
 as pr instructions for 1/4 Sec corner

8000 Drove Charred Stake and raised
 mound of earth with pits etc.
 as pr instructions for corner to
 Sec 19, 20, 29 & 30

Drove pine Stake 2ft long 2in
 square in I C pit

Land rolling Soil good Good grass

North Range. 32 East Will Mer. 258

East on random line between Sec 20 & 29.

4000 Set temporary 1/4 Sec corner

8090 Intersect N & S line 25 lbs South
of corner

S 89° 49' W on true line

4045 Drove charred Stake and raised
mound of earth with pits etc
as per instructions for 1/4 Sec Cor.

8090 The corner

Land rolling Soil good. good grass

West on random line between Sec 19 & 30

4000 Set temporary 1/4 Sec corner

8040 Intersect West boundary 32 lbs
South of the corner.

S 89° 44' E On true line

4040 Drove charred Stake and raised

mound of earth with pits etc
as per instructions for 1/4 Sec corner

8040 The corner

Land rolling Soil 1st rate good grass

Subdivisional lines of Township No 6.

North between Sec 19 & 20,

Var 21° 30' East

4000 Drove charred Stake and raised mound of earth with pits etc as per instructions for 1/4 Sec corner

8000 Drove charred Stake and raised mound of earth with pits etc as per instructions for corner to Sec 17, 18, 19 & 20

Drove pine Stake 2ft long 2 in square in I.C. pit.

Land gently rolling Soil 1st rate
Good grass

East On random line between Sec 17 & 20

4000 Set temporary 1/4 Sec corner

8080 Intersect N & S line 16 lbs

South of the corner

18953' W. on true line,

4040 Drove charred Stake and raised

mound of earth with pits etc as per instructions for 1/4 Sec cor

North Range 32 East Will Mes 260

20

80.80 The corner
Land gently rolling Soil good

West On random line between Secs
18 & 19.

4000 Set temporary $\frac{1}{4}$ Sec corner

79.30 Intersect West boundary 126.
Wks South of corner

$S 89^{\circ} 06' E$. on true line

39.50 Drove charred stake and raised
mound of earth with pits etc.
as per instructions for $\frac{1}{4}$ Sec cor.

79.50 The corner

Land rolling. Soil good. Good grass

Note: The West boundary of Sec 19 is
80.94 Chs in length and bears 60
Wks East of North. (See resurvey
of east boundary Sec 24. page 5
Subdivisions of T. 6 N. R. 31 E.)

261 Subdivisional lines of Township

North between Sec 17 & 18
 ran $21^{\circ}30'$ East

4000 Intersect Boundary line between
 Oregon and Washington Territory
 1032 lks. West of 6 Mile Corner
 Drove charred Stakes and raised
 mound of earth with pits etc
 as per instructions for closing
 corner to fractional Sec 18 & 19.
 Drove pine Stakes 2 ft long
 2 in square in East pit.

Land gently rolling. Soil 1st rate
 Good grass
 Nov. 23rd 1874.

6. North Range 32 East of Will. No. 2

General Description

The land in this fr. Township is generally rolling prairie, covered with good bunchgrass. The Soil is generally good sandy loam suitable for agricultural and grazing purposes. There is no timber and no water in the Township.

List of Names

A list of the names of the individuals employed to assist in running measuring and marking the lines and corners described in the foregoing field notes of the Subdivisional lines of Fractional Township No. 6 North of the base line of Range No. 32 East of the

263

Willamette Meridian, showing the
respective capacities in which they
acted)

Rufus L. Moore Chairman
Henry Meldrum Chairman
William H. Cooper Assn

We hereby certify that we assisted
 Nicholas O Walden, Deputy Surveyor, in
 Surveying the Subdivisional lines of Trac-
 tioned Township No 6 North of Range 32
 East of Willamette Meridian in the capa-
 cities indicated by our respective signatures
 and that said fractional Township has
 been in all respects to the best of our
 knowledge and belief well and faithfully
 Surveyed and the boundary monuments
 started according to the instructions
 furnished by the Surveyor General

R. J. Moore Chairman

Henry Meldrum Chairman

William, H. Cooper Assman

Subscribed and sworn to before me

a Notary public this the 12th day
 of December 1874.

John W. Meldrum
 Notary Public

Meldrum
 John W.

265

I Nicholas O Walden Deputy Surveyor, do solemnly swear that in pursuance of a contract with Benjamin Simpson U S Surveyor General for the State of Oregon bearing date the 6th day of July 1874. and in strict conformity to the laws of United States and the instructions furnished by the said Surveyor General I have faithfully surveyed the Subdivisional lines of Fractional Township No 6 North of the base line of Range No 32 East of the Willamette Meridian in the State aforesaid, and do further solemnly swear that the foregoing are the true and original fieldnotes of such survey.

Nicholas O Walden

Deputy Surveyor

Subscribed and sworn to by the above named Nicholas O Walden, Deputy Surveyor this 19th day of March

1875.

John W. Melanum
Notary Public

my of

266

U.S. Surveyor General's Office
Portland Oregon June 23rd 75

The foregoing field notes of the survey of the subdivisional
lines of N. W. R. 32 East Mill New Oregon executed by
Nicholas A. Walden D. S. under contract No 209 ^{bearing date 6th July 1874} having
been critically examined the necessary corrections
and explanations made the said field notes and the
survey they describe are hereby approved

Ben Simpson
Assistant of