

North, Range No. 31 East - Will. Mer. Oregon

required by the instructions I retrace this line and the line between Secs. 35 & 36 and find no error.

I therefore begin at the corner to Townships 5 & 6 North, Ranges 31 & 32 East and run thence

North on a blank line along the East boundary of Sec. 36
T 6 N. R. 31 E.

40.46 The 1/4 Sec. Cor.

81.44 The corner to Secs. 25 & 36

Note The South boundary of Sec. 36 in this Township is 80.86 chains in length and has a bearing to the South of West 58 lbs. (See field notes of Resurvey of Exterior Boundaries of T. 5 N. R. 31 E.) therefore

88° 34' W. on true line between Secs 25 & 36

49.50 Drove charred stake and raised mound of earth with pits &c as per instructions for 1/4 Sec. Cor.

- 100

81.00 The Corner to Secs. 25, 26, 35 & 36

- 150

Land hilly Soil good

Subdivisional lines of Frac. Township No. 6

North between Secs. 25 + 26

Var. $21^{\circ}30'$ East -

40.00 Drove charred stake and raised mound
of earth with pits &c as per instruc-
tions for $\frac{1}{4}$ Sec. Cor. + 100

80.00 Drove charred stake and raised mound
of earth with pits &c as per instruc-
tions for corner to Secs. 23, 24, 25 + 26 + 30

Drove Pine Stake 2 ft long 2 in
square in S.E. pit.

Sand rolling; Soil good.

East on random line between Secs. 24 + 25 -

40.00 Set temporary $\frac{1}{4}$ Sec. Cor.

81.60 Intersect East Boundary of Township
278 lbs. South of the corner.

$88^{\circ}01'$ W. on true line

40.80 Drove charred stake and raised mound
of earth with pits &c. as per in-
structions for $\frac{1}{4}$ Sec. Cor.

81.60 The corner.

Sand rolling; Soil 1st rat.

North Range No. 31 East Will. Mer. Oregon

North between Secs. 23 + 24,

Var. $21^{\circ} 30'$ East -

40.00 Drove Churred Stake and raised mound of earth with pits &c. as per instructions for $\frac{1}{4}$ Sec. Cor.

80.00 Drove Churred Stake and raised mound of earth with pits &c. as per instructions for corner to Secs. 13, 14, 23 + 24

Drove Pine Stake 2 ft. long 2 in square in S.E. pit -

Sand rolling; Soil 1st rate.

Nov 12th 1874.

East on random line between Secs. 13 + 24

40.00 Set temporary $\frac{1}{4}$ Sec. Corner.

82.00 Intersect East Boundary of Township

346 lbs. South of the Corner.

This close being out of the required limits and finding no error in my own work I began at the corner to Secs.

25 + 26 in the East Boundary of the Township and run North on the East boundary of Secs. 25, 24 + 13 as follows.

155

Subdivisional Lines of Tract Township No. 6

North on a blank line along the East boundary of Sec 25

40.46 The $\frac{1}{4}$ Sec. Corner80.00 A Point 66 lbs West and 90 lbs South of
the corner to Secs. 24 + 25

Continuing on same line

North on a blank line along the E. boundary of Sec. 24

40.47 A point 103 lbs West of the $\frac{1}{4}$ Sec. Cor.80.00 A point 126 lbs West and 184 lbs. South
of the corner to Secs. 13 + 24

This result very nearly corresponding
with the close, as above I conclude
that - it is right. Therefore,

887°31' W. on true line between Secs. 13 + 24

41.00 Drove sharpened stake and raised mound
of earth with spade &c, as per instruc-
tions for $\frac{1}{4}$ Sec. Cor.

82.00 The corner

Soand rolling;

Soil $\frac{1}{2}$ rot.

List of Names

A list of the names of the individuals employed to assist in running measuring or marking the lines and corners described in the foregoing field notes of the Survey of the Subdivisional lines of Gerald Township No. 6 North of the Base line of Range No. 31 East of the Willamette Meridian showing the respective capacities in which they acted;

Rufus S. Moore	Chainman
J. Henry Meldrum	Chainman
William H. Cooper	Assessor

183

We hereby certify that we assisted
Nicholas O. Walden, Deputy Surveyor, in
surveying the subdivisional lines of Tract,
Township No. 6 North of the base line
of Range No. 31 East of the Willamette
Meridian in the capacities indicated by
our respective signatures, and that
said fractional Township has been in
all respects to the best of our knowledge
and belief well and faithfully survey-
ed and the boundary monuments plant-
ed according to the instructions furnished
by the Surveyor General

Henry Meldrum Chairman
Rufus S. Moore Chairman
William H. Cooper Chairman

Subscribed and sworn to before me a

Notary Public this 12th day of Dec. 1874

John W. Meldrum

Notary Public.

W. H. Meldrum
Notary Public

I, Nicholas O. Walden, Deputy Surveyor do solemnly swear that in pursuance of a contract with Benjamin Simpson U. S. Surveyor General for the State of Oregon bearing date the 6th day of July 1874, and in strict conformity to the laws of the United States and the instructions furnished by the said Surveyor General, I have faithfully surveyed the subdivision and boundary lines of Frazer Township No. 6 North of the base line of Range No. 31 East of the Willamette Meridian in the State aforesaid and do further solemnly swear that the foregoing are the true and original field notes of such such Survey.

Nicholas O. Walden

Deputy Surveyor

Subscribed and sworn to by the above named Nicholas O. Walden Deputy Surveyor on this the 12th day of December 1874

John W. Meldrum
Notary Public

W. Meldrum

NOTARY PUBLIC
WILLAMETTE COUNTY
OREGON

U S Surveyor Generals Office
Portland Oregon June 25 1875

The foregoing field notes of the survey of the subdivisional lines of Township 6 North Range
3 East Willamette Meridian Oregon executed by N. O. Walden D. S. under Contract
No 209 bearing date July 6 1874 having been critically examined the necessary
corrections and explanations made the said field notes and the surveys they
describe are hereby approved

Ben Simpson
Sur Genl of Oregon