

1 5

Field Notes of the Sub-divisional  
Lines for Townships 6 North of  
Ranges 33, 34 & 35 East of Willamette  
Meridian, made under contract  
No. 110, bearing date, February  
7<sup>th</sup> 1865.

79<sup>85</sup>

Township 6 N, Range 33 East Will, Mer,  
Land rolling, grass, good,  
Soil 2<sup>nd</sup> rate,

North between sections 134 & 14,  
Township 6 N, Range 33 East,  
Variation 20° 30' East,  
12,00 Trail or road course W,  
40,00 Set  $\frac{1}{4}$  section post corner  
Drove charred stake, dug pits,  
and raised mound as per  
instructions.  
5-3,10 To State boundary 9,45 ch  
West of 16<sup>th</sup> Mile post  
Set post corner for fractional  
Sections 134 & 14, Township 6 N  
Range 33 E, Drove charred stake,  
dug pits and raised mound  
as per instructions  
Land gently rolling,  
Good grass. Soil 2<sup>nd</sup> rate,

Township No 6 N. Range 33 E. Will. Mer,  
Tenn

S 89° 51' W on town line

40,37 Set post corner for 1/4 section  
Drove charred stake dug  
pits and raised mound  
as per instructions

80,75 To post corner  
Land gently rolling  
Soil 2<sup>nd</sup> (date)

North between sections 14 & 15

Township 6 N R 33 East

Over 21° East

36,00 True course West,

40,00 Set 1/4 section post corner

Drove charred stake dug  
pits and raised mound  
as per instructions.

52,94 To Northern boundary

line of Oregon, 9.93 chs

West of the 15<sup>th</sup> Will post,

Township 6 N. R. 33 East Will. Mer,  
Set post Drove charred stake  
dug pits and raised mound  
as per instructions  
Sand rolling Soil 2<sup>d</sup> Rate

North between sections 33 & 34  
Township 6 N. R. 33 E. Will. Mer

40,00 Set  $\frac{1}{4}$  section post corner  
Drove charred stake, dug pits  
and raised mound as per  
instructions.

80,00 Set a post corner for  
sections 27, 28, 33 & 34, Drove  
Charred stake dug pits  
and raised mounds as per  
instructions

Sand broken Soil 2<sup>d</sup> Rate

East on Burdorn between  
Sections 27 & 34 T. 6 N. R. 33. East,

Township 6 N, Range 33 East Mill, Mo,

East on Random between sections

15 & 22, Township 6 N, R. 33 East

40,00 Set temporary  $\frac{1}{4}$  Section post

80,00 Intersect N 73 Line 3' 5" S

Post of Post from which I run

N 89° 45' West on true line

40,00 Set  $\frac{1}{4}$  Section post corner

on East side of Gully, Drive  
churned stake, Dig pit, and  
raised mound as per instructions

80,00 To Post corner,

This line passes over a  
succession of ridges

found quite broken

Soil 2<sup>nd</sup> rate

North between sections

15 & 16, Township 6 N, R. 33 E,

Variation 18° 30' East

40,00 Set  $\frac{1}{4}$  Section post corner,

94

90

Township 6 N, Range 33 East Will. Mer,  
Drove charred Stake dug  
pits and raised mound as  
per instructions,

52,50 To State Boundary Line

9.09 West of Mile post  
No. 14,

Set post corner for sections  
15 & 16, Drove charred stake,  
dug pits and raised  
mound as per instructions

Land broken

Soil 2<sup>nd</sup> Rate,

North between sections 32 & 33

Township 6 N, R33 East,

4000 Set 4 Section post, corner  
Drove charred Stake, dug  
pits and raised mound  
as per instructions,

8000 Set post corner for sec

28, 29, 32 & 33, Drove charred

95 99

Township 6 N. Range 33 East Will. Mer,

North between sections 16 & 17  
Township 6 N. R33 E  
\* Bar 21° E

40,00 Set  $\frac{1}{4}$  section post corner  
Drove charred stake, dug  
pits and raised mound as  
per instructions,

52,79 To North boundary of State  
2.55 miles west of mile post  
No 134

Set post corner for sections  
16 & 17, Drove charred stake,  
dug pits and raised mound  
as per instructions  
Lured Baker  
Soil 2<sup>nd</sup> rate,

North between sections 81 & 82,  
Township 6 N. Range 33 East,  
40,00 Set  $\frac{1}{4}$  section post corner, too

Township 6 N, Range 33 East Will, Mer,  
Drove charred stake, dug pits,  
and raised mound as per  
instructions

1978 To Post Corner

Land rolling, Soil 2<sup>nd</sup> rate,

---

West on random between section  
18 & 19, Township 6 N. Range 33 East,

40,00 Set  $\frac{1}{4}$  section post, corner temporary

7924 Intersect N.W. Line 65 lbs

North of Post, from which  
Down N.  $89^{\circ}32'$  E, on true line

3924 Set  $\frac{1}{4}$  section post, Drove charred  
stake, dug pits and raised  
mound as per instructions

7924 To Post Corner

Land rolling

Good grass

Soil 2<sup>nd</sup> rate,

---

North between sections 18 & 19  
Township 6 N, Range 33 East



Y 102

Township 6 N, Range 33 East T11, Mer,  
Variation 21° 8.

40.00 Set  $\frac{1}{4}$  section post corner  
Drove charred stake,

dug pit & raised  
ground as per instructions

52.00 To State line 8.98 chs

West of B. & O., No. 12

Set post corner  
for sections 17 & 18

Drove charred stake  
dug pit and raised  
ground as per  
instructions,

Sand broken

Soil 2<sup>nd</sup> rate,

but it is not far to water to  
 the North, the Walla River  
 runs nearly parallel with the  
 State line about 1 mile distant.

I William H. Odell, do hereby  
 certify that the foregoing are the  
 true and original field notes  
 of the survey of the subdivisional  
 lines of Township No. 6 N., Range, 38 E,  
 as made under contract No. 110  
 bearing date February 7<sup>th</sup> 1863,  
 as will appear from Affidavit  
 duly made out at the close of  
 said Contract and attached  
 to the field notes for the Exterior  
 lines of T. 6 N., R. 37 E., Will Mes,  
 William H. Odell  
 Deputy Surveyor

Surveyor General's Office  
Eugene City. 1865

The foregoing field notes of the survey of Subdivis-  
ional lines of Township 6 North Range 33 East  
Willamette Meridian, Oregon, executed by Odell & Lewis  
Deputy Surveyors, under their contract No. 110, dated  
Feb. 7, 1865, having been critically examined, the  
necessary explanations and corrections made, the said  
field notes and the surveys they describe are hereby  
approved.

Surveyor General of Oregon