

Field Notes of the Survey of  
the Subdivisional lines of Township  
No 6 North of the base line  
of Range No 39 East of the  
Willamette Meridian Executed  
by Nicholas O. Walden, Deputy  
Surveyor, under his Contract No  
209 bearing date the 6<sup>th</sup> day  
of July 1874  
Commenced Nov 24<sup>th</sup> 1874  
Completed Nov 28<sup>th</sup> 1874.

Enhart

Index

Referring the lines to the pages in the fieldnotes:

T.C.N.R. 276.

6	5	4	3	2	1					
7	8	9	10	11	12					
<i>State Boundary line:</i>										
18	24.	17.	19	16	15	15	11.	14	7.	13
24.		23.		19		15		10.		6
19	23	20	19	21	14	22	10	23	6	24
22		22		18		14		9		5
30	22	29.	18	28	13.	27	9	26	5	25
21.		20				12		8.		3
31	20	32	16	33	12	34	7	35	3	36.
				17				8		4

7  
Subdivisional lines of Township No 6.

79.50 The corner  
Land gently rolling. Soil 1<sup>st</sup> rate.

North between Secs 13 & 14  
Var 21°00' East

4000 Drove Charred Stake and raised mound of earth with pits etc as per instructions for 14 Sec Cor.

65.09 Intersect Boundary line between Oregon and Washington Territory

910 Was West of the 16 Mile Corner  
Drove Charred Stake raised mound of earth with pits etc as per instructions for closing corner to fr. Sec 13 & 14

Drove pine post 2 ft long 2 in square in East pit.

Land gently rolling Soil good.

North between Secs 34 & 35

4000 Set Aspen post 4 ft long 3 in diam. Drove Charred Stake and

11

289

Subdivisional lines of Township No 6

7947 Intersect N & S line 2621 Yds  
North of the corner

N 71° 45' W On true line:

3200 Ravine course North - 75

4184 Drove charred stake and raised  
mound of earth with pits etc  
as per instructions for 1/4 Sec Cor + 75

8368 The corner  
Land gently rolling Soil good

North between Sec 14 & 15  
Var 21° 00' E.

3855 Intersect Boundary line between  
Oregon and Washington Territory  
733 Yds West of the 15 Mile  
corner Drove charred stake  
and raised mound of earth with  
pits etc. <sup>as per instructions</sup> for closing corner to foot  
Sec 14 & 15

Drove pine stake 2ft long in  
square in cut pit.

Land gently rolling Soil good

Note: Remasured the 16<sup>th</sup> mile of the

15  
285

Subdivisional lines of Township No. 6.

8000 Set Basalt Stone 16 x 9 x 7. 8 in - 200  
in ground for corner to Sec 15, 16 21 & 22  
Land rolling Soil good.

East on random line between Sec 15 & 22

4000 Set temporary 1/4 Sec corner

7924 Intersect at S line 175 Ws  
South of the corner

S 88° 45' W. On true line

3962 Set Basalt Stone 14 x 7 x 6 - 7 in  
in ground for 1/4 Sec corner + 60

7924 The corner - 100  
Land hilly Soil 2<sup>d</sup> rate  
Nov 26<sup>th</sup> 1874.

North between Sec 15 & 16. v. 21° 00' E.

4000 Drove charred stake and raised  
mound of earth with pits etc  
as per instructions for 1/4 Sec corner - 100

4050 Intersect boundary line between  
Oregon & Washington Territory  
592 Ws West of 1/4 mile corner

16.  
286

North of Range No 33 East Will Mex.

Drove charred Stake and raised mound of earth with pits etc as per instructions for closing corner to fractional Secs 15 & 16.

Drove pine Stake 2ft long 2 in square in East pit.

Note Remeasured the 15<sup>th</sup> mile on the State Boundaryline East from the 14<sup>th</sup> to the 15<sup>th</sup> mile corner and found it to be 80.50 Chs in length Land rolling sloping to North Soil D rate.

North between Secs 32 & 33.

4000 Deposited a Basalt Stone 10x8x6 marked 1/4 and raised mound of earth with pits etc as per instrum for 1/4 Sec corner + 100

8000 Set Basalt Stone 18x9x5. 9 in - 200 in ground for corner to Secs 28, 29, 32 & 33 Land hilly Soil good.

19289

Subdivisional lines of Township No. 6

North between Secs 20 & 21.

Var 21° 30' East

4000 Set Basalt Stone 15x8x5 8 in  
in ground for 1/4 Sec corner 125

8000 Set Basalt Stone 18x10x6.9 in  
in ground for corner to Sec, 16,

17, 20 & 21.

Land rolling - Soil good.

+ 50

East On random line between Sec 16 & 21.

4000 Set temporary 1/4 Sec corner

8000 Intersect R. & S. line 80 lbs  
North of the corner

N 89° 26' W. on true line

4000 Set Basalt Stone 16x9x8.8 in  
in ground for 1/4 Sec corner

8000 The corner 50  
Land hilly Soil 2<sup>d</sup> rate.

North between Secs 16 & 17.

Var 21° 30' East

3990 Intersect Boundary line between

North of Range No 33 East Will Mer.

Oregon and Washington Territory  
567 lbs west of the 13 mile corner  
Set Basalt Stone 16 x 8 x 8 8 in  
in ground for closing corner to  
fractional Sec 16 & 17.

100

Land rolling Soil 2<sup>d</sup> rate.  
Nov 27<sup>th</sup> 1874.

North between Sec 31 & 32

3350 Ravine course west

100

4000 Set Basalt Stone 12 x 10 x 5 6 in  
in ground for 1/4 Sec corner

175

8000 Set Basalt Stone 14 x 8 x 6 7 in  
in ground for corner to Sec 29,  
30 31 & 32

+60.

Land rolling Soil 1<sup>st</sup> rate.

East On random line between Sec 29 & 32

4000 Set temporary 1/4 Sec corner

8048 Intersect of R & T line 12 lbs S  
of the corner

S 89° 55' W On true line:

4024. Deposited a Basalt Stone 8 x 4 x 13

200



North of Range No 33 East Will. Mex.

4020 Set Basalt Stone 12x10x9 in  
in ground for  $\frac{1}{4}$  Sec corner

8040 The corner +100  
Land rolling Soil good

West On random line bet Sec 18 & 19

4000 Set temporary  $\frac{1}{4}$  Sec corner

8400 Intersect West boundary of Township  
200 links South of the corner

S88°34'E on true line:

4400 Set Basalt Stone 12x10x8 in

in ground for  $\frac{1}{4}$  Sec corner - 40

8400 The corner +100

Land rolling Soil 2<sup>d</sup> rate.

North between Sec 17 & 18

Var 21° 00' East

3989 Intersect boundary line between  
Oregon and Washington Territory  
587 links West of the 12 mile  
corner

Set Basalt Stone 14x10x8 in in

25

1905.  
Subdivisional lines of Township No. 6.

ground for Closing corner to Fractional  
Lots 17 & 18.

Land gently rolling Soil good  
Nov 28<sup>th</sup> 1874.

### General Description

The land in this Tr. Township  
is generally rolling. - It is covered  
with a heavy growth of Bunch  
grass and adapted to grassing pur-  
poses. - It has no water, but is  
convenient to water for stock  
near its boundaries.

The Soil is generally good 2<sup>d</sup> rate

North of Range No 33 East Will Mer.

List of Names.

A list of the names of the individuals employed to assist in running measuring and marking the lines and corners described in the foregoing Field Notes of the Subdivisional lines of Fractional Township No 6 N of the Base line of Range No 33 East of the Willamette Meridian, showing the respective capacities in which they acted:

Rufus L. Moore Chairman  
 Henry Meldrum Chairman  
 William A Cooper Assessor

We hereby certify that we assisted  
 Nicholas O. Walden, Deputy Surveyor  
 in surveying the Subdivisional lines of  
 Tract, Township No. 6 North of the  
 base line of Range No. 33 East of the  
 Willamette Meridian in the capacities  
 indicated by our respective signatures  
 and that said Tract, Township, has been  
 in all respects to the best of our knowl-  
 edge and belief well and faithfully  
 surveyed, and the boundary monuments  
 placed according to the instructions  
 furnished by the Surveyor General,  
 Rufus, B. Moore Chairman  
 Henry Melanson Chairman  
 William H. Cooper Chairman

Subscribed and sworn to by the above named  
 persons before me a Notary Public this  
 12<sup>th</sup> day of December 1874

John W. Seldrum  
 Notary Public

Walden

John W.

I Nicholas O Walden Deputy Surveyor  
do solemnly swear that in pursuance  
of a Contract with Benjamin Simpson  
U.S. Surveyor General for the State of  
Oregon bearing date the 6th day of  
July 1874 and in strict conformity  
to the laws of United States and the  
Instructions furnished by the said  
Surveyor General I have faithfully  
surveyed the Subdivisional lines of  
Fractional Township No 6 North of  
the Base line of Range No 33 East  
of the Willamette Meridian in the  
State aforesaid, and do further solemnly  
swear that the foregoing are the  
true and original field notes of such  
Survey

Nicholas O Walden  
Deputy Surveyor

Subscribed and Sworn to by the above  
named Nicholas O Walden Deputy Surveyor  
This 19th day of March 1875.

John W. Meldrum  
Notary Public

Witness  
Surveyor

US Surveyor General's Office 300

Portland Oregon June 23<sup>rd</sup> 1875

The foregoing field notes of the survey of the  
subdivisional lines of S. 6. N. R. 33 E

Will Mer Oregon, executed by A. O.

Walden D. S. under his contract no

209, bearing date July 6<sup>th</sup> 1874

having been critically examined

the necessary corrections and

explanations made the said

field notes and the surveys

they describe are hereby approved

Ben Simpson

Surgeon