

1 5

Field Notes of the Sub-divisional
Lines for Townships 6 North of
Ranges 33, 34 & 35 East of Willamette
Meridian, made under contract
No. 110, bearing date, February
7th 1865.

78

74

Index
Township 6 N Range 33 East,

18	17	16	15	14	13
105	104	98	99	85	82
19	20	21	22	23	24
103	102	96	91	86	81
30	29	28	27	26	25
101	100	95	89	84	79
31	32	33	34	35	36

Suspended to refer
Under inst app

Not Recorded.

Superseded by later survey
by N O Walden. See
Book 137
JNR

Commenced the survey of the
 subdivisional lines of Township
 No. 6 North of Range 33 East of
 Willamette Meridian,

April 19th 1865

North between sections 35 & 36

Township 6 N, Range 34 East

40.00 Set $\frac{1}{4}$ section post corner, Drove
 churred stake, dug pits and
 raised mound as per instructions

80.00 Set post corner for sections
 25, 26, 35 & 36 Drove churred stake,
 dug pits and raised mound as
 per instructions Land broken
 good grass soil hardly
 2nd rate,

East on a line between
 sections 25 & 36 T₆N, R₃₃E,

40.00 Set temporary $\frac{1}{4}$ section post

79.43 Intersect C₁ 48, line 65 chs

North of post, from which
 Town N₈₉° 35' West on true line

50

76

Township 6 N. Range 33 East Will, Mer.

39,71 Set $\frac{1}{4}$ Section Post corner,
Drove charred stake, dug pits
and raised mound as per
instructions

79,43 To Post corner,
Land broken grass
Good soil hardly
2 $\frac{1}{2}$ date,

North between sections 25 & 26
Township 6 N. R. 33 East,
Meridian 21° 30' East

40,00 Set $\frac{1}{4}$ Section Post corner
Drove charred stake, dug
pits and raised mound
as per instructions,

80,00 Set a post corner for sec,
23, 24, 25 & 26, Drove charred
stake dug pits, and
raised mound as per
instructions.

Land broken, grass

77 81
Township 6 N, Range 33 East Will, Ill.,
good soil 2nd date,

Cast on random between secs,
24 & 25 Township 6 N, R 33 East,
40.00 Set temporary $\frac{1}{4}$ section post
corner,

79.83 Intersected N & S Line 54 the
North of Post, from which
I run N 89° 34' West on true line

39.91 Set post corner for $\frac{1}{4}$ section
Drove charred stake, dug
pits and raised mound as
per instructions.

79.83 To Post Corner,
Land rolling grass
good soil 2nd date,

North between sections 23 & 24
Township 6 N, Range 33 East,
Variation 20' East,
40.00 Set $\frac{1}{4}$ section post corner,

78
Township 6 N. Range 33 East Will, Mer
Drove charred stake dug
pits and raised mound
as per instructions.

80.00 Set a post corner for sections
13, 14, 23 & 24. Drove stake, dug
pits, and raised mound
as per instructions,
Land rolling Soil 2^d Rate,

East on random between
sections 13 & 24 Township 6 N. R. 33 E.

40.00 Set temporary $\frac{1}{4}$ section
post,

79.56 Intersected N & S line
at post, from which I
ran West on true line

39.78 Set $\frac{1}{4}$ section post corner
Drove charred stake, dug pits,
and raised mound as per
instructions,

79.56 To post corner

79⁸⁵

Township 6 N, Range 33 East Will, Mer,
Land rolling, grass, good,
Soil 2nd rate,

North between sections 134 & 14,
Township 6 N, Range 33 East,
Variation 20° 30' East,
12,00 Trail or road course W,
40,00 Set $\frac{1}{4}$ section post corner
Drove charred stake, dug pits,
and raised mound as per
instructions.

5-3,10 To State boundary 9,45 ch
West of 16th Mile post
Set post corner for fractional
Sections 134 & 14, Township 6 N
Range 33 E, Drove charred stake,
dug pits and raised mound
as per instructions
Land gently rolling,
Good grass. Soil 2nd rate,

Township 6 N, Range 33 East Will, Mer,

North between sections 34 & 35,
 Township 6 N, Range 33 East
 40.00 Set $\frac{1}{4}$ section post corner Drove
 charred Stake, dug pits,
 and raised mound as
 per instructions, This
 post stand in the middle of
 a flat or valley $\frac{3}{4}$ mile
 wide coursing to the N. E.

80.00 Set a post corner for sections
 26, 27, 34 & 35, on edge of gully
 30 ft deep, Drove charred
 Stake, dug pit and raised
 mound as per instructions

Good Grass Soil 2^d Rate,

East on random between
 sections 26 & 35 T. 6 N, R. 33 E.
 40.00 Set temporary $\frac{1}{4}$ section
 post corner,

- Township 6 N, Range 33 East Nat, Mex,
 81,03 Intersect N 4 S Line 35 lbs South
 of post corner, from which
 Town, S. 89° 45' Mon Town line
 40,04 Set 1/4 section post corner
 Drove charred stake, dug
 pits and raised mound as
 per instructions
 80,09 To post corner,
 Lined, broken soil
 2nd date,

North between sections

26 & 27 Township 6 N, R 33 East,
 Variation 21° East

40,00 Set 1/4 section post on side
 hill slopes to the N, W, above
 remains 40 ft deep,

80,00 Set post corner for sections
 22, 23, 26 & 27, Drove charred
 stake dug pits and
 raised mound as per

Township 6 N., R. 33 East Will, Mex,
 instructions,
 Land Broken Soil
 2nd rate,

East on random between
 sections 23 & 26, T. 6 N. R. 33 East,
 40,00 Set temporary $\frac{1}{4}$ Section
 post corner,
 50,50 Large well beaten trail course
 N. & S, in Dry gulch,
 80,50 Intersected N & S Line.
 37 Lhs South of post, from
 which I run S. $89^{\circ} 44' W$
 on true line
 40,25 Set $\frac{1}{4}$ Section post, corner
 Drive churred stake,
 dig pit and raised
 mound as per instructions
 80,50 To post corner
 Land Broken Soil
 2nd rate,

Township 6 North Range 33 East Will, Mex

North between sections 22 & 23

Township 6 N Range 33 East,
Variation $20^{\circ}15'$ East,

4000 Set $\frac{1}{4}$ section post, on side
of steep ravine, Drove charred
stake dry pit and raised
mound as per instructions,

8000 Set a post corner for sections
14, 15, 22 & 23, Drove charred
stake, dry pit and raised
mound as per instructions

Land broken Soil
2nd rate,

East on random between
sections 14 & 23, T 6 N R 33 East

4000 Set temporary $\frac{1}{4}$ section
post

8075 Intersected N. S. Line 27
the South of Post from

Township No 6 N. Range 33 E, Will. Mer,
Tenn

S 89° 51' W on town line

40,37 Set post corner for 1/4 section
Drove charred stake dug
pits and raised mound
as per instructions

80,75 To post corner
Land gently rolling
Soil 2nd (ate)

North between sections 14 & 15

Township 6 N R 33 East
Bear 21° East

36,00 True course West,

40,00 Set 1/4 section post corner
Drove charred stake dug
pits and raised mound
as per instructions.

52,94 To Northern boundary
line of Oregon, 9.93 chs
West of the 15th Will post,

Township 6 N. R. 33 East Will. Mer,
 Set post Drove charred stake
 dug pits and raised mound
 as per instructions
 Sand rolling Soil 2^d Rate

North between sections 33 & 34
 Township 6 N. R. 33 E. Will. Mer
 40,00 Set $\frac{1}{4}$ section post corner
 Drove charred stake, dug pits
 and raised mound as per
 instructions.
 80,00 Set a post corner for
 sections 27, 28, 33 & 34, Drove
 Charred stake dug pits
 and raised mounds as per
 instructions
 Sand broken Soil 2^d Rate

East on Burdick between
 sections 27 & 34 T. 6 N. R. 33. East,

90
86
Township 6 N. Range 33 East W. Mer,
40,00 Set temporary $\frac{1}{4}$ Section
post corner,

80,20 Intersect N & S Line
15 lbs north post corner,
from which I run,

40,00 Set $\frac{1}{4}$ Section post
corner, Drove charred
Stake dug pits and
raised mound as per
instructions.

80.20 To post corner
and very broken
Soil $2\frac{1}{4}$ date,

North between sections
27 & 28, Township 6 N, R. 33 E,
Bar 21 East

40,00 Set $\frac{1}{4}$ Section post corner,
Drove charred stake,
dug pits and raised
mound as per instructions

Township 6 N, Range 33 East Will, Mex,
 8000 Set a post corner for
 sections 21, 22, 27 & 28, Drove
 charred stake dug pits
 and raised mound as per
 instructions.

Land broken soil 2nd rate,

East on boundary between
 sections 22 & 27, Township 6 N, R. 33 E,
 4000 Set temporary 1/4 Section
 post corner,

8009 Intersect MPB line 40 lbs
 North of post, from which
 Run,

N 89° 43' W on true line,

4004 Set 1/4 Section post corner
 Land slopes to the NW,
 Drove charred stake, dug
 pits and raised mound as
 per instructions,

8008 To post corner,

Township 6 N, Range 33 East, Will, Mex
Land broken
Soil 2^d rate,

North between sections 21422,
Township 6 N, Range 33 E Will, Mex,
Variation 21° East

40,00 Set 4 section post corner
on summit of ridge ⁺80
Drove churried stake,
dug pits and raised
mound as per instructions

80,00 Set post corner for sec
15, 16, 21 & 22. Drove ⁺90
churried stake dug
pits and raised mound
as per instructions,
Land broken
Soil 2^d rate,

Township 6 N, Range 33 East Mill, Me,

East on Random between sections

15 & 22, Township 6 N, R. 33 East

40,00 Set temporary $\frac{1}{4}$ Section post

80,00 Intersect N 73 Line 3' 5" S

Post of Post from which I run

N 89° 45' West on true line

40,00 Set $\frac{1}{4}$ Section post corner

on East side of Gully, Drive
churned stake, Dig pit, and
raised mound as per instructions

80,00 To Post corner,

This line passes over a
succession of ridges

found quite broken
Soil 2nd rate

North between sections

15 & 16, Township 6 N, R. 33 E,

Variation 18° 30' East

40,00 Set $\frac{1}{4}$ Section post corner,

94

90

Township 6 N, Range 33 East Will. Mer,
Drove charred Stake dug
pits and raised mound as
per instructions,

52,50 To State Boundary Line

9.09 West of Mile post
No. 14,

Set post corner for sections
15 & 16, Drove charred stake,
dug pits and raised
mound as per instructions

Land broken

Soil 2nd Rate,

North between sections 32 & 33

Township 6 N, R 33 East,

4,000 Set 4 Section post, corner
Drove charred Stake, dug
pits and raised mound
as per instructions,

8,000 Set post corner for sec

28, 29, 32 & 33, Drove charred

Township 6 N Range 33 East Will, Okla,
Stake, dug pits and raised
mound as per instructions,
Land Rolling
Soil 2nd rate,

East on random between
sections 28 & 33 T6 N, Range 33 E,
4000 Set temporary 4 section post
near top of hill sloping to the
S.W.

7979 Intersect N & E line 20 lbs South
post corner, from which
I run

S 89° 51' W on true line

89.89 Set 4 section post, drove
churned stake & raised mound
as per instructions,

7979 To post corner,
Land Broken

Soil 2nd rate

Township 6 N. Range 33 East Will, Mo.,

North between sections 28 & 29
Township 6 N, Range 33 East,
Bar 21° East,

40,00 Set $\frac{1}{4}$ section post, on steep
side hill facing the S.W.,
Drove charred stake dug
pits and raised mound
as per instructions,

80,00 Set a post corner for
sections 20, 21, 28 & 29,, Drove
charred stake dug pits and
raised mounds as per
instructions,

Land broken,

Grass good,

Soil 2nd rate,

East on random between
sections 21 & 28 T6 N Range 33 E,

40,00 Set temporary $\frac{1}{4}$ section

Township 6 N Range 33 East Mill, Mer,
post corner,

79,62 Intersect of South line 52 lbs
South of post from which I
run $389^{\circ}38'$ West on true line

39,81 Set $\frac{1}{4}$ section post, on level, 40
Drove charred stakes, dug pits
and raised mound as per
instructions,

79,62 To Post corner, 100
Sand broken,
Soil 2nd rate,

North, between sections 20 & 21
Township 6 N. R 33 East,
Bar 21st East

40,00 Set $\frac{1}{4}$ section post corner, 50
Sand Secend to the N,
Drove charred stakes, dug
pit and raised mound as per
instructions

80,00 Set post corner for sections 40

Township 6 N, Range 33 East Will, Men
 16, 17, 20 & 21, Drove churres
 Stake dug pits and raised
 ground as per instructions
 Land broken
 Soil 2nd Rate,

East on random between
 sections 16 & 21 T. 6 N, R. 33 E,
 40,00 Set temporary $\frac{1}{4}$ section
 post,
 79.76 Intersect the N & South line
 42 lbs South of post from
 which I run
 S 89 42° W on true line,
 39.85 Set $\frac{1}{4}$ section post, Drove
 churres Stake, dug pits
 and raised ground as
 per instructions,
 79.70 To Post corner,
 Land broken
 Soil 2nd Rate,

Township 6 N. Range 33 East Will. Mer,

North between sections 16 & 17
Township 6 N. R33 E

* Bar 21° E

40.00 Set 1/4 section post corner
Drove charred stake, dug
pits and raised mound as
per instructions,

52.79 To North boundary of State
2.55 miles west of mile post
No 134

Set post corner for sections
16 & 17, Drove charred stake,
dug pits and raised mound
as per instructions
Lured Baker

Set 2 1/2" nails,

North between sections 81 & 82,
Township 6 N. Range 33 East,

40.00 Set 1/4 section post corner, too

Township 6 N, R 33 East Will, Mer,
Drove Charred Stake, dug
pits & raised mounds as per
instructions,

8000 Set a post corner for sections
29, 30, 31 & 32, on high hill 100
Drove charred stake, dug pits
and raised mounds as per,
instructions,

Soil broken

Soil 2nd rate

East on Random between
sections 29 & 32 T. 6 N, R. 33 E,
4000 Set temporary $\frac{1}{4}$ section
post corner,
7979 Intersect N. & South line 150
25 lbs N. of post corner
from which I run
N. 89° 49' W on town line
3988 Set temporary $\frac{1}{4}$ section
post, Drove charred

Township 6 N. Range 33 East, Will, Mer,
Stake, dug pits, and raised
mound as per instructions

78,77 To Post corner,
Land broken.
Soil 2nd Rate

West on bandon between
Sections 30 & 31, T6 N R33 East,
40,00 Set temporary 1/4 Section
78,92 Intersect West Town line
at post from which
I run ^{1/4} West on true line

38,52 Set 1/4 Section post, Drove
charred Stake dug pits
and raised; mound as per
instructions

78,52 To post corner,
Land broken
Soil 2nd Rate

North between sections 29 & 30

102

98

Township of Range 33 East Mill Mer,
Variation $21^{\circ} E$

40,00 Set $\frac{1}{4}$ Section post corner
on level, Drove chumel stake
dug pit and raised

Mound as per instructions

80,00 Set a post corner for sections
19, 20, 29 & 30, Land slopes to
the North, Drove charred
stake, dug pit, and
raised mound as per
instructions,

Land broken

Soil 2^{nd} Pat,

East on Random between
Sections 20 & 29, S 6 N, R 33 E

4000 Set temporary $\frac{1}{4}$ Section
post,

79,56 Intersect N 4 S Line 51 lbs
No of post. from which

Run $N 83^{\circ} 38'$ West on true line,

32,78 Set $\frac{1}{4}$ Section post,

Township 6 N, Range 33 East Will, Minn,
Land slopes to the N, E, 75
Drove charred stake, dug pits,
and raised mound as per
instructions,

7,56 To post corner
Land broken,
Soil 2nd rate,

West on Pandora between
Sections 19 & 30, T6 N, R33 E,
4,000 Set temporary $\frac{1}{4}$ Section post
7,905 Intersect West Town Line 30 fms
N of post corner from which I run
N89°47'E on true line,

3,905 Set $\frac{1}{4}$ Section post corner,
on hill side sloping to the East
Drove charred stake, dug pits
and raised mound as per
instructions,

7,905 To Post Corner,
Land broken Soil 2nd rate,

Township 6N, Range 33 East,
North between sections, 19, 420

Township 6N, Range 33 East
Variation 20° East,

4000 Set $\frac{1}{4}$ Section post and 90
slopes to the North, drove
charred stake, dug pit,
and raised mound as per
instruction,

8000 Set $\frac{1}{4}$ post corner for section
17, 18, 19, 420, drove charred
stake, dug pit and raised
mound as per instruction
Land broken, Soil 2^d Rate,

East on random between
sections, 17, 420, Township 6N, R. 33E,

4000 Set temporary $\frac{1}{4}$ section
post,

7978 Intersect N & S line 90 lbs
North of post, from which
I run, N 89° 30' W on true line

8989 Set $\frac{1}{4}$ section post, corner

Township 6 N, Range 33 East Will, Mer,
Drove charred stake, dug pits,
and raised mound as per
instructions

7,78 To Post Corner

Land rolling, Soil 2nd rate,

West on random between section
18 & 19, Township 6 N. Range 33 East,

40,00 Set $\frac{1}{4}$ section post, corner temporary

7,924 Intersect N.W. Line 65 lbs

North of Post, from which
Run N. $89^{\circ}32'$ E, on true line

3,924 Set $\frac{1}{4}$ section post, Drove charred
stake, dug pits and raised
mound as per instructions

7,924 To Post Corner

Land rolling

Good grass

Soil 2nd rate,

North between sections 18 & 19
Township 6 N, Range 33 East

102

Township 6 N, Range 33 East T11, Mer,
Variation 21° 8.

40.00 Set $\frac{1}{4}$ section post corner
Drove charred stake,

dug pit & raised
ground as per instructions

52.00 To State line 8.98 chs

West of B. & O., No. 12

Set post corner
for sections 17 & 18

Drove charred stake

dug pit and raised
ground as per
instructions,

Sand broken

Soil 2nd rate,

The foregoing surveys were made
 by Deputy William H. Odell, assisted
 by W. W. Johnson Compassman
 C. C. Harcamer } Chainmen
 A. H. Shibles }
 William Warren Axeman

General remarks.

This Township embraces lands
 only adapted for grazing purposes
 The southern portion is very
 broken the hill rising from
 Walla Walla Valley in broken
 ridges about 300 feet. The
 Northern portion is gently rolling
 but high for irrigation,
 The whole is covered with a
 fine growth of Grass, and
 the soil is good,

There is no water in this
 Township in the dry season,
 (over)

but it is not far to water to
 the North, the Walla River
 runs nearly parallel with the
 State line about 1 mile distant.

I William H. Odell, do hereby
 certify that the foregoing are the
 true and original field notes
 of the survey of the subdivisional
 lines of Township No. 6 N., Range, 38 E,
 as made under contract No. 110
 bearing date February 7th 1863,
 as will appear from Affidavit
 duly made out at the close of
 said Contract and attached
 to the field notes for the Exterior
 lines of T. 6 N., R. 37 E., Will Mes,
 William H. Odell
 Deputy Surveyor

Surveyor General's Office
Eugene City. 1865

The foregoing field notes of the survey of Subdivis-
ional lines of Township 6 North Range 33 East
Willamette Meridian, Oregon, executed by Odell & Lewis
Deputy Surveyors, under their contract No. 110, dated
Feb. 7, 1865, having been critically examined, the
necessary explanations and corrections made, the said
field notes and the surveys they describe are hereby
approved.

Surveyor General of Oregon