

54 ~~394~~

494  
Index

To Exterior lines of Township N<sup>o</sup> 5 N, R<sup>o</sup> 34 E.

See Page 67

71	72	73	73	74	75	
6	5	4	3	2	1	70
						12 69
						13 69
						24 68
						25 67
						36 67



To 419 510

Township No. 5 N, R. 34 E, Will. Mer,  
677. Dug pits drove charred  
Stake, and raised mound as per  
instructions,

Land hill grass poor Soil  
3<sup>rd</sup> Rate,

North between Ranges 34 & 35 on  
East boundary of Sec, 1 S 5 N  
Var, 2<sup>o</sup> East,

40.00 Set 1/4 Sec post corner 20  
Drove Charred Stake, dug  
pits, and raised Mound as  
per instructions

80.00 Set post Corner for Towns, 60  
546 N in Ranges 34 & 35 E  
on Secs 1. & 31 & 36. Land  
Slopes to the North  
Drove Charred Stake, dug  
pits, and raised Mound  
as per instructions,  
Land hill fair grass  
Soil 3<sup>rd</sup> Rate,



Township No 5 N. Range 33 E Will. Mer,

April 11<sup>th</sup> 1865;

West between Towns 5 & 6 N. R 33 E  
on N boundary of sec. 6, T 5 N.

Variation 21° East

Set half mile and mile posts  
at 40.00 and 80.00 chains

and find the Township line  
to be 5 Miles 78.44 chs. and

the falling to be 1.47 South,  
of post,

True line will be S 89° 50' E

S. 89° 50' East on true line on North

Boundary of sec 6 T 5 N. R. 33 E.

~~39.44~~ Var 21° East

38.44 Set 1/4 Sec, post on east  
side of ravine 40 ft deep  
Drove charred stake,

clay pits, and raised  
mound as per instructions

78.44 Set post corner sec

5. 6. 31 & 82, Drove charred



Township No. 5 N R 34 East Will, Mer  
 Stake, and raised mound  
 as per instructions

Land very broken soil  
 hardly  $\frac{2}{3}$  rate,

S 89° 50' East on true line between  
 sections 5432 S, 5460 N, R, 34 E,

Bar 21° East,

40,000 S 1/4 Section post, Drove

Charred stake, dug pits  
 and raised mound as  
 per instructions,

80,000 Set a post corner for sections

4, 5, 32 & 33, Drove charred  
 Stake dug pits and raised  
 mound as per instructions.

Land broken grass  
 good soil  $\frac{2}{3}$  rate,



Township N. 5 N. R. 34 E, Will. Mer,  
April 14<sup>th</sup> 1865,

\* S 89° 50' E on true line between  
Towns 546 N, Range 34 E on North  
boundary of sec 4. Var 21° E

40.00 Set 1/4 Sec post, Drove Charred  
Stake, dug pits, and raised  
Mound as per instructions

80.00 Set post corner for Secs 3, 4  
33 & 34, Drove Charred Stake, dug  
pits and raised Mound as per  
instructions,

This line passes over hilly  
land good grass soil  
2<sup>nd</sup> Rate,

S, 89.50' E, on true line between  
Towns 546 N, in Range 34 E,  
on North boundary of Sec 3  
Var 21° E -

40.00 Set 1/4 sec post, Drove Charred  
Stake, dug pits and raised  
Mound as per instructions



74

414 514

Township No 5 N. Range 34 E, Will, Mo.,  
 8000 Set post corner for secs 2.3  
 34 & 35, Drove Charred Stake,  
 dug pit, and raised  
 Mound as per instructions  
 Land hilly soil hardly  
 2<sup>nd</sup> rate, Grass good,

S 89° 50' E, on true line on  
 North boundary of Sec 2. T50N  
 R 34 E,  
 Var 21° E,

4000 Set 1/4 Sec, post Drove Charred  
 Stake dug pits and  
 raised Mound as  
 per instructions

7700 Pine Creek 20 lbs wide Course N, W,

8000 Set post corner for secs 1.2,  
 35 & 36, Drove Charred Stake  
 dug pits and raised Mound  
 as per instructions  
 Land Broken soil  
 hardly 2<sup>nd</sup> rate, Good grass,



Township No 5 N, R, 34 E, Will, Ill.,  
S 89° 50' E, on true line between  
Towns 5 & 6 N in Range 34 E  
on North boundary of sec 1,  
Bar 21° E.

15.00 Summit of ridge between Pine <sup>+</sup> 70  
Creek & Dry Creek  
Bar 23° E -

40.00 Set 1/4 Sec post on hill 20  
facing the North.  
Drove charred stake, dug pits,  
and raised mound as  
per instructions.

80.00 To post corner of Township 40  
Land hilly Soil 3<sup>rd</sup> rate  
good grass

---

For general remarks  
see Book No of subdivisonal  
lines page

---



Surveys made by Deputy  
 W. D. Odell assisted by  
 C. C. Harcum & Chaimen  
 A. Shibles &  
 William Warren Axman,

I William D. Odell, do hereby  
 certify that the foregoing are  
 the true and original field  
 notes of the survey of  
 Township No. 5 North of Range  
 34 East of Will. Mer. in the  
 State of Oregon; made, under  
 contract No. 110 in accordance  
 with the laws of the United  
 States and the Instructions  
 furnished by the Surveyor  
 General, as will appear  
 from Appendix A duly  
 made out after completing  
 said Contract and attached  
 to field notes of Township  
 No. 5 North of Range



517

77

417

Line of Range No. 34 East  
of Willamette Meridian

William H. Odell

Deputy Surveyor



Township No 5 N, Range 33 E, Will, Mer,  
4000 Set 1/4 Sec post cor in dup

Barine Course N 100

Dug pits Drove Charred  
Stake, and Raised Mound  
as per instructions.

8000 Set post corner for sec,  
1. 12. 677. on Spur of hill  
Course North.

Drove Charred Stake, dug  
pits, and Raised Mound  
as per instructions.

Land hilly good Grass Soil  
2<sup>nd</sup> Rate,

North on East boundary of sec  
1 T. 5 N, R. 33. E, Will, Mer,  
Bar 21° E.

4000 Set 1/4 Sec post on ridge.  
Course N, W,

Drove Charred Stake, dug  
pits and Raised Mound  
as per instructions



2  
 Township No 33 N, Range 33 E, Will, Mo.,  
 8000 Set post corner for Townships  
 546 N in Ranges 33 & 34 E,  
 and sec 1. 6. 31. 436.

Drove churned stake, dug pits  
 and raised mound as per  
 instructions,  
 Found Broken good  
 Grass soil hardly 2<sup>nd</sup> Rate,

West on Random between  
 Townships 546 N, Range 33 E,  
 Bar, 21° E,

April 20<sup>th</sup> 1865,  
 Set Half Mile and Mile posts  
 at 4000 and 8000 ch and  
 found the Town line to  
 be 5 Miles 78.60 The  
 falling to be, 50 South  
 of Corner post,

The correction will be  
 S 89° 56' E, on true line the  
 west fraction 1.40 Short



Surveyor General's Office  
 Eugene City Aug 23 1865

The foregoing field notes of the Survey of the ~~the~~  
~~Standard Quarter North, through Ranges 31,~~  
~~32, 33, 34, 35, 36 & 37 East Will. Mer. Oregon,~~  
~~and of the exterior lines of Tps. 5 North Ranges~~  
 33, 34, 35 East Willamette Meridian, Oregon,  
 executed by Odell & Lewis, Deputies, under con-  
 tract No. 110, bearing date February 7<sup>th</sup> 1865,  
 having been critically examined, the necessary ex-  
 planations and corrections made, the said field  
 notes and the surveys they describe, are hereby approved.

E. L. Applegate  
 Surveyor General of Oregon.