

1 5

Field Notes of the Sub-divisional
Lines for Townships 6 North of
Ranges 33, 34 & 35 East of Willamette
Meridian, Work under Contract
No. 110, bearing date, February
7th 1865.

44

40

10

Index

Township 6 N, Range 34 East

18	70	17	69	16	68	15	67	14	66	13
71		71		64		59		55		49
19	70	20	69	21	68	22	67	23	66	24
69		68		63		57		53		47
30	69	29	68	28	67	27	66	26	65	25
67		66				56		51		45
31	68	32	67	33	66	34	65	35	64	36

copy affidavits of Warren & Johnson

Commenced the survey of the
 subdivisional lines of Township
 N. 6 N., R. 34 E., Will, Mer,
 April 19th / 1865,

North between sections 35 & 36
 Township 6 N R 34 E Will Mer
 Variation 21° East,

- 40.00 Set 4 section post Drove churred
 stake dry pits and raised
 mound as per instructions
- 80.00 Set a post Corner for Secs 30
 25, 26, 35 & 36, Drove churred
 stake, dry pits and raised
 mound as per instructions
 Land rolling Soil 2^d Rate,

Cont on random between Secs
 25 & 36 Township 6 N., R. 34 E -

- 16.00 Dry Creek 25 lbs wide course N, W,
- 40.00 Set temporary 4 section post,
- 45.60 Cross ditch fence and enter field
- 58.80 Leave field,

46

- Township 6 N, R. 34 E, Will, Mer
79,28 Intersected East and West line
40 ^{ths} South of post, from which
Town, $389^{\circ} 43'$ West on true line
39,64 Set $\frac{1}{4}$ Section post corner
Drove charred stake dug
pit and raised mound
as per instructions.
79,28 To post corner.
Land rolling soil $2\frac{1}{2}$ rate

North between sections
25 & 26, Township, 6 N, R, 34 E,
Barration 21° E,

- .65 Road course E & W,
9,15 Dry creek course N, W,
34,40 Spring Branch $7\frac{1}{2}$ ^{ths} wide course E, W,
40,00 Set $\frac{1}{4}$ Section post corner
Drove charred stake dug pit
and raised mound
per instructions,
80,00 Set a post corner for

Township 6 N, R, 34 E, Will, Mer,
 Sections 23, 24, 25 & 26 T, 6 N, R, 34 E,
 Drove charred stake dug pits
 and raised mound as per
 instructions

Land gently rolling Grass
 good Soil good 2nd Rate,

East on random between secs
 24 & 25, Township 6 N, R, 34 E

500 Creek course N.W.

4000 Set 4 section post, Drove
 charred stake dug pits
 and raised mound as per
 instructions

79.63 Intersect East Town line
 59th south of post, from
 which I run

88° 35' West on town line

39.81 Set 4 section post Drove
 charred stake dug pits and
 raised mound as per
 instructions,

#8

44
Township 6 N, R, 34 E, Will, Mer,
79.63 To post corner

Land gently rolling
Grass good, Soil 2nd Rate,

North between sections 23 & 24

Township 6 N, R, 34 E,
Variation 2nd East,

5.10 Spring Branch corner N, W,
40.00 Set 1/4 Section post, Drive
Charred stake, dug pits
and raised mound as
per instructions,

57.00 Road course West,

80.00 Set a post corner for
sections 13 & 14, 23 & 24,
Drive charred stake, dug
pit and raised mound
as per instructions,

Land rolling good
Grass Soil 2nd Rate,

45
49

Township No 6 N, R, 34 E, Will, Miss,

East on random between
sections, 13424 56 N, R, 34 E,
40.00 Set temporary $\frac{1}{4}$ Section
post

7947 Intersect East Town line 68 lbs
South of post from which
I run $S 89^{\circ} 31' W$ on true line

39.73 Set $\frac{1}{4}$ section post corner
Drove charred stake dry pits
and raised mound as per
instructions

7947 To Post corner,
Land gently rolling
Soil 2nd date,

North between sections
13414 Township 6 N, R, 34 E,
Bar $21^{\circ} E$,

.15 Spring Branch course West
22.50 Road, course West,

50

46

46

Township 6 N, R. 34 E, Will. Mer
40.00 Set 4 section post. Drove charred
stake, dug pit & raised mound
as per instructions.

52.41 Intersect State boundary 11.56 ch
Wes of post, 22³/₄ Mile post
Set post corner for sec
13 & 14, Drove charred stake
dug pit and raised mound
as per instructions

North between sections,
34 & 35 Township 6 N, R. 34 E,
Bar 21° East,

40.00 Set 4 section post corner,
Drove charred stake, dug
pit and raised mound as
per instructions

43.50 Pine creek 25¹/₂ mi course N, W,

49.00 do, do, do, do, do, N, E,

80.00 Set 4 post corner for sections
26, 27, 34 & 35 Drove charred
stake dug pit and raised
mound as per instructions

Township No. 6 N., R. 34 E., Mill, Mer,
 Lined broken, from Pine
 Creek North, the soil is first
 rate, South 2nd rate,

East on random between
 sections, 26 & 35 - T. 6 N., R. 34 E.,
 12,75' Pine Creek Course N
 40,00' ~~Set 4 section~~ of line sec, post
 79,75' Intersect N & S. line 55' West of
 post from which I run
 N 85° 35' West, on true line,
 39,87' Set 4 section post corner
 Drove charred stake deep pits
 and raised mound as per
 instructions.

79,75' To post corner,
 Lined gently, rolling
 grass good soil East to
 the crossing of Pine
 Creek 1st rate and under
 cut through Pine Creek
 forming the inclosure on the
 South & East,

Township No. 6 N. R. 34 E. Will, Mer,

North between sections

26 & 27, T. 6 N. R. 34 E, Will, Mer,

Variation 21° East,

40,00 Set $\frac{1}{4}$ section post corner,

Drove charred stake, dug
pit and raised mound as

per instructions,

4650 Pine Creek course N. W.

80,00 Set a post corner for

sections 22, 23, 26 & 27, Drove

charred stake dug pit and

raised mound as per
instructions,

Land gently rolling
Soil to pine Creek 1st rate

thence 2nd rate,

East on random between

sections 23 & 26, T. 6 N, R. 34 E,

4000 Set temporary $\frac{1}{4}$ section

post corner.

- Township 6 N, R. 34 E, Will, Mex,
 80,25 Section N, S, Line 30 lbs ~~wood~~
 of post, from which I run
 N 85° 47' W, on true line
- 40,12 Set 4 Section post I drove charred
 stake, dug pits and raised
 mound as per instructions,
- 80,25 To post corner
 land gently rolling
 Soil 2 1/2 ft. rate,

North between sections

22 & 23 Township 6 N, R. 34 E,
 Bar 21° E,

- 40,00 Set 4 Section ~~first~~ corner
 Drove charred stake dug
 pits & raised mound as
 per instructions
- 49,00 Creek 10 lbs wide course N, W,
 52.15 Road course N, W,
 80,00 Set a post corner for sections
 14, 15, ~~22~~ 23, Drove charred

50
 Township 6 N, R. 34 E, Will, Mer,
 Stake dug pits and raised
 mound as per instructions
 Land gently rolling
 Soil 2nd rate,

East on random between
 sections 14923 Township 6 N, R 34 E,
 40.00 Set temporary $\frac{1}{4}$ section
 post,

79.75 Intersect N-S line & the
 south of post from
 which I run

S $83^{\circ} 57'$ W on true line
 39.87 Set $\frac{1}{4}$ section corner post,
 Drive charred stake dug
 pits and raised mound
 as per instructions

79.75 In post corner,
 Land gently rolling
 Grass good Soil good
 2nd rate,

Township 6 N, R, 34 E, Will, Mer,
 April 21st, 1865,
 North between Sections 14 & 15
 Township 6 N, R, 34 E,
 Variation 21° East,

- 935 Road course N. W.
- 40.00 Set first corner for 1/4 section
 Drove charred stake dug
 pits and raised mound
 as per instructions
- 46.00 Spring Branch course N. W.
- 52.10 To State line 9.78 chs West
 of 21st Mile post,
 Set post corner for fractional
 sections 14 & 15, Drove charred
 stake dug pits and raised
 mound as per instructions
 Land gently rolling
 Soil good 2nd rate,

North between sections
 33 & 34 Township 6 N, R, 34 East,

52
 Township 6 N. R. 34 East Mill, Mer,
 Bar 21° E,

40.00 Set 4 Section Post corner

80.00 ~~Set 4 Section Post~~ a post
 corner for sections 27, 28,

33 & 34, drove churched stake

Dug pits and raised
 mound as per instructions.

Land broken grass
 Good Soil 2nd Fall,

East on transect between
 sections 27 & 34 to N R 34 East,

40.00 Set temporary 4 section
 post,

79.50 Intersect N & S line 47 ths
 N of post, from which
 I run N 85° 40' West on true line

39.75 Set 4 section post, drove
 churched stake, dug pits,
 and raised mound as
 per instructions,

Township 6 N. R. 34 E. Will Mer,
 7950 To post corner,
 Land Broken Soil
 2nd Rate,

North between sections 27, 28
 40,00 Set $\frac{1}{4}$ section post corner
 Mar. 21st 00
 Drove charred stake, dug
 pit and raised mound
 as per instructions

80,00 Set a post corner for sections
 21, 22, 27 & 28, Drove charred
 stake dug pit and raised
 mound as per instructions
 Land broken Soil 2nd
 Rate,

East on Parcelom between
 sections 22, & 28, Township
 6 North Range 6 N
 40,00 Set temporary $\frac{1}{4}$ section post
 80,00 Intersect N & E line 15 lbs
 South of Post from which

Township 6 N, R, 34 E, Will, Mer,
Run 389°54' West on
same line,

40,05 Set $\frac{1}{4}$ Section post, Drove
charred stake dug pit
and raised mound as
per instructions,

80,10 To Post corner,
Sand rolling
Good Grass Soil $\frac{1}{2}$ post,

North between sections
22 & 21 Township 6 N, R, 34 E,
Variation 21° East,

40,00 Set $\frac{1}{4}$ Section post, Drove
charred stake, dug pits,
and raised mound as
per instructions,

80,00 Set a post corner for
sections 15, 16, 21 & 22,
Drove charred stake, dug
pits and raised mound

Township 6 N. Range 34 E Will. Mer,
 as per instructions,
 Land rolling soil 2^d pate,
 Good grass,

East on random between
 sections 15 & 20 T. 6 N., R. 34 E.
 35.00 Ditch fence,
 40.00 Set temporary 1/4 section
 post

8020 Intersect N. & S. line 12 lbs
 South of post, from which
 Drive S 85° 55' West on true
 line

40.10 Set 1/4 section, post. Drive
 churree stake, dug pits and
 raised mound as per instruct-
 ions

8020 To post corner
 Land broken soil
 2^d pate,

Township 6 N. Range 34 East Will, Alex,

North between sections 15 & 16

* Township 6 N. Range 34 East,
 9.50 Enter field, $N. 21^{\circ} E$

40.00 Set 4 sections post, Drive
 charred stake, dug pit
 and raised mound as per
 instructions,

52.45 Intersect State boundary

9.30 Chas west of the 20th

mile post,

Set post corner for

sections 15 & 16, Drive

charred stake dug pit

and raised mound as
 per instructions,

Land level, Soil

good 2nd date,

North between sections

32 & 33 Township 6 N. R. 34 E,

Var 21^o East,

Township 6 North Range 34 E, Will Mer,
 40.00 Set $\frac{1}{4}$ section post, Drove 10.0
 Charred stake dug pits
 and raised mound as
 per instructions,

80.00 Set a post corner for sections
 2849, 32433, On hill side 75
 sloping to the North, Drove
 Charred stake dug pits
 and raised mound as per
 instructions,

Land broken good
 grass soil 2nd rate,

East on Randona between
 sections 28433 to N, R, 34 E,

40.00 Set temporary $\frac{1}{4}$ section
 post

7.92 Intersect NW line 40 the
 South of post, from which
 I run S, 65 43' W on town line

39.96 Set $\frac{1}{4}$ section post corner,

Township 6 N, Range 34 E, Will, Okla,
 on land sloping to the
 East, Drove charrred stake
 dug pits and raised
 mound as per instructions
 75.92 To post corner
 Land broken soil
 2nd rate,

North between sections
 28425, Township 6 N, R, 34 E,
 Variation 21° East,
 40.00 Set 1/4 Section post corner, drove
 charrred stake, dug pits
 and raised mound as per
 instructions,
 80.00 Set a post corner for
 sections 20, 21 28429,
 Drove charrred stake dug
 pits and raised mound
 as per instructions,
 Land rolling good

Township 6th, Range 34th, Will. Mer,
grass Soil 2nd rate.

East on Rowdown between
sections 21 & 28 T. 6 N., R. 34 E.

4000 Set temporary 1/4 Section post,
80,17 Intersect N. P. S. Line at
Post, from which
Run West on true line

40,05 Set 1/4 section post, Drive
churned stake dug pits
and raised mound as
per instructions,

80,17 To Post corner,
Land rolling soil
2nd rate

X

April 21st, 1865,
North between sections
20 & 21 Township 6th, R. 34 East,
Variation 21 East,

22,50 Trail course west,

40,00 Set 1/4 Section post corner
Drove churned stake, dug pits

Township 6. N. R 34. E. Hill. Mer.
and raised mound as per Instructions.
80,000 } Post corner for Secs 16, 17, 20 & 21
Drove charred stake dug pits & raised
mound as per Instructions.
Land Rolling grass good. Soil
2^d Rate

East on random between
sections 16 & 21 To N. R 34 East,
7,60 Road course North West,
9,76 Pine Creek course N.W.,
40,00 Set temporary $\frac{1}{4}$ section
post,
80,25 Intersect N 75^o Line 30
the south of post, from
which I run
S 85^o 47' West on true line
40,12 Set $\frac{1}{4}$ section post, Drove
charred stake dug pits and
raised mound as per
Instructions,
80,25 To post, corner
Land Rolling
good grass Soil 2nd Rate,

0.61

Township 6 N, R 34 E NW 1/4, Mer,

North between sections 16 & 17

Township 6 North Range 34 East,

Variation 21° East,

950 Pine Creek course N W,

3200 Fence course S W,

4000 Set 4 section post corner,

Drove charred stake dug

pits and raised mound as per instructions,

5283 To State boundary line 9.35 ch

West of 18th Mile post,

Set post corner for fractional

sections 16 & 17, Drove charred

stake dug pits and raised

mound as per instructions,

x

North between sections 31 & 32

Township 6 N, R 34 East,

Variation

4000 Set 4 section post corner,

Township 6 N, Range 34 E, Will, Minn,
on level slopes to the
North, dug pits, and
excised mound as per
instructions.

80.00 Set a post corner for
sections 29, 30, 31 & 32, Land
slopes to the N, West,
Drove cherted stake
dug pits and excised
mound as per instructions
Land broken good
Grass Soil 2nd date,

East on road between
sections 29 & 32 T 6 N, R 34 East,
40.00 Set temporary ~~the~~ section
post corner
99.66 Intersect N 9 S Line 30
the South of post, from
which I run S 89° 47' West on
true line,

Township 6 N, R. 34 East Will, Mer,
 39,83 Set $\frac{1}{4}$ section post corner,
 Land slopes to the N, W,
 Drive & hurred Stake,
 dug pit, and raised
 ground as per instructions
 7966 To post corner
 Land rolling good
 grass soil 2^d rate,

West on sundown between
 sections 30 & 31, T. 6 N, R. 34 East,
 40.00 Set temporary $\frac{1}{4}$ section post
 corner,
 7865 Intersect West Town line
 24, the South of Post,
 from which Town,
 S 89° 50' East on true line
 3865 Set $\frac{1}{4}$ section Post, Drive
 hurred Stake, dug pit
 and raised ground as per
 instructions,
 7865 To post, corner

Township 6 N Range 34 E Will, Mer,
 Land rolling grass
 good soil 2nd date

North between sections
 29430 Township 6 N R 34 E,
 Variation 21° E

40.00 Set 1/4 section post corner

Drove charred stake dug
 pits and raised mound as
 per instructions,

80.00 Set a post corner for sections

19.20, 29430. Drove charred
 stake dug pits and raised
 mound as per instructions
 Land rolling, good
 grass, soil 2nd date,

East on random
 between sections 20799

Township 6 N R 34 E,

40.00 Set 1/4 section post corner

Township 6 N Range 34 E Williston,
North Dakota,

7981 Intersect W 43 Line 15 lbs
South of post, from which
Drove S 85° 54' West on true line

3990 Set 1/4 Section post, corner
Drove charred stake,
Aug 1911 and raised
monument as per instructions

7981 For Post corner
Land selling grass
good soil 2nd date,

West on tunnel between
sections 19 & 30 T. 6 N, R. 34 East,

2950 Road course N, E, & S, W,

4000 Set temporary 1/4 section post.

7871 Intersect West Town line
17 lbs South of post,
from which Drove
S. 89° 52' West, on true line

3871 Set 1/4 Section post corner

Township 6 N Range 34 E Mill, Mer,
 Drove charred stake dug
 pit and raised mound
 as per instructions,
 7871 To Post, cor,
 Land rolling
 Grad given Soil 9th note,

April 23rd, 1865,

North between sections 19 & 20
 Township 6 N, Range 34 East,
 Variation 21° East,

27,50 Road course S, W, N, E,
 40,00 Set 4 section post corner
 Drove charred stake,
 dug pit and raised
 mound as per instructions
 72,50 Gait course S 9 W,
 8000 Set a post corner for sec
 17, 18, 19 & 20, Drove charred
 stake dug pit and
 raised mound as per
 instructions,

Township 6 N Range 34 E Will, Mer,
 Land gently rolling
 Good grass Soil 2nd Rate,

East on sundown between
 sections 17470 T. 6 N, R. 34 East
 4000 Set temporary $\frac{1}{4}$ section post
 80,45 Intersect N 78 line 37th
 South of Post from which
 I run $S 85^{\circ} 44' W$ on true line
 80,22 Set $\frac{1}{4}$ section post corner
 Drove charred stake, dug
 pits and raised mound
 as per instructions
 80,45 To Post corner,
 Land gently rolling
 Good grass, Soil 2nd Rate,

West on sundown between
 sections 18419 T. 6 N, R. 34 E,
 27,80 Trail cross. Nearly E & W
 4000 Set temporary $\frac{1}{4}$ section post,

72

68

68

Township 6 N, R. 34 E, Will, Minn

78.91 Intersect West Town line

43 Ahs south of Post, from
which A run 3

889°42' East on town line

38.91 Set 4 section posts,
Drove charred stake, dug
pit and raised mound
as per instructions,

78.91 To Post corner,
Level gently rolling
Good grass, Soil
2nd rate

Township 6 N, Range 34 E Will, ellis,

North between sections 17 & 18

Township 6 N, R, 34 E,

Cor 21° E

40.00 Set 4 section post corner

Drove charred stake,

dug pit, and raised

mound as per instructions

53.12 To State boundary line

9.54 chs West of 18th Mile

Post,

Set post corner for

sections 17 & 18 Drove

charred stake dug pits

and raised mound as

per instructions,

Land & entry rolling

gas good Cor 21°

Ratey

General Remarks,

This Township embraces some of the best lands in Walla Walla Valley, what is known as the Hudson's Bay Farm is in the Northern portion of the Township. This farm is very valuable for the hay that it produces, there are several other valuable places along Dry Creek, above the junction of Pine Creek also some good land on Pine Creek,

All the lands not adapted to cultivation are valuable for pasturage,

The surveys were executed by Deputy William S. Lewis
 Assisted by Cyrus Dixon
 J. L. Wallace } Chasmen
 Robert Cook Axeman

I William S Lewis, do hereby
certify that the foregoing are the
true and original field notes
of the subdivisional lines of
Township No 6 North Range
34 East of Willamette Meridian
as made under Contract No 110,
bearing date February 7th
1865,

William S Lewis
Deputy Surveyor

Page 13

Surveyor General's Office
Eugene City, Aug. 23^d 1865

The foregoing field notes of the Survey of Sub-divisional lines of Township 6 North, Range 34 East, Willamette Meridian, Oregon, executed by Odell & Lewis, Deputy Surveyors, under their contract No. 110 dated July 7th 1865, having been critically examined, the necessary explanations and corrections made, the said field notes and the surveys they describe are hereby approved.

E. L. Applegate
Surveyor General of Oregon