

54 ~~394~~

494
Index

To Exterior lines of Township N^o 5 N, R^o 34 E.

See Page 67

71	72	73	73	74	75	
6	5	4	3	2	1	70
						12 69
						13 69
						24 68
						25 67
						36 67

Thursday March 23rd 1865

Commenced the survey of the Exterior
Lines of Township No 5 North of Base
Line in Range 35 East of Willamette
Meridian, At the South East Cor,
North between Ranges 35 & 36 on East
boundary of section 36, in
Township 5 North

Variation 20° E

2800 A Settlers house bears East about 2400

4000 Set post corner for 1/4 section on
side hill facing the East,
dug pits, drove charred
stake, and raised earth mound
as per instructions,

7300 A Wagon Road Course N. W.

8000 Set post corner for sec 25 & 36. 30 & 31,
on hill side facing the East,
drove charred stake, dug pits
and raised mound as per
instructions. This line passes
along hill side sloping to the East
Good Grass Soil good Good Water

Township No 5 North Range 35 East of Will, Mex.

1912, 647. Land gently slopes to the N.E.

Drove Charred Stake, dug pits, and raised Mound as per instructions.

This line passes up rocky hill on the South half, the North half over gently rolling ground good grass soil Good 2nd rate,

North, between ~~between~~ Ranges 35 & 36
Township No 5 North, on east boundary
of section 1.

Variation 21° East

40.00 Set post corner for 1/4 section
on level Drove charred, stake, dug
pits, and raised Mound as per
instructions.

80.00 Set post corner for Township No 5 N. 6
North, in Ranges 35 & 36 East and
Sections 1, 6, 31, & 36.

50

Drove charred stake, dug pits,
and raised Mound as per instructions
This line passes down gently.

60 ~~400~~ 500

Township No. 5 North Range 35 East Will. Mex.
descending grounds good grass
Soil good 2nd Rate.

West on North boundary of sec
1 in Random Township 5 N
Range 35 East

Variation 21 East,

March 25th 1865,

35.50 Wagon Road Course N, E,

37.50 Enter Creek bottom 90

40.00 Set post corner for 1/4 Section
Drove Charred Stake, and
raised Stone Mound as per
instructions

43.25 Creek 75 lbs wide course North

51.60 do, 50 do, do, do, do,

65.50 Road course North,

80.00 Set temporary post corner
for sec. 1 & 2. 35 & 36

Level level, Soil 2nd Rate
on East half, on West rocky.

Township No. 5 N. Range 35 E, Will. Mer,
March 27th 1865

West on North boundary of sec,
2 on Random,
Bar, 21° East

- 4.40 Creek 25 lbs wide course North
- 9.00 do, 20 do, do, do, do,
- 17.25 do, do, do, do, do, do,
- 40.00 Set Temporary 1/4 Sec post on level
- 80.00 Set temporary post corner for
sec 2 & 3. 34 & 35

Land level, Soil 1st Rate
between the Creeks, west
gravelly. but Good Grass

March 28th 1865
West on Random on North bound-
ary of sec 3. T. 5 N, R, 35 E.
Bar, 21° East

- 7.60 Road course North West
- 40.00 Set Temporary 1/4 Sec post.
- 80.00 Set temporary sec. corner post
- Land level Good Grass.
- Soil 2nd Rate

62 ~~902~~ 502

Township, N^o 5 N. Range 35 E, Will Mer,
March 29th 1865,

West on Boundary on North to
boundary of sec 4 T5N, R, 35 E,
Var. 21° East

25.00	Foot of hill	
30.00	Summit of hill	60
40.00	Set temporary 1/4 Sec post	
74.35	Road Course N, W,	
80.00	Set temporary sec. cor. post	
	for secs 4 & 5. 3373 4 ²	40
	Land Rolling good	
	Gross Soil 2 ^d Rate	

West on ^{North} ~~South~~ boundary of
Sec 5, T5N, R35 E -
Var 21° East,

31.00	Dry Creek 20 lks course N, W,	20
34.00	do, do, do, do, do, S, W,	
40.00	Set temporary 1/4 Sec post	
44.75	Same Creek Course N, W,	
60.00	Set temporary post cor,	
	for secs 5 & 6. 31732.	

Township No. 5 N. Range 35 E, Will. Mer,

The land on this line is
broken good grass soil good
2nd Rate.

West on Random on North
boundary of sec. 6 T. 5 N. R. 35 E,
Bar, 21° East,

40.00 Set temporary 1/4 sec post,
78.67 Intersect North & South line
97 lbs South of post,
Land gently rolling
Good Grass Soil 2nd Rate

East on true line on North
boundary of Township No. 5 N
Range 35, between Sec 3 & 6,
Course S 89° 43' E,
Bar, 21° East,

38.67 Move temporary 1/4 sec post
86 lbs North Drove charred
Stake dug pit and raised
Mound as per instructions

Township N. 5th Range 35th Will, Mer,
 78.67 Set post corner for secs 546
 31432. Drove Charred Stake,
 dug pit, and raised
 Mound as per instructions

S 89° 43' E, on North boundary
 of sec 5 T. 5 N. R. 35 E

40.00 Set 1/4 Sec post Drove Charred
 Stake, dug pit, and raised
 Mound as per instructions

80.00 Set post corner for secs
 445, 32433, Drove Charred
 Stake, dug pit, and raised
 Mound as per instructions

S 89° 43' E on North boundary
 of sec, 4 T. 5 N. R. 35 E,

40.00 Set 1/4 Sec post, dug pit
 Drove Charred Stake
 and raised Mound as
 per instructions

80.00 Set post corner for secs

Township 5 N, Range 35 E, Will, Mer,
 3 & 4. 33 & 34. Drove Charred Stake,
 Aug pits, and raised
 Mound as per instructions.

S 89° 43' E on North boundary
 of Sec 3 & 5 N, R 35 E,

4000 Set 1/4 Sec cor. post, Drove Charred
 Stake, Aug pits and Made
 Mound as per instructions,

8000 Set post Corner for Secs 2 & 3. 34
 & 35, Drove Charred Stake, Aug
 pits and Made Mound
 as per instructions,

S 89° 43' E, on North boundary of
 Section 2, T 5 N, R 35 E -

4000 Set 1/4 Sec post and Made
 Stone Mound with Charred
 Stake as per instructions,

8000 Set post Corner for Secs 1 & 2.
 35 & 36 from which a
 Cotton Wood in dia, bears S 59° 30' E 58 lbs

66 ~~406~~
 Township 5 N. R. 35 E. Will Mer,
 A Cotton Wood 5 in. dia, bears N 76° 30' E 41 lks
 do, do, do, 12 do, do, do, S 2° 30' W, 5-8 do,
 Made Stone Mound no Tree near
 in sec 2,
 April 10th 1865

For general remarks
 See general remarks after
 the field notes of subdivisional
 lines for T. 5 N. R. 35 E.
 Book No Page

The surveys of the lines
 of which the foregoing are
 the field notes were made
 by Deputy W. H. Colwell
 assisted by

Cyrus Dixon } Chainmen
 H. C. Wallace }
 Robert Axeman

To 419 510

Township No. 5 N, R. 34 E, Will. Mer,
677. Dug pits drove charred
Stake, and raised mound as per
instructions,

Land hill grass poor Soil
3rd Rate,

North between Ranges 34 & 35 on
East boundary of Sec, 1 S 5 N
Cor, 2nd East,

40.00 Set 1/4 Sec post corner

20

Drove Charred Stake, dug
pits, and raised Mound as
per instructions

80.00 Set post Corner for Towns,

60

5 & 6 N in Ranges 34 & 35 E
on Secs 1. & 31 & 36. Land

Slopes to the North

Drove Charred Stake, dug
pits, and raised Mound
as per instructions,

Land hill fair grass
Soil 3rd Rate,

Surveyor General's Office
Eugene City Aug 23 1865

The foregoing field notes of the Survey of the ~~the~~
~~Standard Quarter North, through Ranges 31,~~
~~32, 33, 34, 35, 36 & 37 East Will. Mer. Oregon,~~
~~and of the exterior lines of Tps. 5 North Ranges~~
33, 34, 35 East Willamette Meridian, Oregon,
executed by Odell & Lewis, Deputies, under con-
tract No. 110, bearing date February 7th 1865,
having been critically examined, the necessary ex-
planations and corrections made, the said field
notes and the surveys they describe, are hereby approved.

E. L. Applegate
Surveyor General of Oregon.