

1 5

Field Notes of the Sub-divisional
Lines for Townships 6 North of
Ranges 33, 34 & 35 East of Willamette
Meridian, work under contract
No. 110, bearing date, February
7th 1865.

Index

Township 6 North Range 35 East.

18	38	17	20	16	15	14	13
37		37		29	23	17	11
19	36	20	21	22	23	24	
35		34		28	21	15	10
30	34	29	28	27	26	25	
33		32	26	20	14	7	
31	31	32	33	34	35	36	

Commenced the survey
of the subdivisioral lines
of Township N. B., North of
Base Line of Range 35 East
of Willamette Meridian
March 25th 1865.

North between sections 35 & 36

Base 2^d East

40.00 Set 4 Section post, on level,
Drove churred Stake & dug
pit, and raised mound
of stone as per instructions

80.00 Set post corner for sections
25, 26, 35 & 36, on level, drove
churred stake & raised
mound of stones as per
instructions.

Level level soil quite
gravelly"

East on Bandover between
sections 25 & 36, 35 & 36, 35 & 36,

28.00 Road course N

8. 4

Township No 6 N, R 35 E, Will, Mer,
30.10 Creek 40 lbs wide course N,
40.00 Set temporary $\frac{1}{4}$ Sec, post
42.30 Creek 20 lbs wide course N,
45.40 Enter Mr Lovel's field,

course of fence N

79.25 Leave field

80.05 Intersect East Town
line 22 lbs N of post
corner from which
I run N $89^{\circ} 41'$ West on
true line

40.12 Set $\frac{1}{4}$ Section post corner
Drove charred stake and
raised mound of
stone as per instructions

80.05 To post corner,
Land level, soil
in field $\frac{1}{2}$ fut balance
Stony some Cotton
wood Alder & Birch
Timber along the
stream, but of small
growth,

5 9

Township No. 6 N, R. 35 E, T11, Mer,

North between sections 25 & 26,
T6 N, R, 35 E,
Bar 21° East,

32.20 Enter field course of fence N, W,

40.00 Set 4 Section post corner
Drove charred stake dug pits
and raised mound as
per instructions,

49.00 Cross partition fence course, E,

79.00 Spring branch 10th wide course, E,

54.00 Set post corner for sections

23, 24, 25 & 26, Drove charred
stake dug pits & raised
mound as per instructions

Land level soil $\frac{1}{2}$ rate
Some Willow and Alder
along spring branch

10

6

Township No 6 N, R 35 E, Will, Wis,

East on Random between
Sections 24 & 25, T 6 N, R 35 E,

~~7.9.77~~ Spring branch course N, E

40.111 Set $\frac{1}{4}$ Section post temporary

45.00 ^{Corner} Road ^{Corner}

62.50 Cracks 60 ft wide Course N.

79.78 Intersect East Town line

52 ft North of post
from which Iron
N 89° 38' West on true line

39.89 Set $\frac{1}{4}$ section post corner

Drove Charred Stake

dug pits and raised

mound as per instructions

79.98 To Post corner

Land level, some

timber along the

bank of stream,

consisting of Cottonwood

Alder & Birch, Willow

under growth, Soil $\frac{1}{2}$ "

Rate,

7 11

Township 6 N, R, 35 E, Will, Wis,

North between sections ³24 & ⁴25,
Township 6 N, R, 35 E,
Bar 21° East,

40.00 Set 4 Section post corner.

Drove charred stake, dug pits
and raised mound as per
instructions.

55.00 Creek 15 lbs wide course N, W,

62.00 Summit of bank

15

80.00 Set post corner for sections

13, 14, 23 & 24. Drove charred stake
dug pits and raised mound as
per instructions.

Land level to bank Soil
1st rate on bank, 3rd rate,

East on random between Secs
13 & 24, T, 6 N, R, 35 E.

40.00 Set temporary 4 Section post.

47.00 Decend bank

15

53.00 Creek 40 lbs wide course N,

55.00 " 25 " " " "

12

8

- Township 6 N, R, 35 East Will, Mer,
- 57.00 Leave Creek bottom,
- 79.91 Intersect East Town line
21 Lks N of post corner,
from which I run
N 89° 51' West on true line
- 39.95 Set $\frac{1}{4}$ section post corner
Drove charred stake; dug pits,
and raised mound as per
instructions.
- 79.91 To Post corner,
Sand rolling soil on
bank of creek hardly 2nd
rate, along creek 1st rate,
-

North between sections 13 & 14,
Township 6 N, R, 35 E,
Bar 21° E,

- 40.00 Set $\frac{1}{4}$ Section post corner
Drove charred stake dug
pits, and raised mound
as per instructions,
- 40.00 Spring branch course N, W,

Township 6 N, R, 35 E, Will, Mer,
 53.50 Intersect Northern State Line
 17.30 West of post on said
 Line marked 28 M,
 Set post corner for fractional
 sections 13 & 14, Drove charred
 stake dug pits and raised
 mound as instructions
 Land rolling soil 2nd rate,

North between sections 34 & 35.

Township 6 N, R, 35 East,

variation 20° East,

40.00 Set 1/4 section post corner, Drove
 charred stake dug pits and
 raised mound as per instructions

80.00 Set a post corner for sections
 26. 27. 34 & 35 Drove charred stake,
 and raised Mound of Stone as
 per instructions,
 Land level and quite stony
 good grass,

40.00

80.00

14

Township No 6 N, R, 35 E, Will, Mer,

East on random between sections

26 & 35 To N, R, 35 East,

20.00 Creek 20 lks wide course N, ~~W~~

39.00 do, do, do, do, do, do, do,

40.00 Set temporary $\frac{1}{4}$ section corner,

58.40 Creek 30 lks wide ~~west~~ course N,

79.87 Intersect N & S line 20 lks

North of post, from which I run
N 89° 51' W on true line,

39.93 Set $\frac{1}{4}$ section post, Drove charred

Stake and raised mound as

per instructions,

79.87 To post corner,

Land level, soil gravelly,

North between sections 26 & 27

Township 6 N, R, 35 E,

Bar 21 East,

34.00 Creek 15 lks wide course N, W,

40.00 Set $\frac{1}{4}$ section corner post,

Drove charred Stake dug

Township 6 N, R, 35 E, Will, Minn
 pits and raised mound as per
 and from which a ~~White~~ Alder
 bears S 36 W, 76 fks.

- 64.35 Creek 45 fks wide course N
 70.00 Same creek course East of N,
 79.10 do, do, do, West of N,
 80.00 Set ~~for~~ sections. 22, 23, 26 & 27, corner
 post, Drove charred Stake, from which
 a Red Willow 3 in Dia, bears N, 49° W, 15 fks
 do, Birch 7 do, do, do, S 66° 30' E, 52 do,
 a Cottonwood 10 do, do, do, S 57° W 30 do,

This line passes over level land
 soil 1st rate some timber along
 Creek, Cottonwood, Alder & Birch
 Willow undergrowth,

East on random between sections

23 & 27 Township 6 N, R, 35 East,

- 450 Same Creek as above course E
 650 Turns to the N, E,
 7.00 N. Florida Horse bears N 100
 80.00 Spring branch course N,
 30.00 Enter brush course N,

16

Township 6 N R 35 E, Will, Mex,
40.00 Set temporary $\frac{1}{4}$ section post,
41.87 Road course N,
46.52 Creek 40 lbs wide course N,
48.00 House bears N. 200 chs
79.50 Intersect N & S line 15 lbs

N of Post corner from which
I run N 89° 54' West on true line
39.75 Set $\frac{1}{4}$ section post, Drove charred
Stake, dry pits & raised mound
as per instructions, from which
A Willow 8 in dia bears N 81° 30' W, 58 lbs
79.50 To post corner,
Land level, Soil 1st Rate,

March 25th, 1865,

North between sections 22 & 23

Township 6 N R 35 East,

Parish 21 East,

12.00 Walla Walla river as above
Course N E,
13.15 Same Stream Course W of N,
25.00 Small creek 4 lbs wide course N, W,
36.00 House bears West 200 chs.

Township No 6 N, R 35 E. Will. Mer,

40.00 Set $\frac{1}{4}$ Section post, drove charred
Stake dug pits and raised mound
as per instruction.

80.00 Set a post corner for sections
14, 15, 22 & 23, Drove charred Stake
dug pits and raised mound as
per instructions.

Land level excepting
the last 20 chs which
passes over barren ridge

Soil ^{1st} rate Timber along
Creeks as above stated;

+
15-

East on random between
sections 14 & 23 To N, R 35 E,

20.00 House bears South, 50 lbs.

+
15-

25.70 Creek 30 lbs wide course N, W,

40.00 Set temporary $\frac{1}{4}$ section post

66.94 Creek 20 lbs wide course N,

73.50 Top of bank,

+
15-

79.70 Intersect N, & S, line 13 lbs

N of post, from which

18

14

14

Township No 6 N. R. 35 E Will, Mer,
I own

N $89^{\circ}54'$ West on true line,
39,85 Set $\frac{1}{4}$ section post, Drove
charred stake, dug pits
and raised Mound as
per instructions,
79,70 To post corner,
This line passes over
barren land the first 20, chs
then 1^{st} rate land to bank
then barren,

North between sections 14 & 15
Township 6 N, R, 35 East,
Variation 21° East,
12,00 Creek 6ths wide course N, W,
40,00 Set $\frac{1}{4}$ section post Drove
charred stake dug pits
and raised Mound as
per instructions,
53,00 Intersect State boundary

Township 6 N, R, 35 E, Will, Mer,
 17.20 West of Boundary
 Monument post Marked
 27 M,
 Set post corner for fractional
 Sections 14 & 15, Drove charred
 Stake dug pit and raised
 Mound as per instructions.
 Level Soil 2nd rate,

North between sections 33 & 34
 Township 6 N, R, 35 E,
 Variation 21° E -

40.00 Set 1/4 section post corner
 Drove charred stake dug
 pit and raised Mound
 as per instructions

57.90 Road course N, W,

8000 Set post corner for
 sections 27, 28, 33 & 34
 Drove charred stake dug
 and raised Mound of

10
 Township No 6 N, R 35 E, Will, Mex,
 Stones as per instructions
 Land level good grass
 & soil 2nd rate,

East on Brandon between
 sections 27 & 34 T 6 N, R 35 E,
 40,00 Set temporary $\frac{1}{4}$ section post,
 79,68 Intersect T & S line

20 lbs South of post,
 from which Town
 S 89° 59' West on true line
 39,84 Set $\frac{1}{4}$ section post

Drove charred stake along
 ribs & raised monument
 as per instructions
 79,68 To Post corner
 Land level soil
 gravelly,

Township R. 6 N, R. 35 E, Mill, Mur,

North between sections 27 & 28

Township 6 N, R. 35 East

Bar 21 East,

40.00 Set 4 Sections post dug pit
Drove charred stake and
raised mound as per
instructions

6375 Spring branch 4th course, N, W,

6944 Creek 15th wide course N, W,

8000 Set a post corner for sections
21, 22, 27 & 28, Drove charred
stake dug pit and
raised mound as per
instructions,

Turned level soil 2 1/4 feet,

East on bandorn between
sections 27 & 27 T. 6 N R. 35 E,

975 Road course N, W,

2120 Creek 10th wide course N,

Township 46th N, R. 35th W, Mer

29,00 Road course N, W.

30,00 Center field

40,00 Set 4 section temporary
Corner,

60,17 Creek 10th mile course N, W,

73,25 do, do, do, do, do, do,

79,00 Creek 40 " " "

79,55 Intersect N, T, S, line

10th N of post,

from which I run

N 89° 56' West on true line

89,77 Set 1/4 section post

Corner done chanced

Stake dug pit and

raised monument as per

instructions.

79,55 To Post corner,

Land level, in

field soil first date,

West 2nd date,

19

Township No 6 N, R, 35 E, T11 N, S1, 19

North between sections 21422
Township 6 N, R, 35 E,
Bar 21 East,

2350 Spring branch 4ths wide course N, W,

4000 Set 4 sections post Drive
Charred stake dug pits
and raised mound as
per instructions,

5830 Branch 4ths wide course N, W,

6040 Road course N, W,

8000 Set post corner for sections
14, 15, 21, 22. Drive Charred stake
dug pits and raised
mound as per instructions
Land Level Soil 2nd rate

March 27th 1875

Cast on panelom between
sections 15422, T6 N, R, 35 E,

640 Road course N, W,

750 Decend hill

- Township No 6 N, R, 35 E, Willmers
 15,506 Creek 10 ft wide course N, W,
 19,25 Road course N, E,
 39,90 Creek 30 ft wide course N, W,
 40,00 Set temporary 1/4 section
 post 10 ft West of true
 corner on left bank
 of Creek,
 71,50 Road course N, E,
 79,25 Intersect N & S line 60 ft
 North of post, from which
 I run N 83° 34' W on true line
 39,62 Set 1/4 section post, from
 which an Alder 6 in dia bears N 5° W 54 ft
 do, do, 5 do, do, do, S 22° 30' E, 30 ft
 79,25 To Post corner,
 Soil on the bottom lands
 1st rate on upland 2nd rate

North between sections,
 15 & 16 Township 6 N R 35 East,
 Over 21° East

- Township No 6 N. R 35 E Will. Mer,
- 950 Road course N, W,
- 18,50 Decend hill ad enter field 20
- 28,10 Creek 10ths wide course N, W,
- 40,00 Set $\frac{1}{4}$ Section post, Aug pits
and raised around as per
instructions.
- 49,00 Creek 45ths wide course N,
- 50,00 Same Creek - " W,
- 53,50 Intersect Northern State boundary
14.60, West of 26th Mile post
Set post Drove channel & the
Aug pits and raised
around as per instructions
Turned on upland
2nd Gate on bottom 1st
Gate,

- North between sections 32 & 33
- Township 6 N R 35 E
- 22,25 Trail
- 40,00 Set $\frac{1}{4}$ section post corner

Township R. 6 N, R. 35 E, Will, Minn
 Drove Churned Stake dug
 pits & raised Mounds as per
 instructions,

8000 Set $\frac{1}{4}$ section post corner
 for Secs 28, 29, 32 & 33,

Drove Churned Stake dug
 pits and raised Mound
 as per instructions

Land gently rolling
 good grass, Soil good
 2nd Late,

East on Paragon between
 sections 28 & 33, T. 6 N, R. 35 E,

4000 Set temporary $\frac{1}{4}$ Section post,

4075 Road Course N. W,

8047 Intersect N. 4 S, line 10th

South of post, from
 which I am

S 85° 56' West on true line

4023 Set $\frac{1}{4}$ section post cor,

23 27

Township 6 N, R. 35 E, Will. Mer,
Drove charred stake, dug
pits and raised pits and
mound as per instructions
80.47 To post corner
Land gently undulating
good grass soil good
2nd rate,

North between sections
28 & 29 Township 6 N, R. 35 E,
Bearing 21° East,
30.60 Road course North West,
40.00 Set $\frac{1}{4}$ Section post corner
Drove charred stake, dug
pits and raised mound
as per instructions,
64.67 Spring Branch 5 ft wide
Course N. W.
80.00 Set post corner for sections
20 21. 28 & 29, Drove
charred stake, dug pits

Township No 6 N, R 35 E, Will, Minn
 and raised mound as
 per instructions.

Land gently, rolling
 good grass. Soil 2nd Rate,

East on road between
 Section 21 & 28. To N. R. 35 E,
 40.00 Set temporary $\frac{1}{4}$ Section
 post.

64.90 Small creek 5th wide ~~at~~ course N, W,

80.15 Intersect N 48 line

40 links south of post,
 from which I run

S, 89° 43' W, on true line

40.07 Set $\frac{1}{4}$ Section post Dig

pits, Drove Charred
 Stake, and raised mound

80.15 as per instructions
 To post corner

Land rolling grass
 good soil 2nd Rate,

Township No 16 N, R, 35 E, Will, Mo,

North on west boundary of
section 21 T, 16 N, R, 35 E, Will, Mo,
Bar 21° East,

14.10 Road Course N, W,
40.00 Set 4 Section, ^{corners} Drove charred
Stake, dug pits and
raised mound as per
instructions

80.00 Set a post corner for secs
16, 17, 20 & 21, Drove charred
Stake dug pits and
raised mound as per
instructions

Land rolling grass
Good Soil 2nd note,

East on boundary between
Sections 16 & 21, T, 16 N, R, 35 E,

4.20 Small Creek 6 blocks wide course N, W,
40.00 Set temporary 4 Section post

30

26

Township R. 6 E, N. 35 E, Will, Mes,
 57,15 Spring Branch Course N, W,
 80,29 Intersected N & S Line
 60 lbs South of post
 from which I run
 $S 89^{\circ} 34' W$ on true line
 40,14 Set $\frac{1}{4}$ Section post corner
 Drove charred stake, and
 dug pits and raised
 mound as per instructions
 80,29 To Post corner,
 Land gently rolling
 Grass good Soil
 Low rate,

North between sections
 16 & 17, S. 5 N, R. 35 E,
 bar $21^{\circ} E$,

15,18 Ditch fence
 17,15 Creek 10 lbs wide course W,
 32,13 Learning field ditch fence,
 40,00 Set $\frac{1}{4}$ Section post,

Township T⁶S R³³E Will, Men
Drove charred stake dug pits
and raised mound as
per instructions,

53,10 ~~To~~ Northern Boundary of
State 13, 50 chs west of
25th Mile post,

Set post corner for
fractional sections 16417
Drove charred stake dug
pits and raised mound
as per instructions,

Land gently rolling
grass good Soil
2^d Rate.

March 28th, 1865,

North between sections

31432 T⁶N R³⁵E

10,80 Dry Creek 25th Mile course N, W, 20

40,00 Set 4 Section post corner

Drove charred stake, dug
pits, and raised mound

Township No. 6 N., R. 35 E., W. 4 Mer,
 80.00 Set a post corner for sec,
 29.30.31432, Drove Churred
 Stake, dug pits, and
 raised mound as per
 instructions,
 Land broken good
 Grass Soil 2nd rate,

East on Random between
 sections 29432, T. 6 N., R. 35 E.,
 12.22 Spring Branch course N, W,
 29.00 " " " " "
 27.00 " " " " "
 40.00 Set temporary $\frac{1}{4}$ Section
 post
 79.54 Intersect N, S, Line 50 lbs
 North of post, from which
 Run N 89° 39' W on true line
 39.77 Set $\frac{1}{4}$ Section post Corner
 Drove Churred Stake, dug
 pits and raised mound

Township 6 N. R. 35 E. Will. Mer,
 as per instructions,
 79.54 To post corner,
 Land gently rolling
 Good Grass, Soil 2nd rate

West on random between
 Sections 30 & 31, T. 6 N., R. 35 E.,
 4.00 Set temporary $\frac{1}{4}$ Section
 post,
 79.78 Intersect N 43 Line 18 ths
 South of Post, from which
 found $S 85^{\circ} 52'$ East on true line
 39.78 Set $\frac{1}{4}$ Section post corner,
 Drive churred stakes, dig
 pits and raised mound
 as per instructions.
 79.78 To post corner,
 Land gently rolling
 Soil 2nd rate,

Township No 6 N. R. 35 E, Will, Wis,

North between Sections

29 & 30, T. 6 N, R. 35 E,

Bar 21° East,

14.11 Spring Branch course N,

40.00 Set $\frac{1}{4}$ Section post. Corner,

Drove charred stake,

dug pits and raised

mound as per instructions

57.50 Spring Branch course N, W,

80.00 Set post corner for sections,

19. 20. 29 & 30, Drove charred

stake, dug pits, and raised

mound as per instructions,

Land level grass good

Soil 2nd rate,

Easton's random between

sections 20 & 29 T. 6 N, R. 35 E,

29.32 Road course W West

39.17 Road " N, W,

Township 6 N, R, 35 E, Will, Mex,
 40.00 set temporary $\frac{1}{4}$ section post,
 67.50 Spring Branch course N, W,
 79.55 Intersect N.S. Line 75 N of post,
 from which I run
 $N 89^{\circ} 28' W$ on true line
 39.77 Set $\frac{1}{4}$ section post Drive
 churred stake, dug pits and
 raised mound as per instructions
 79.55 To post corner,
 Sand gently rolling
 Soil 2nd Pulv.

West on random between
 sections 19 & 30 T6 N, R, 35 E,
 23.00 Road course N of West,
 40.00 set temporary $\frac{1}{4}$ section post,
 79.75 Intersect West Youn Line
 45 lbs N of Post, from which
 I run $N 85^{\circ} 41' E$ on true line
 39.75 Set $\frac{1}{4}$ section post Drive
 churred post dug pits

Township 6 N. R. 35 E. Will, Men,
and raised mound as per
instructions,

79.75 To post corner,
Land gently rolling
Soil 2nd Rate

North between sections 19 & 20
Township 6 N R 35 East,
Bar 21st East

40.00 Set $\frac{1}{4}$ section post corner
Drove charred stake,
dug pit and raised mound
as per instructions;

80.00 Set a post corner for sections
17-18-19 & 20. Drove charred
stake dug pit and
raised mound as per
instructions

Land gently rolling
Soil 2nd Rate,

Township No. 6 N, R. 35 E, Will. Mer,

East on Prandon between

Sections 17920, T. 6 N, R. 35 E,

40.00 Set temporary $\frac{1}{4}$ Section post

57.19 Road course N,

79.68 Intersect N 8 Line 38 Mts

N of post from which I

run N 89° 46' West on true line,

39.84 Set $\frac{1}{4}$ Section post & row

Charred stake, dug pits

and raised mound as per
instructions,

79.65 To Post corner,

Land gently & rolling
Soil 2nd Rate

West on Prandon between

Sections 18419 T. 6 N, R. 35 E,

40.00 Set temporary $\frac{1}{4}$ Section
post

65.50 Spring Branch Course W, W,

38 34

Township 6 N, R, 35 E, Will, Mer,
79.84 Intersect West Town Line

59. The North of Post,
from which Town
N 89.35 E on true line,

3984 Set $\frac{1}{4}$ Sec post Drive
Charred Stake dug pits
and raised mound as

79.84 per instructions,
To post corner.
Level level
Soil 2 $\frac{1}{2}$ rate,

March 29th 1865,

North between sections
17 & 18, T. 6 N, R, 35 E,
Cor 21st E,

40.00 Set $\frac{1}{4}$ Section post.
Drive Charred Stake,
Dug pits and raised
mound as per instruction

5200 To State Line 13.65
West of 23 $\frac{1}{2}$ mile post,
Set post corner

sections 17 & 18. Drove
churched stake, dug pits
and raised mound as
per instructions,

General Remarks.

This Township braces much
the largest portion of the valuable
lands suitable for cultivation

The Walla Walla River divides
upon entering the valley into
a great number of channels
running almost on a level with
the whole valley, thus irrigating
the lands and furnishing an
abundance of water,

The soil along the different
channels is of the 1st quality
I found it quite impracticable
to enter in the field

Note the different inclosures from
 the fact that in most places the
 streams were made to answer
 as a portion of the inclosures
 and in in other places the
 fences were either down or
 of such an indifferent character
 that they really did not deserve
 a record. The Farmers have delayed
 making anything like permanent
 improvements awaiting such
 time as will enable them to
 build their fences upon lines
 established by the surveys.

The surveys were executed
 by Deputy Williams & Cole
 assisted by J

Cyrus Dixon } Chamber
 D. C. Wallace }
 Robert Cook & Axeman

I William H. Odell, do hereby
certify that the foregoing are the true
and original field notes of
the subdivisional lines of
Township No 6 North Range
35 East of Willamette Meridian
State of Oregon, as made under
contract No 109, bearing date
February 7th 1865,

William H. Odell
Deputy Surveyor

Page 13

Surveyor General's Office

Queen City, ~~July~~ ^{Aug.} 23^d 1865

The foregoing field notes of the survey of Subdivisional lines of T. 6 North Range 35 East Willamette Meridian, Oregon, executed by Odell & Lewis, Deputy Surveyors, under their contract No. 110 dated February 7, 1865, having been critically examined, the necessary explanations and corrections made the said field notes and the surveys they describe are hereby approved

E. L. Applegate
Surveyor General.