

110

Index T. 6 N. R. 36 E.

6	5	4	3	2	1
7	8	9	10	11	12
<i>State Line</i>					
18 25	17	16	15	14	13
24	23	17	13	9	4
19	20	21	22	23	24
22	21	16	11	7	3
30	29	28	27	26	25
20	19	15	10	6	1
37	32	33	34	35	36

P. 109
blank

101

Commenced the survey of the subdivi-
sional lines of Township 6, north,
of Base Line, of Range 36,
East of Millamitte Meridian.

April 1st 1865

North between Secs 35 & 36.

Town 6, N., R. 36, East.

Var 21st East.

4000 Set $\frac{1}{4}$ Sec Post Drove charred
Stake, Dug Pit & Raised mound
as Per Instructions.

8000 Set Post corner for Secs 25, 26,
35 & 36. Drove charred stake dug pit
and raised mound as Per Instructions.
Land Rolling, grass good,
Soil 2^d Rate.

Eastern Random between Secs 25 & 36,
Town 6, N., R. 36, East.

4000 Set temporary $\frac{1}{4}$ Sec Post.

79.75 Intersect north & south Town line
29 links north of Post. from which

Township No 6, N. R. 35, East Hill, M.
I run N. 89° 48' W. on a
true line

89.75⁸⁷ Set 1/4 Sec Post Drove Charred
Stake Dry Pits & raised mounds
as per instructions. Post set
on side Hill sloping to the
east.

49.75 To Post corner.
Land Rolling grass good.
Soil 2nd Rate.

North between Secs 25 & 26,
Town 6, N. R. 36, East,
Var 21° East.

40.00 Set 1/4 Sec Post Drove Charred
Stake Drove Charred Stake
Dry Pits & raised mounds as
per instructions.

80.00 Set Post Corner for Secs 23, 24,
25 & 26, at foot of Hill sloping
to the East, Drove Charred Stake
Dry Pits & raised mounds

Township 6, N., R. 36, East Hill, Mev,
as per instructions.

Land Broken, Grass good, Soil
D. Rate,

East on Ransom between Secs 24 & 25
Town 6, N., R. 36, East

4000 set temporary 1/4 Sec Post.

80,18 Intersect north & south Town line.

28 Secs north of Post, from which
I run N. 89° 48' W. on a true
line.

40, ~~18~~⁰⁹ set 1/4 Sec Post, at foot of Hill
facing East. Wove chased
stake dry pits & raised mound
as per instructions

80,18 To Post corner,

Land Rolling, Grass good
Soil D. Rate,

4114

Township No. 6. N. R. 36. East Hill, M.

x

North between Secs 23 & 24,

Town 6. N. R. 36. East,

Var 21° East

4000 Set 1/4 Sec Post Drove

Chambers State. Dry Pit.

Raised Mound as Per Instructions

8000 Set Post corner for Secs 13, 14,

23 & 24. Drove Chambers State

Dry Pit - Raised Mound

as Per Instructions.

Land gently rolling grass

good Soil 2. Rate,

East on Random between Secs 13 & 24,

Town 6. N. R. 36. East,

Var 21° East,

4000 Set temporary 1/4 Sec Post,

79.89 Intersect ~~East~~ north & south Town line

at Post, from which down

N. on true line,

39.8⁹⁴ Set 1/4 Sec Post Drove Cham

Township No. 6, R. 3, E. Mill, W.
State, Dept of Lands & raised
income as per instructions
49.89 To Post Comm.

Land Rolling gently, grass
good. Soil 2nd Rate.

North between Secs 13 & 14
Town 6, N. R. 3, E. East,
Twp 2nd East.

4000 Sect 14 Dec Post Prove changed
State, Dept of Lands & raised income
as per instructions.

57.19 Intersect State Boundary line
16 chains & 80 links West of Post,
Mile Post No. 34. Set Post
Comm for fractional sections
13 & 14. Land Rolling grass
good. Soil 2nd Rate.

Township No. 6, N. R. 36, East, Mill. N.

North between Secs 34 & 35
 Town 6, N., R. 36, East,
 Twp 21° East,

40,00 Set 1/4 Sec Post drove chanced
 dug pits & raised mound,
 as per instructions

80,00 Set Post corner, sand
 Raising grass good,
 Soil 2nd Kate,

East on Random between Secs 24 & 35,
 Town 6, N., R. 36, East,

40,00 Set temporary 1/4 Sec Post,
 80,22 Intersect north & south, from line,
 19 north of Post, from which
 I run N. 89° 57' W. on
 true line

~~40,00~~ Set 1/4 Sec Post drove chanced
 stake dug pits & raised
 mound as per instructions,
 80,22 5th Post corner,

7
Township No. 11, R. 31 East, Mill, W.
Land Rolling, Grass good.
Soil 2^d Rate.

x

North between Secs 26 & 27,
Town 6, N. R. 31 East,
Var 2^d East.

44.00 Set 1/4 Sect Post Drive Chained
Stake, Dwy Pit, & raised mound
as Per Instructions

80.00 Set Post corner for Secs 22, 23,
26 & 27, on level, Drive Chained
Stake, Dwy Pit & raised mound
as Per Instructions.

Land gently Rolling, Grass
good, Soil 2^d Rate.

East on Randam between Secs 23 & 26,
Town 6, N. R. 36 East,

40.00 Set Temporary 1/4 Sect Post.

79.93 Intused north & south Town line
at Post, from which Drive
N. on true line.

Township No 6, N. R 36, East Mill, Mo.
 39.96 Set 1/4 Sec Post Wove Charred
 Stake, N^o 1/4 Pil - raised
 ground as per instructions

79.93 Set Post corner ~~for~~
 Land Rolling gran good,
 Soil 2 Rate.

x

Chart between Secs 22, & 23,
 Town 6, N. R 36, East,
 Variation N^o East.

40.00 Set temporary 1/4 Sec Post, on land
 Wove Charred Stake, N^o 1/4
 Pil - raised ground as per
 instructions.

80.00 Set Post corner for Secs 14, 15,
 22 & 23. Wove Charred Stake,
 N^o 1/4 Pil - raised ground as
 per instructions.
 Land gully Rolling, gran
 good Soil 2 Rate.

119

Township No 6, N, R 36, East, Mill, Mer.

April 3^o, 1865

East on Randome between Secs 14 & 23,

Town 6, N, R 36 East.

44,000 Set temp or any 1/4 sec Post.

80,19 Intersect North & South Town line.

44 Sinks North of Post from
which I ran N. 89° 43' W. on
town line

44, ~~4~~⁶⁹ Set 1/4 sec Post. Drove charred
stake, dug it & raised
mound as per instructions.

80,19 To Post Corner.

Land Rolling, grass good
Soil 2^o Rate.

x

North between Secs 14 & 15,

Town 4, N, R 36 East.

Variation N° East.

44,000 Set 1/4 sec Post Drove charred
stake

52,20 Missouri State boundary line

16 chains or 55 links West of

10 120

Township No 6, N, R 36, East, Mill, W.

0 Mile Post No 33, Set Post

Corner for fractional Secs 15 & 14,
Drove charred stake, dug pit & raised mound as per instructions,
Land Rolling, Grass good,
Soil 2nd Rate.

North between Secs 33 & 34

Town 6, N, R 36, East

Variation 21° East.

30.00 Road, course west of north.

40.00 Set 1/4 Sec Post Drove charred

stake dug pit & raised mound as
per instructions.

80.00 Set Post corner for Secs 27, 28,

33 & 34, Drove charred stake

dug pit & raised mound as

per instructions. Land Rolling

Grass good Soil 2nd Rate.

East on Random between Secs

27 & 34, Town 6, N, R 36, East,

40.00 Set Temporary 1/4 Sec Post

79.94 Distance north & south line 12 Sins

south of Post from which I

11
120

Township No. 6, N., R. 36, East, Hill, W.
run S. 89° 55' W. on true line
39.97 dug pit & raised mound as
Per Instructions

79.94 To Post Corner.

Land Rolling, grass good
Soil 2^d Rate,

North between secs 27 & 28,
Town 6, N., R. 36, E.
Var 21° East,

40.40 Set 1/4 Sec Post Prove Charred
Stake dug pit & raised mound
as Per Instructions

80.00 Set Post Corner for Secs 21, 22,
28 & 27. Drove Charred Stake dug pit
& raised Mound as Per Instructions
Land Rolling gently, grass good
Soil good 2^d Rate

East on Random between Secs
22 & 24, Town 6, N., R. 36 East.

40.00 Set Temporary 1/4 Sec Post,

12 122

Township No 6, N, R 36, East, Hill, M,
80,06 Intersect north and south line
28 links, south of Post, from
which I run S. 89° 48' W, on
a true line

41,03 Set 1/4 Sec Post Dry Pit
& raised Mound as per
Instructions.

80,06. To Post Corner, Land
gently rolling, grass good
Soil good 2^d Rate,

North between Secs 21 & 22,
Town 6, N, R 36, East,
Variation 21° East.

41,00 Set 1/4 Sec Post. Drove Charred
Post. Dry Pit & raised
Mound as per Instructions.

80,00 Set Post Corner for Secs 15, 16,
21 & 22, Drove Charred Stake Dry Pit
& raised Mound as per Instructions,
Land Rolling, grass good. Soil good
2^d Rate,

Township No 6, N, R, 36, East, Mill, W,

East on Random between Secs 15 & 22.

Town 6, N, R, 36, East,

40.00 Set temporary 1/4 Sec Post.

79.92 Intersect North & South line. South of Post 32. Link, from which I run S. 89° 46' W. on a true line.

39.96 Set 1/4 Sec Post. Drove charred stake. Dug pit & raised mound as per instructions

79.92 To Post Corner. Sand rolling grass good. Soil good 2nd Rate.

North between Secs 15 & 16.

Town No 6, N, R, 36, East,

Variation 21° East.

40.00 Set 1/4 Sec Post Drove charred stake. Dug pit & raised mound as per instructions.

52.50 Intersect State Boundary line

114

124

Township No. 11, R 31, East, Will. Co.,
 16 Chains + 15 Links West of
 Mile Post No 32, Set Post Corner
 for fractional Secs 15 + 16,
 Drove charred stake & dry pit
 & raised mound as Per Instructions,
 Saw Rolling grass good,
Soil good 2^d Rate.

North between Secs 32 + 33
 Town 11, R 31 East,
 Variation 21° East,

4000 Set 1/4 Sec Post, Drove charred
 stake & dry pit & raised mound
 as Per Instructions,

8000 Set Post Corner for Secs 28, 29,
 32 + 33, Drove charred stake
 & dry pit & raised mound as Per
 Instructions, Saw Rolling
grass good, Soil 2^d Rate.

15
125

Township 70 N, R 31 East, Mill, W.

X

April 4th 1885

East on Raudon between Secs
28 & 33, Town 1, N, R. 31, East.

40, 11 Set temporary 1/4 sec Post,

80, 28 Intersect north & south line at
Post, from which I run West,
on true line.

40, 14 Set 1/4 sec Post dry pit, drove
Charred stake, & raised mound
as per instructions

68, 00 ^{Roadway corners west of north.}
80, 28 Set Post corner. Land pretty
rolling, grass good soil 2^d.
Rate.

North between Secs 28, 29,
Town 1, N, R. 31, East,
Variation 21° East.

40, 00 Set 1/4 sec Post drove Charred
stake, dry pit & raised mound
as per instructions.

80, 00 Set Post corner for Secs 20, 21,
28 & 29, drove Charred stake

16
126

Township No 6, N, R. 31, East, Will. M.,
Dugtil, & raised mound as
per Instructions. Land
Rolling grass good, Soil
2^d Rate.

East on south Random between
Secs 21 & 28, Town 1, N, R. 31, East.

4,000 Set temporary 1/4 Sec Post.

8,000 Intersect North & South line

25 Sinks north of Post, from
which I run N. 89° 49' W.
on true line.

40,000 Set 1/4 Sec Post. One chain
Stake, Dugtil, & raised
mound as per Instructions.

~~8,000 To Post corner E~~

47,50 Road corner ^{N. of} North

8,000 To Post corner. Land gently
Rolling. Soil 2^d Rate

17
27
Township No 1, N, R 36, East, Mill, W,

North between Sec 20 & 21.

Town 1, N, R 36, East,

Var 21st East.

40.00 Set 1/4 Sec Post & one charred
Stake, Dry Pit & raised
mound as per instructions

80.00 Set Post Corner for Sec 16, 17,
20 & 21. Drove Charred Post, Dry
Pit & raised mound as per
instructions. Sand gully
Rolling grass good.
Coil 2nd Rate.

East on Random between Sec 16 & 21
Town No 1, N, R 36, East.

40.00 Set temporary 1/4 Sec Post, one
charred, Stake Dry Pit & raised
mound as 1st

79.48. Intersect north & south line
at Post, from which I run
West, on true line.

18. 128.

Township No 6. N. R. 36. E. Hill, N.
39.84 Sec 14 Sec Post. Drove charred
Stake. Dry pit & raised

marked as per instructions

42.50 Road ~~Corner~~ N. of ~~Post~~ corner. Land
79.18 10 Post corner. Land

Rolling gently. grass. good
Soil 2^d Rate.

North between Secs 16 & 17.
Town 6. N. R. 36. East.
Tav 21^o East.

41.00 Oct 1/4 Sec Post Drove charred
Stake. Dry pit & raised
marked as per instructions

53.00 Intersect State Boundary line
17 chain West of Mile Post.
No 31. Sec Post corner for
fractional Secs 16 & 17. Drove
charred stake Dry pit & raised
marked as per instructions.

Land gently Rolling grass good
Soil 2^d Rate.

Township No. 10, R. 31, E. 11, N. 19
129

North between Secs 31 & 32,
Town 10, R. 31, East.
Variation N. East.

40.00 Set 1/4 Sec Post Drove charred
Stake, Dug Pit & raised
mound as Per Instructions
8000 Set Post corner for Secs 29, 30,

31 & 32. Drove charred stake, dug
Pit & raised mound as Per
Instructions. Sand Rolling gently
grass good soil 2^d Rate.

East on Random between Secs 29 & 32,
Town No. 10, R. 31, East.

40.00 Set temporary 1/4 Sec Post.

79.78 Intersect North & South line
32 Sink North of Post from
which I run N. 89° 41' W. on
true line.

39.89 Set 1/4 Sec Post Dug Pit - Drove
charred stake, raised as Per

22. 130

Township No. 6, N. R. 36, E. Hill, M.
Instructions

79.78 To Post Corner, Sand gutt,
Rolling, grass good, Soil
2nd Rate,

Met on Random between Secs
30 & 31, Town 6, N. R. 36, E.

40.00 Set temporary $\frac{1}{4}$ Sec Post.

79.75 Intusect into South Town line
18 Links north of Post from
which I run N. $89^{\circ} 52'$ E.
on true line.

29.75 Set $\frac{1}{4}$ Sec Post drove chain
stake dry Pil; raised worm
as per Instructions.

15.25 Creek course North West.

79.75 To Post corner, Sand gutt,
Rolling, grass good, Soil
2nd Rate,

21
131

Township No. N, R. 31, East Mill, W.

X

April 5th 1885

North between Secs 29 & 30,
Town No. N; R. 31, East,
Twp 21st East.

40,000 Set 1/4 Sec Post. Drove charred
Stake, Dug Pit - raised
Mound as Per Instructions.

80,000 Set Post corner for Secs 19, 20
30 & 29, Drove charred stake,
Dug Pit - raised Mound as Per
Instructions. Sand gently
Rolling grass good. Oil
good 2nd Rate.

East on Random between Secs 20 & 29,
Town N, R 36, East.

40,000 Set temporary 1/4 Sec Post.
7990 Intersect North South line at
Post from which draw N,
on true line.

39,95 Set 1/4 Sec Post Drove charred
Stake, Dug Pit - raised Mound.

Township No. 2, R 31, East, Hill, M.
Instructions.

79,900 To Post corner, Sand
Rolling gently, grass good
Soil 2^d Rate.

West on Random between Secs.
19 & 20, Town 6, N, R 36, East,
40,000 Set temporary 1/4 sec Post.
79,85 Intersect north South Town line
22 links north of Post, from
which I run N, 89° 50' E,
on true line.

⁴⁰
39,85 Set 1/4 sec Post, Drive chains
Stake dry pit - raised mound
as Per Instructions.

7500 Creek course North West,
66,35 Road ~~course~~ North
Rail Fence, or lease field,
79,85 To Post corner, Sand
gently Rolling, grass good
Soil 2^d Rate.

23
133

Township No. 1, N, R 31, East Mill, W.

North between Secs 19 + 20,
Town 1, N, R. 31, East,
Variation 21° East.

40.11 Oct 1/4 Sec Post, Drove chanced
State Dry Pit, & Raised Mound
as Per Instruction.

80.00 Oct Post Corn for Secs 17, 18,
19 + 20, Drove chanced State
Dry Pit, & raised mound as
Per District, Land gentle
Rolling gran good soil
good L. Rate.

East on Random between Secs 17 + 20,
Town 1, N, R 31, East.

40.11 Oct temporary 1/4 Sec Post,
80.19 Intusect North & South Line 30 Sines,
South of Post, from which
I run, S. 89° 47' N, on true
line

40.09 Oct 1/4 Sec Post Dry Pit, Drove

24 134

Township N^o 1, N. R. 31, East, Hill, M.
charred stake, raised mound
as per instructions

80.19 To Post corner, Sand Rolling
gently, grass good, soil
good 2nd Rate,

Met on Random between Secs
18 & 19, Town 1, N. R. 31, East,

~~40.00~~ Set $\frac{1}{4}$ Sec Post drove charred
stake, dug pit & raised mound
as per instructions

110.00 Set temporary $\frac{1}{4}$ Sec Post,
79.94 Intersect north & south town line
at Post, from which I
run E. on town line

39.94 Set $\frac{1}{4}$ Sec Post drove charred
stake, dug pit & raised mound
as per instructions

79.94 To Post corner, Sand
Rolling gently, grass good
soil 2nd Rate,

25
135

Township No. 6, R. 36, East Will, W.

+

North between Secs 17 & 18,
Township No. 6, R. 36, East,
Variation 21° East.

40.00 Set $\frac{1}{4}$ Sec Post. Drove Chained
Stake, dug pit, & raised mound
as Per Instructions.

53.10 Intersect State Boundary line 17
chains west of Post, No 30,
Set Post Corner for fractional
Secs 17 & 18. Drove chained stake
dug pit, & raised mound as Per
Instructions. Land Rolling
grass good soil & Rate.

J. W. S. Lewis, do hereby Certify that
the foregoing are the true and
original field notes of the
Subdivisional lines of Township
6, North, Range 36, East. Made
under Contract No 110, bearing
date Feb'y 7th 1845. as will

appear from affidavits made
at the close of said contract
in due form and attached to
the field notes of ~~Township~~
^{Subdivisional}
~~Survey~~ lines of Township No. 5
N. of Range 3rd East.

William S. Lewis,
Deputy Surveyor.

137

The lands in this Township are gently rolling. The soil is good 2^d Rate quality of soil and of unusual depth. The grass is good throughout. Quite a number of Springs are found, affording plenty of good water. Claims are being taken quite rapidly. The township is almost destitute of timber, but can be readily supplied, as to all practical purposes, from the mountain lands, but a few miles distant.