

Index

To the Field Notes of the
 Exterior Lines of the
 fractional Township No 6
 N. Range 35 East Will. Mer.

6	5	4	3	2	1
---	---	---	---	---	---

12

State Line. ²⁹ ~~35~~ Miles
 13 35

24 34

25 33

36 33

March 24th 1865

655

553

Commenced the Survey of the Eastern
Line of Township 6 North Range 35, E.
North on East Boundary of Sec 36.
Town 6 North Range 35, East,
Var 21° East.

4.00 Sch 1/4 Sec Post. - 2 - 20 ft

Drove Charred Stake, Nug Pit
raised Mound as per Instructions

5.00 Wagon Road Corner North East,

57.25 on Branch Turn Sun River

15 Sinks side Corner East of
north,

8.00 Sch Post Corner for Sec 25, 36,

31, 32. Drove Charred Stake

Nug Pit - raised Mound
as per Instructions.

Land gently Rolling Soil
last Half mile 1st Rate.

North on East Boundary of Sec 25.

Town 6 North Range 35 East,

Variation 21° East,

11.57 Enter Field Corner of Fence
East of north,

Township 6, North, Range 35, East,
40,00 Set 1/4 Sec Post on a Suel.

Drove Charred Stake Way,
Pit-raised Mound as per
Instructions.

65,50 Crossed Partition Fence
Corner East West,

69,90 Another Branch of the Turn-
sum. 15 Sinks Wide
Corner East of North,

82,00 Set Post Corner for Sec.
24, 25, 13 & 19, on a Suel.

Drove Charred Stake Way,
Pit-raised Mound as
per Instructions.

Sand Suel Soil 1st Bal.

North on East Boundary of
Sec 24, Town 6 North R 35, East,
Variation 21° East,

40,00 Set 1/4 Sec Post, on Suel

Drove Charred Stake Way
Pit-raised Mound as

Township 6 North Range 35 East.
In Instructions.

51.25 Branch of Turn Sum Corner
north of West.

54.75 Same do. do.

60.50 Same the Same Corner
West of North, & Dean Field

80.00 Set Post Corner for Sec 13.

24. 1849. on Level. In Road.
Corner of Road North West
Soil 1st Rate.

North on East Boundary of Sec
13. Town 6 North Range 35 East.
Variation East 21° East.

40.00 Set 1/4 Sec Post on Level
Hole Charred Post dug
Pit & raised mound as per
Instructions.

53.00 Intersect State Line 16 Chains
& 22 Links West of Boundary
Post. Marked by M. on
West side 46 S. 1864 on

Township 6 north Range 35 East
 East Side Sec Post Corner
 for Fractional Secs 13 & 18,
 more charred stake, dug
 pit raised mound as per
 instructions sand level
 soil 1st Rate.

For General Remarks
 see field notes of
 subdivisional lines

The Survey of this line
 was made, as shown

by affidavits, by
 Deputy W. H. Odell assisted
 by Cyrus Dixon } Chairman
 D. C. Wallace }
 Robert Cook Axeman,

I William H. Odell do hereby certify
that the foregoing are the true and
original field notes of the exterior
lines of Township No. 6 N R 35 E;
of Will. Mer. State of Oregon,
made under contract No. 110,
with B. J. Pengra Surveyor
General, and bearing date Feb
7th 1865, in accordance with
the laws of the United States
and the instructions from
the Surveyor General, as will
appear from affidavits which
were made at close of said contract
and are attached to the field notes
for Township No. 5 N R 34 E.

William H. Odell
Deputy Surveyor.

624

Surveyor General's Office
Eugene City, Aug. 23^d 1865

The foregoing field notes of the Survey of the Exterior
lines of ~~Tps. 4 N. R. 31, 32, 33, & 4 East; and of~~
Tp 5 N. Ranges 31, 32 and 36 East; and of
Tp 6 N. Ranges 34, 35 and 36 East, Will. Mer,
Oregon, Executed by Odell and Lewis under contract
No. 110 bearing date February 7th 1865, having
been critically examined, the necessary explanations
and corrections made, the said field notes and
the surveys they describe are hereby approved.

E. L. Applegate
Surveyor General.