

Index.

To N. 12.37 E.

To N. R. 37 E.

		65	64	
13	24	25	31 1/2	63
		See	35	62
		34	39	61
		33	39	61
		32	32	60
		31	31	59

Copy all

(Run index around)

(Run index around)

5 N - 37 E Sec 6

67

Township 60 N, Range 37 East, Will, Mer,
8000 set a post corner for sections

1, 2, 3 & 36, from which

A Larch 18 in dia, bears $N 49^{\circ} W$, 8 ths

A " 18 " " " $S 53^{\circ} W$, 32 "

A " 20 " " " $S 12^{\circ} E$, 30 "

A " 20 " " " $N 54^{\circ} E$, 34 "

This line passes up steep
mountain side

Timber excellent Fir &
Larch Undergrowth same and
Green Willow and Maple,

East to South boundary of
section 36 T 6 N, Range 37 East

Orientation 21° East,

4000 Set 4 Section post corner

from which

A Fir 20 in dia, bears $S 54^{\circ} 30' E$ 20 ths

A Willow 5 " " " $N 19^{\circ} W$, 30 "

8000 Set a post corner for ~~at~~

Townships 54 & 6 N, Ranges 37 & 38 E,

Township N. Range 37 East W. Mer,
from which

- A Fir 20 in dia, bears N, 7° W, 23 lbs
- A " 20 " " " N, 18° E, 22 "
- A " 20 " " " S, 40° E, 18 "
- A " 10 " " " S, 23° W, 24 "

This line passes through
 excellent timber, Land
 gently rolling soil good
 timber Fir Larch & Pine
 Under growth some and
 maple & gum,

North on East boundary
 of sections 36, 6 N, W, 37 East,
 Variation 21° East,

4000 Made corner for section 100
 on Gum tree 2 inches
 which a Fir 20 in bears S 41° E 12 lbs
 a Gum 8 " " S, 38° W, 25 "

8000 Set a post corner for sections
 25. 36. 31 & 30 on side of Butte

Township 6 N, Range 37 East Will, Mer,
from which

- A Fir 20 in, dia. bears S. 12° E, 80 lbs
- A " 3 " " " S, 50° 30' W, 24 "
- A " 10 " " " N 24° 30' E, 50 "
- A Larch 14 " " " N, 44° W, 57 "

This line passes through
 Excellent timber Fir Larch
 Spruce & Pine, Undergrowth
 Junce & Willow & Maple
 Sailed 1st Kate,

May 27th 1865,

North on East boundary of sec
 25 Township 6 N, Range 37 East
 Bar 20° East,

400 Lease Timber
 32,00 Summit of ridge + 500
 Bar 17° East,

40,00 Set 4 Section post corner
 deposited marked stone
 and raised mound of
 stones as per instructions

66

496

Township 6 N, Range 3 E, Willabett,
8000 Mark corner on fir 4 in, Aug 180

for sections 19, 30, 24 & 25,
in thick growth of
L' timber small growth,

on steep hill side facing
the N, East, from which

A Fir 4 in Dia bears S 40° W, 6 lbs

A " 8 " " " " S 50° E, 5 "

A " 4 " " " " N 20° W, 10 "

A " 3 " " " " N 10° E, 8 "

This line passes over high
Ridge laid on the South on
the N East, some Lumber,
Course of Ridge West of
North,

I was unable to
trace this line further
by reason of a severe
Storm of Wind rain
hail and Snow
Compelling us to.

Accent to the Valley,
The distance from our
Camp and the difficulty
of getting to the work
prevented our return,

This Township
should be subdivided also
One or two tiers of sections on
the West side of Range 38 E
The lands along the
base of the Mountains are
rich and produce well
and wherever water
can be had and sufficient
level land to make a farm
settlers have taken claims
The timber is very valuable
and would command a
good price if put into
market, The settlers are
cutting the timber
and taking it away quite

~~498~~

fact, and soon the land
will be worthless unless
put into Market,

The whole of the lands
embraced in Contract
No. 10, and the Addendum
may be considered as one
extended range of pasture lands.
A very small portion, ^{of} which
may be considered barren,
Compared with the whole a
very small proportion can
be cultivated to advantage,
because of the dryness of the
seasons, otherwise rich and
productive, The Walla
Walla River is a fine
stream of cold water, well
supplied with excellent
fish, Trout & Salmon.

x

595

69
~~497~~

The Valley along the river
 is rich and very productive
 but narrow until the river
 enters the N. E. corner of
 Township 5 N, R. 35 E, and the
 hills are high and very
 steep generally,

The other streams,
 Dry Creek & Pine Creek, pass
 through deep canyons
 with narrow bottoms,

What is known as Walla
 Walla Valley lies principally
 in Washington Territory; but
 some of the best lands are
 situated in the fractional
 Townships No 6 North of Range
 34. 35 & 36 East, - here the land
 is level or gently undulating
 and the different streams
 above named afford fine opportunities
 for irrigation,


502

We hereby certify that
 we assisted William H.
 Odell and William S.
 Lewis, deputy surveyors,
 in surveying and marking
 the following lines, to wit;
 The 1st Standard Paralled North
 between Townships 4 & 5 and
 East through Ranges 31. 32,
 33. 34. 35. & 37. East of Will. Mer,
 also the subdivisioral lines
 of Townships 5 N. Ranges 33. 35 & 36,
 do, 6 N, do, 34. 35 & 36 do,
 do 4 do, do, 32 & 33 do,
 and the Extremors of Townships
 5 N Range 35. 36,
 6 do, do, 34. 35. 36 & 37 East
 4 do do 31. 33. & 35 do,
 and that said lines
 have been in all respects

To the best of our knowledge
and belief, well and
faithfully surveyed, and
the boundary monuments
planted according to the
instructions furnished by
the Surveyor General.

Cyrus Dion Chairman
Robert Beck Assessor

State of Oregon }
County of Benton } 1865 Subscribed
and sworn to before me
this 17 day of June 1865
Leoberec
Notary Public



506

602

P.
666-601
Blank



I hereby certify that I assisted
William H. Odell and William S.

Lewis deputy surveyor, in surveying
the following lines, to wit;

The ~~1st~~ Standard Parallel North
between Townships 4 & 5 North and

East through Ranges 31. 32. 33. 34.

35. & 37. East of Willamette Meridian

also the subdivisional lines

of Townships Nos 5 North Ranges 33. 35. & 36 E,

do, do, 6 do, do, 34. 35 & 36 do,

do, do, 4 do, do, 32 & 33 do,

and the Exterior of Townships

Nos 5 North Range 35 & 36, 37 East

do, 6 do, do, 34. 35. 36 & 37, do,

do, 4 do, do, 31. 33. & 35, do,

and that said lines have

been in all respects

to the best of my knowledge and
belief, well and faithfully surveyed,
and the boundary monuments
planted according to the instructions
furnished by the Surveyor General,
D. C. Wallace Chairman

State of Oregon)
County of Lane) ss.

Sworn & subscribed before me this
24th day of June 1865

Joel Mann

Notary Public

